

339



**SUBMITTAL TO THE BOARD OF SUPERVISORS  
COUNTY OF RIVERSIDE, STATE OF CALIFORNIA**

Dept. of Mental Health  
Maria Mabey / Asst. Dir. Date  
3-10-10

FORM APPROVED COUNTY COUNSEL  
BY: Cynthia M. Gunzel DATE  
3-10-10

**FROM:** Economic Development Agency

**SUBMITTAL DATE:**  
February 24, 2010

**SUBJECT:** Lease – Department of Mental Health, Cathedral City

**RECOMMENDED MOTION:** That the Board of Supervisors:

1. Approve the attached Lease and authorize the Chairman to execute the same on behalf of the County; and
2. Authorize the Auditor-Controller to adjust the Economic Development Agency's FY 2009/10 budget as set out on Schedule A.

**BACKGROUND:** (Commences on Page 2)

FISCAL PROCEDURES APPROVED  
ROBERT E. BYRD, AUDITOR-CONTROLLER  
BY: *[Signature]* 3/11/10  
SUSANA GARCIA-BOCANEGRA

*[Signature: Dan Martinez]*  
Robert Field, Assistant County Executive Office/EDA  
By Dan Martinez, EDA Managing Director

<b>FINANCIAL DATA</b>	<b>Current F.Y. Total Cost:</b>	\$ 113,409	<b>In Current Year Budget:</b>	Yes
	<b>Current F.Y. Net County Cost:</b>	\$ 2,336	<b>Budget Adjustment:</b>	Yes
	<b>Annual Net County Cost:</b>	\$ 3,574	<b>For Fiscal Year:</b>	09/10
<b>SOURCE OF FUNDS:</b> Federal 9.7%; State 14.76%; MHSA 18.23%; Grants/MOU 24.71%; 3 <sup>rd</sup> Party 0.33%; Other 30.21%; County 2.06%			<b>Positions To Be Deleted Per A-30</b>	<input type="checkbox"/>
			<b>Requires 4/5 Vote</b>	<input checked="" type="checkbox"/>

**C.E.O. RECOMMENDATION:** APPROVE  
Reviewed by *[Signature]* CIP TEAM  
Christopher Hans  
County Executive Office Signature  
BY: *[Signature]* Jennifer L. Sargent

Policy  
 Policy

Consent  
 Consent

**MINUTES OF THE BOARD OF SUPERVISORS**

On motion of Supervisor Stone, seconded by Supervisor Buster and duly carried by unanimous vote, IT WAS ORDERED that the above matter is approved as recommended.

Ayes: Buster, Tavaglione, Stone, Benoit and Ashley  
Nays: None  
Absent: None  
Date: March 23, 2010

Kecia Harper-Ihem  
Clerk of the Board  
By: *[Signature]*  
Deputy

Dep't Recomm.:  
Per Exec. Ofc.:

xc: EDA, CIP, Auditor, EO, Mental Health

Prev. Agn. Ref.: 12/02/97, 3.9;  
08/04/98, 3.10; 12/11/01, 3.17;  
09/28/04, 3.28

District: 4  
Agenda Number: 3.9

3.9

**BACKGROUND:**

The Department of Mental Health has occupied space for their Substance Abuse and Mental Health Treatment programs at 68615 Perez Road since 1998, expanding in size over the years to meet the program demands. The location continues to be well suited for client services, and the current requirement for office space with this new 5-year lease reduces the space by 7,730 square feet for the operation of the Substance Abuse program only. The tenant improvements requested include minimal floor plan revisions and various cosmetic updates throughout. The revised rent reflects the change in market conditions to adequately provide for maintenance services required in the lease.

Location: 68615A Perez Road, Suites 5, 6, & 7  
62625 Perez Road, Suites 9B & 10B  
Cathedral City, CA

Lessor: T W Investments  
c/o Capri Realty  
78-100 Main Street, Suite 205  
La Quinta, CA 92253

Size: 8,784 square feet

Term: Five (5) years.

Rent:	<u>Current</u>	<u>New</u>
	16,514 square feet	8,784 square feet
	\$ 1.01 per sq.ft.	\$ 1.32 per sq.ft. Mod. Gross
	\$ 16,540.27 per month	\$ 11,595.00 per month
	\$198,483.24 per year	\$139,140.00 per year

Savings per month, including custodial:	\$ 3,627.79
Savings per year, including custodial:	\$43,533.48

Rental Adjustments: Three (3%) percent increases at months 18, 36, and 54.

Custodial: Lessor provides and County pays \$1,317.48 per month in addition to base rent. Cost to be reviewed annually and adjusted as needed.

Utilities: County shall pay for telephone and electric services. Lessor to pay for all other utility services.

Interior/Exterior Maintenance: Provided by Lessor

(Continued)

**BACKGROUND:**

Improvements: Not-to-exceed \$116,488.00. County to pay in full upon completion.

RCIT: \$6,584.90

The attached Lease has been reviewed and approved by County Counsel as to legal form.

**FINANCIAL DATA:**

All associated costs for this Lease will be fully funded through the Department of Mental Health's budget. Mental Health has budgeted for these costs in FY 2009/10; however, the Economic Development Agency (EDA) requires a budget adjustment to its FY 2009/10 budget to cover related transactional costs with the property owner. While EDA will front the costs for this Lease with the property owner, Mental Health will reimburse EDA for all associated lease costs.

## Schedule A

Decrease Appropriations:

10000-7200400000-526700 – Rent/Lease Buildings	(\$ 10,883)
10000-7200600000-529540 - Utilities	(\$ 2,783)
10000-7200400000-572500 – Intra – Leases	\$10,883
10000-7200600000-573800 – Intra – Utilities	\$ 2,783

# Exhibit A

## Square Footage-Current & New:

### **BUDGETED AMOUNTS**

Current office:		16,514 SQFT		
Cost Per Sq. Ft:	\$	1.01		
Lease Cost per Month			\$ 16,540.27	
<b>Total Lease Cost included in Budget for FY 2009/10</b>				<b>\$ 198,483.24</b>

### **ACTUAL AMOUNTS**

Current office:		16,514 SQFT		
Approximate Cost per SQFT (July - Mar)	\$	1.01		
Proposed office:		8,784 SQFT		
Approximate Cost per SQFT (April - June)	\$	1.32		
Lease Cost per Month (July - Mar)	\$	16,540.27		
Lease Cost per Month (April - June)	\$	11,595.00		
Total Base Rent Cost (July - Mar)			\$ 148,862.43	
Total Base Rent Cost (April - June)			\$ 34,785.00	
<b>Total Base Rent Cost for FY 2009/10</b>				<b>\$ 183,647.43</b>

### **Custodial Costs**

Costs per Month (Apr - June)			\$ 1,317.48	
<b>Total Custodial Cost for FY 2009/10</b>				<b>\$ 3,952.44</b>
<b>Total ACTUAL Lease Costs for FY 2009/10</b>				<b>\$ 187,599.87</b>
<b>TOTAL LEASE COST SAVINGS FOR FY 2009/10</b>				<b>\$ (10,883.37)</b>

## Estimated Additional Costs:

### **UTILITIES**

#### **BUDGETED AMOUNTS**

Utility Cost per Square Foot	\$	0.12		
Estimated Utility Costs per Month			\$ 1,981.68	
<b>Total Estimated Utility Cost for FY 2009/10</b>				<b>\$ 23,780.16</b>

#### **ACTUAL AMOUNTS**

Utility Cost per Square Foot	\$	0.12		
Costs per Month (July - Mar)			\$ 1,981.68	\$ 17,835.12
Costs per Month (Apr - June)			\$ 1,054.08	\$ 3,162.24
<b>Total Actuals Utility Cost for FY 2009/10</b>				<b>\$ 20,997.36</b>
<b>TOTAL UTILITIES COSTS SAVINGS FOR FY 2009/10</b>				<b>\$ (2,782.80)</b>

### **Tenant Improvement Costs**

\$ 116,488

### **RCIT Costs**

\$ 6,584.90

EDA Budgeted Lease Management Fee (Based @ 3.79%)	\$	7,522.51		
EDA Actual Lease Management Fee (Based @ 3.79%)			\$ 11,524.93	
<b>TOTAL MANAGEMENT FEES</b>				<b>\$ 4,002</b>

**TOTAL LEASE COST FY 2009/10** **\$ 113,409.15**

**Total Net County Cost of 2.06%** **\$ 2,336.23**

# Exhibit B

## Mental Health Lease Cost Analysis for FY 2010/11

68615A Perez Road, Suites 5, 6, & 7 and 62625 Perez Rd. Suites 9B & 10B, Cathedral City

### Square Footage

Current office:		8,784 SQFT		
Approximate Cost per SQFT	\$	1.32		
Base Rent Cost per Month			\$	11,595.00
<b>Total Base Rent Cost for FY 2010/11</b>			<b>\$</b>	<b>139,140.00</b>

### **Custodial Costs**

Costs per Month			\$	1,317.48
<b>Total Custodial Cost for FY 2010/11</b>			<b>\$</b>	<b>15,809.76</b>
<b>Total Lease Cost for FY 2010/11</b>			<b>\$</b>	<b>154,949.76</b>

### Estimated Additional Costs:

#### **UTILITIES**

Utility Cost per Square Foot	\$	0.12		
Estimated Utility Costs per Month			\$	1,054.08
<b>Total Estimated Utility Cost for FY 2010/11</b>			<b>\$</b>	<b>12,648.96</b>

**EDA Actual Lease Management Fee (Based @ 3.79%)** **\$** **5,872.60**

**TOTAL LEASE COST FY 2010/11** **\$** **173,471.32**

**Total Net County Cost of 2.06%** **\$** **3,573.51**

**LEASE**

Department of Mental Health  
68615A Perez Road, Suites 5, 6 & 7  
68625 Perez Road, Suites 9B & 10B  
Cathedral City, California

Table of Contents

1. Parties ..... 1

2. Premises ..... 1

    2.1 Letting..... 1

    2.2 Defined ..... 1

    2.3 Common Area Defined ..... 1

    2.4 County's Rights – Common Area ..... 1

    2.5 Preparation of Premises/Acceptance ..... 2

    2.6 Condition of Premises..... 2

3. Use ..... 2

4. Term..... 2

    4.1 Commencement ..... 2

    4.2 Confirmation of Lease Information ..... 3

    4.3 Delay in Delivery of Premises ..... 3

    4.4 Holding Over..... 3

5. Rent ..... 3

    5.1 Rent..... 3

    5.2 Tenant Improvement Reimbursement..... 4

6. Options..... 4

    6.1 Option to Extend Term..... 4

    6.2 Right to Extend Lease Term ..... 4

    6.3 County's Right to Early Termination..... 4

7. Compliance ..... 5

    7.1 Compliance..... 5

    7.2 Americans With Disabilities..... 5

    7.3 Asbestos and Lead Based Paint ..... 5

    7.4 Hazardous Substance..... 5

    7.5 Sick Building Syndrome ..... 6

    7.6 Waste Water..... 6

8. Custodial Services..... 7

    8.1 Custodial Services ..... 7

    8.2 County's Right to Provide Custodial Services and Deduct Costs ..... 7

9. Utilities ..... 7

10. Repairs and Maintenance..... 8

    10.1 Lessor's Repair and Maintenance Obligations ..... 8

    10.2 Lessor's Default ..... 8

    10.3 County's Right to Make Repairs and Deduct Cost ..... 8

    10.4 Emergency Repairs ..... 9

    10.5 Periodic Services ..... 10

11. Alterations and Additions..... 10

    11.1 Improvements by Lessor..... 10

    11.2 Improvements by County ..... 11

    11.3 Communications Equipment ..... 11

12. Indemnification and Insurance..... 11

    12.1 Indemnification and Hold Harmless..... 11

	12.2	Insurance.....	12
13.		Damage and Destruction.....	14
	13.1	Repair of Damage.....	14
	13.2	Repair Period Notice.....	15
	13.3	Lessor's Option to Terminate or Repair .....	15
	13.4	County's Option to Terminate .....	15
	13.5	Rent Abatement Due to Casualty.....	15
	13.6	Damage Near End of Term.....	15
	13.7	Effective Date of Termination; Rent Apportionment .....	16
	13.8	Waiver of Statutory Provisions .....	16
	13.9	Release on Termination.....	16
14.		Eminent Domain.....	16
	14.1	Total Condemnation .....	16
	14.2	Partial Condemnation .....	16
	14.3	Award .....	17
	14.4	Temporary Condemnation .....	17
15.		Estoppel Certificates .....	17
16.		Subordination, Non-Disturbance and Attornment .....	17
	16.1	Subordination, Non-Disturbance and Attornment Agreement.....	17
	16.2	Subordination .....	17
	16.3	Attornment.....	18
17.		Breach by Lessor .....	18
	17.1	Lessor's Default.....	18
	17.2	County's Right to Cure Lessor's Default and Deduct Cost .....	18
	17.3	Rent Setoff.....	18
18.		Lessor's Representations and Warranties .....	18
	18.1	Title.....	18
	18.2	Certificate of Authority.....	18
	18.3	No Litigation.....	19
	18.4	Easements.....	19
19.		Miscellaneous .....	19
	19.1	Quiet Enjoyment .....	19
	19.2	Non Waiver.....	19
	19.3	Binding on Successors .....	19
	19.4	Severability .....	19
	19.5	Venue .....	20
	19.6	Attorney's Fees.....	20
	19.7	County's Representative .....	20
	19.8	Agent for Service of Process.....	20
	19.9	Entire Lease .....	20
	19.10	Interpretation .....	20
	19.11	Time of Essence .....	21
	19.12	Recording .....	21
	19.13	Consent .....	21
	19.14	Title.....	21
	19.15	Conveyance by Lessor .....	21
	19.16	Mechanic's Liens .....	21
	19.17	Surrender.....	21
	19.18	Notice .....	21
	19.19	Authority .....	22
	19.20	Approval of Supervisors.....	23



**EXHIBITS**

The following exhibits are attached hereto and made a part of this Lease:

Site Plan.....	Exhibit A
Leasehold Improvement Agreement.....	Exhibit B
Asbestos.....	Exhibit C
Confirmation of Lease Information.....	Exhibit D
Custodial Services Agreement.....	Exhibit E
General Construction Specifications for Leased Facilities.....	Exhibit F
Estoppel Certificate.....	Exhibit G
Subordination, Non-Disturbance & Attornment Agreement.....	Exhibit H

1 LEASE  
2 COUNTY OF RIVERSIDE  
3 Department of Mental Health  
4 68615 Perez Road, Suites 5, 6 & 7  
5 68625 Perez Road, Suites 9B & 10B  
6 Cathedral City, California

7 **1. Parties.**

8 **1.1** This Lease ("Lease") is made by and between the **COUNTY OF RIVERSIDE**, hereinafter referred to as "County" and **TERRY WILLIAM IRELAND dba T W INVESTMENTS**, hereinafter referred to as "Lessor". County and Lessor are hereinafter collectively referred to as the "Parties" or individually as a "Party".

9 **2. Premises.**

10 **2.1 Letting.** Lessor hereby leases to County, and County hereby leases from Lessor, the Premises, for the term, at the rental, and upon all terms, covenants and conditions set forth in this Lease.

11 **2.2 Defined.** The Premises shall consist of that certain portion of the Project, as defined herein, including all improvements therein or to be provided by Lessor under the terms of this Lease, and commonly known as 68615-A Perez Road, Suites 5, 6 & 7 and 68625 Perez Road, Suites 9B & 10B, located in the City of Cathedral City, County of Riverside, State of California, also identified as Assessor Parcel Number 687-330-024 and 687-330-023 respectively and generally described as office space consisting of approximately eight thousand seven hundred eighty four (8,784) square feet with twenty-four (24) unreserved parking spaces, all as shown on the site plan attached as Exhibit "A". It is understood that the Premises include all appurtenances and easements thereto and the non-exclusive right of ingress and egress at all times to and from the public streets and highways for County, its employees and invitees. The Premises, the building, the Common Areas, the land upon which they are located, along with all other buildings and improvements thereon, are herein collectively referred to as the "Project".

18 **2.3 Common Areas Defined.** The term "Common Areas" is defined as all areas and facilities outside the Premises and within the exterior boundary line of the Project and interior utility raceways and installations within the Premises that are provided by and designated by the Lessor from time to time for the general non-exclusive use of Lessor, County, and other tenants of the Project and their respective employees, suppliers, shippers, customers, contractors, and invitees, including, but not limited to, common restrooms, parking areas, loading and unloading zones, trash areas, roadways, walkways, driveways, and landscaped areas.

22 **2.4 County's Rights-Common Areas.** Lessor grants to County, for the benefit of the County and its employees, suppliers, shippers, customers, contractors, and invitees, during the term of this Lease, the non-exclusive right to use, in common with others entitled to such use, the Common Areas as same may from time to time exist. Lessor shall have the right to promulgate rules and regulations for the management, safety, care, and cleanliness of the Common Areas provided, however, that said rules and regulations shall be

1 subject to the approval of County. County's prior approval shall be required for any changes to  
2 the Common Areas which adversely affect County's use and occupancy of the Premises, the  
parking, or accessibility of the Premises.

3 **2.5 Preparation of Premises/Acceptance.** The rights and obligations of  
4 the Parties regarding the construction of the Premises before the commencement of the Lease  
Term are stated in the attached Leasehold Improvement Agreement, Exhibit "B". If this Lease  
5 conflicts with the Leasehold Improvement Agreement, the Leasehold Improvement Agreement  
shall prevail.

6 **2.6 Condition of Premises.** Lessor shall deliver the Premises to County  
7 in a fully clean and safe condition, free of hazards and debris, entirely permitted and inspected  
by local authorities, on the Commencement Date, and Lessor warrants for the term of this  
8 Lease, that all systems and equipment, including, but not limited to, electrical, plumbing, fire  
sprinkler, fire suppression system, fire/life/safety system, elevators, security systems, lighting,  
9 heating, ventilating and air conditioning systems ("HVAC"), loading doors, if any, that serve the  
Premises and all other such elements in the Premises (herein defined as the "Base Building  
10 Systems"), other than those installed or constructed by County, shall be in safe, hazard free,  
good operating condition, and, the roof, bearing walls and foundation of the Premises shall be  
free of material defect.

11 **3. Use.**

12 **3.1** County shall use and occupy the Premises for the purpose of  
13 providing office space for use by the Department of Mental Health, but the Premises may be  
used for any official business of County government or any other legal use which is reasonably  
14 comparable thereto. Nothing contained in this Lease shall be construed to require County to  
occupy the Premises continuously.

15 **4. Term.**

16 **4.1 Commencement.** This Lease shall be effective upon the date of its  
17 full execution by the Parties hereto. The Term of this Lease shall be for a period of sixty (60)  
months ("Original Term") commencing (Commencement Date) on the earlier of (a) the date  
18 County occupies the Premises, or (b) the date on which County accepts the Premises for  
occupancy, which shall occur only after Lessor delivers to County a copy of the Certificate of  
19 Occupancy executed by the appropriate governing authority, if applicable, and provided that  
County, in its' sole discretion, is satisfied that all leasehold improvements have been  
20 completed in accordance with Exhibit "B" and Exhibit "F", excepting minor punch list items.  
The Original Term shall expire at midnight on the last day of the sixty (60) month term  
21 ("Expiration Date"). County currently leases a portion of the premises under terms of a month-  
to-month tenancy upon the terms and conditions of a prior lease. Said prior lease shall  
22 terminate upon the commencement of this new Lease.

23 **4.2 Confirmation of Lease Information.** At such time as the  
Commencement Date of this Lease has been determined, either Party may deliver to the other  
24 Party a notice in the form set forth in the attached Exhibit "D", which the receiving Party shall  
execute, after making any corrections necessary to conform the information to the provisions  
25 of this Lease, and return to the forwarding Party within thirty (30) days after receipt. Either

1 Party will use reasonable efforts to deliver the notice to the other Party within thirty (30) days  
2 after the Lease Commencement Date. Anything to the contrary notwithstanding, failure to  
forward or execute said notice shall not invalidate or nullify the provisions of this Lease.

3 **4.3 Delay in Delivery of Premises.** Lessor shall submit plans to the  
4 building department within thirty (30) days of execution of the Lease Agreement by County or  
County may cancel the Lease. Lessor shall be in receipt of a building permit within forty-five  
5 (45) days from the date of submittal to the building department or County may cancel the  
Lease. If the Original Term of the Lease has not commenced within ninety (90) days from  
6 Lessor's receipt of a building permit, County may, at its sole option, either: (a) deduct from any  
rents that may become due hereunder the sum of Four Hundred Thirty Dollars (\$430.00) for  
7 each day the Premises are not substantially complete and available for occupancy as per  
Paragraph 2.6, after said date, as liquidated damages for failure to provide occupancy in a  
8 timely manner, or (b) cancel this Lease, and Lessor hereby waives any and all rights that it  
may have against County for any costs, expenses and/or charges that Lessor may have  
incurred as a result of preparing the Premises for occupancy.

9 **4.4 Holding Over.** Any holding over by County after the expiration of said  
10 term or any extension thereof shall be deemed a month to month tenancy upon the same  
terms and conditions of this Lease.

11 **5. Rent.** The anniversary dates shall be deemed to fall on the first day of the first  
12 full month of each lease year following commencement of the Lease term.

13 **5.1 Rent.** County shall pay to Lessor as base rent for the Leased  
14 Premises, during the term of this Lease as indicated below:

<u>Amount</u>	<u>Month</u>
\$11,595.00	1-17
\$11,942.85	18-35
\$12,301.14	36-53
\$12,670.17	54-60

15  
16  
17 Said monthly sums shall be payable, in advance, on the first day of the month or as soon  
18 thereafter as a warrant can be issued in the normal course of County's business; provided,  
19 however, in the event rent for any period during the term hereof which is not less than one (1)  
full calendar month, said rent shall be pro-rated based upon the actual number of days of said  
20 month.

In addition to the "base rent" County shall pay the following amounts on a monthly basis:

21 **5.1.1.** Costs of Custodial Services in the amount of \$1,317.48  
22 as outlined in Section 8.1.1 of this Lease Agreement.

23 **5.2** Beginning the first month after execution of the lease by all parties the  
24 County's rent for the space currently occupied, 68625 Perez units 9AB & 10B and 68615-A  
units 1 – 7, shall be \$11,595.00 per month, plus "Costs of Custodial Services" per Paragraph  
25 5.1.1 above.

1                   **5.3 Tenant Improvement Reimbursement.** Notwithstanding the  
2 provisions of Section 5.1 and 5.2 above, County shall pay to Lessor a one-time payment not to  
3 exceed \$91,488.00, plus any utilized County contingency of Twenty Five Thousand Dollars  
4 (\$25,000.00), upon completion and acceptance of the improvements by County, as provided in  
5 Exhibit "B", Leasehold Improvement Agreement, attached to the Lease.

6                   **6. Options.**

7                   **6.1 Option to Extend Term.** Lessor grants to County one (1) option to  
8 extend the Lease term ("Extension Option"). Extension Option shall be for a period of three (3)  
9 years ("Extended Term"), subject to the conditions described in this Section 6.1.

10                   **6.1.1 Exercise of Option.** The Extension Option shall be exercised  
11 by County delivering to Lessor written notice thereof no later than ninety (90) days prior to the  
12 expiration of the Original Term or any extension thereof.

13                   **6.1.2 Option Rent.** The rent payable by County during the Extended  
14 Term shall be increased three percent (3%) from the previous month's rent and shall be  
15 increased three percent (3%) at month eighteen (18) during the Extended Term.

16                   **6.1.3** All terms and conditions of this Lease with exception of Rent and  
17 Lease Term shall remain in full force and effect during the Extended Term.

18                   **6.2 County's Right to Early Termination.** The Parties hereto recognize  
19 and understand that the rental consideration hereunder originates from County, State and/or  
20 Federal sources, and therefore County shall have the right to terminate this Lease (a) if such  
21 funding is reduced or otherwise becomes unavailable, based on County's annual fiscal budget,  
22 or (b) if any law, rule or regulation precludes, prohibits or materially adversely impairs County's  
23 ability to use the Premises for the use permitted herein.

24                   **6.2.1 Notice.** County shall provide Lessor with written notification of  
25 its election to terminate this Lease at least ninety (90) days prior to the date of termination.  
County's notice shall state the reason for its termination of this Lease. County's obligation to  
pay Rent shall continue through the termination date.

**7. Compliance.**

**7.1 Compliance.** Lessor warrants that the Premises and improvements on  
the Premises shall comply with all applicable State and Federal laws, covenants or restrictions  
of record, building codes, regulations and ordinances ("Applicable Requirements") in effect on  
the Commencement Date of this Lease, regardless of the use to which County will put the  
Premises. If the Premises do not comply with said warranty, Lessor shall, promptly after  
receipt of written notice from County or any governmental agency having jurisdiction over such  
matters setting forth the nature and extent of such non-compliance, rectify the same at  
Lessor's expense. If the Applicable Requirements are hereinafter changed so as to require  
during the term of this Lease, unless same is the result of the use to which County puts the  
Premises, the construction of an addition to or an alteration of the Premises, the remediation  
of any Hazardous Substance as hereinafter defined, or the reinforcement or other physical  
modification of the Premises, Lessor shall, promptly after receipt of written notice from County

1 or any governmental agency having jurisdiction over such matters setting forth the nature and  
2 extent of such non-compliance, rectify the same at Lessor's expense.

3 **7.2 Americans With Disabilities.** Lessor warrants and represents the  
4 Premises shall be readily accessible to and usable by individuals with disabilities in  
5 compliance with Title III of the Americans with Disabilities Act of 1990 and California Title 24,  
as amended from time to time and regulations issued pursuant thereto and in effect from time  
to time. Any cost incurred to cause the Premises to comply with said Act shall be borne by  
Lessor.

6 **7.3 Asbestos and Lead Based Paint.** Lessor warrants and represents  
7 the Premises shall be constructed, operated and maintained free of hazard from asbestos and  
lead based paint, as more fully set forth in the attached Exhibit "C".

8 **7.4 Hazardous Substance.** It is the intent of the Parties to construe the  
9 term "Hazardous Substances" in its broadest sense. Hazardous Substance shall be defined  
10 as any product, substance, or waste whose presence, use, manufacture, disposal,  
11 transportation, or release, either by itself or in combination with other materials, is either: (a)  
12 potentially injurious to the public health, safety or welfare, the environment or the Premises;  
(b) regulated or monitored by any governmental authority; or (c) a basis for potential liability of  
County to any governmental agency or third party under any applicable statute or common law  
theory.

13 Lessor acknowledges that County's use may from time to time require the presence of  
14 Hazardous Substances at the Premises. County agrees that all such Hazardous Substances  
located in, at, or on the Premises shall be used, stored, handled, treated, transported, and  
disposed of in compliance with all applicable laws.

15 Lessor warrants and represents to County that Lessor has not used, discharged,  
16 dumped, spilled or stored any Hazardous Substances on or about the Premises, whether  
17 accidentally or intentionally, legally or illegally, and has received no notice of such occurrence  
18 and has no knowledge that any such condition exists at the Premises. If any claim is ever  
19 made against County relating to Hazardous Substances present at or around the Premises,  
20 whether or not such substances are present as of the date hereof, or any such Hazardous  
21 Substances are hereafter discovered at the Premises (unless introduced by County, its agents  
22 or employees), all costs of removal incurred by, all liability imposed upon, or damages suffered  
23 by County because of the same shall be borne by Lessor, and Lessor hereby indemnifies and  
agrees to be responsible for and defend and hold County harmless from and against all such  
costs, losses, liabilities and damages, including, without limitation, all third-party claims  
(including sums paid in settlement thereof, with or without legal proceedings) for personal  
injury or property damage and other claims, actions, administrative proceedings, judgments,  
compensatory and punitive damages, lost profits, penalties, fines, costs, losses, attorneys'  
fees and expenses (through all levels of proceedings), consultants or experts fees and costs  
incurred in enforcing this indemnity. The representation, warranty and indemnity of Lessor  
described in this Paragraph shall survive the termination or expiration of this Lease.

24 **7.5 Sick Building Syndrome.** Lessor warrants and represents the  
25 Premises shall be constructed, operated and maintained free of certain hazards, including, but  
not limited to: spores, fungus, molds, bacteria, chemicals or fumes or other causes of any

1 hazardous micro-environments, sometimes known as "Sick Building Syndrome", emanating  
2 from or within the Premises that may potentially cause discomfort, bodily injury, sickness or  
3 death. Should it be determined that remediation is necessary based on a report by a trained  
4 investigator, Lessor will promptly contract with a qualified and experienced company to safely  
remove the micro-environments using remediation guidelines recommended or required by the  
appropriate governmental agency. Any cost incurred to cause the Premises to be free of such  
hazard shall be borne by Lessor.

5 **7.6 Waste Water.** Lessor shall be responsible for compliance with all  
6 Federal, state or local laws, regulations or permits pertaining to storm water pollution,  
7 prevention plans ("SWPP") and all National Pollution Discharge Elimination System ("NPDES")  
8 laws or regulations adopted or to be adopted by the United States Environmental  
9 Protection Agency. Parking lot sweeping shall be done as required by NPDES rules or as  
10 needed, at least two times per year, once prior to the rainy season.

## 8. Custodial Services.

11 **8.1 Custodial Services.** Lessor shall provide, or cause to be provided,  
12 and pay for all custodial services in connection with the Leased Premises and such services  
13 shall be provided as set forth in the attached Exhibit "E". The provider of such custodial  
14 services will perform background checks through LiveScan or in the manner specified by  
15 County, of qualified permanent and temporary employees to determine their suitability for  
employment. The provider will be bonded in the sum of Ten Thousand Dollars (\$10,000.00),  
and proof of such insurance, as supplied by the Lessor, shall be furnished prior to occupancy  
of Premises by County. In addition to bonding as required herein, Lessor shall also receive  
proof of statutory workers' compensation insurance, commercial general liability and vehicle  
liability insurance from the provider of any custodial functions performed at the Premises  
location.

16 **8.1.1** Notwithstanding the provisions of section 8.1 herein, the cost of  
17 the monthly custodial services shall not exceed \$1,317.48. Within sixty (60) days of each  
18 anniversary date of the Lease, Lessor shall prepare an itemized expense statement of the  
actual cost for custodial services for the previous year. County shall receive a rent credit for  
the amount overpaid. In the event costs exceed \$1,317.48, County shall reimburse Lessor,  
within sixty (60) days, the difference between \$1,317.48 and the actual cost.

19 **8.2 County's Right to Provide Custodial Service and Deduct Cost.** If  
20 County provides written notice to Lessor of an event or circumstance that requires the action  
21 of Lessor with respect to the custodial services as set forth in Section 8.1 and Exhibit "E", and  
22 Lessor fails to provide such action as required by the terms of this Lease within three (3) days  
23 of County's notice, County may take the required action to provide custodial services by its  
24 staff or those of a custodial contractor if: 1) County delivers to Lessor an additional written  
25 notice advising Lessor that County intends to take the required action if Lessor does not begin  
the required action within forty-eight (48) hours after the written notice; and 2) Lessor fails to  
begin the required work within this forty-eight (48) hour period. Upon demand by County,  
Lessor shall promptly reimburse County the actual cost and expenses thereof, provided said  
costs and expenses are reasonable. Should Lessor fail to promptly pay the cost and  
expenses, County may deduct and offset that amount from Rent payable under this Lease.  
For purposes of this Section, notice given by fax or e-mail shall be deemed sufficient.

1           **9. Utilities.**

2           **9.1** Lessor warrants and represents to County that during the term of this  
3 Lease and any extension thereof that sufficient utility services to provide water,  
4 telecommunications, electric power, natural gas and sewers necessary to meet County's  
5 requirements exists or are available for use by County within the Premises.

6           **9.2** County shall pay for all telephone and electrical services within the  
7 leased space, which will be used in connection with the Leased Premises. Lessor shall  
8 provide, or cause to be provided, and pay for all other utility services, including, but not limited  
9 to, water, natural gas, refuse collection and sewer services, as may be required in the  
10 maintenance, operation and use of the Leased Premises.

11           **10. Repairs and Maintenance.**

12           **10.1 Lessor's Repair and Maintenance Obligations.** Lessor shall, at  
13 Lessor's sole expense and in accordance with the terms of this Lease, repair, replace and  
14 maintain in attractive condition, good order and function throughout the term in accordance  
15 with Exhibit "F", General Construction Specifications for Leased Facilities, (a) the structural  
16 portions of the Premises (understood to include the roof, foundation and load bearing walls);  
17 (b) the nonstructural portions of the Premises (understood to include the roof covering and  
18 membrane) including, but not limited to, all improvements, alterations, fixtures, but excluding  
19 furnishings; (c) all systems and equipment, including, but not limited to, Base Premises  
20 Systems as heretofore described that serve the Premises; and (d) the exterior portions of the  
21 Premises, and real property, including, but not limited to, landscaping, driveways, sidewalks,  
22 lighting and parking facilities servicing the Premises. It is the intent of this paragraph that  
23 Lessor performs any and all building repairs, replacements and maintenance. Lessor agrees  
24 to make all repairs to or alterations of the Premises that may become necessary by reason of  
25 industry standard for age, wear and tear, deferred maintenance or defects in any construction  
thereof by Lessor.

1           **10.2 Lessor's Default.** Repairs shall be made promptly when appropriate  
2 to keep the applicable portion of the Premises and other items in the condition described in  
3 this Section. Lessor understands certain response time is required to ensure County  
4 operations continue with minimal interruption to ensure the safety of employees and delivery of  
5 services. The commencement of repairs within twenty-four (24) hours from written notice  
6 include electrical power, HVAC operations and certain essential daily custodial services.  
7 Lessor shall not be in default of its repair and maintenance obligations under this Section 10, if  
8 Lessor commences the repairs and maintenance within twenty-four (24) hours of the  
9 aforementioned areas and thirty (30) days for all others after written notice by County to  
10 Lessor of the need for such repairs and maintenance. If, due to the nature of the particular  
11 repair or maintenance obligation, more than thirty (30) days are reasonably required to  
12 complete it, Lessor shall not be in default under this Section 10 if Lessor begins work within  
13 this thirty (30) day period and diligently pursues this work to completion.

14           **10.3 County's Right to Make Repairs and Deduct Cost.** If County  
15 provides notice to Lessor of an event or circumstance that requires the action of Lessor with  
16 respect to the replacement, repair or maintenance to the Premises or Base Building Systems  
17 serving the Premises as set forth in Section 10.1 and Lessor fails to provide such action as



1 required by the terms of this Lease within the period specified in Section 10.2, County may  
2 (but shall not be obligated to do so) take the required action if: (1) County delivers to Lessor an  
3 additional written notice advising Lessor that County intends to take the required action if  
4 Lessor does not begin the required repair or maintenance within twenty four (24) hours, after  
5 the written notice; and (2) Lessor fails to begin the required work within this twenty four (24)  
6 hour period.

7 **10.3.1** Lessor grants to County a license, effective during the  
8 Lease Term, to enter upon those portions of the Premises access to which is reasonably  
9 necessary for County to take such action.

10 **10.3.2** If such action was required under the terms of this Lease  
11 to be taken by Lessor, County shall be entitled to prompt reimbursement by Lessor of County's  
12 reasonable costs and expenses in taking such action, plus interest at the then prevailing legal  
13 rate of interest from the date these costs are incurred until the date of Lessor's repayment.  
14 Lessor's obligation to reimburse County shall survive expiration or earlier termination of this  
15 Lease.

16 **10.3.3** If, within thirty (30) days after receipt of County's written  
17 demand for payment of County's costs incurred in taking such action on Lessor's behalf,  
18 Lessor has not paid the invoice or delivered to County a detailed written objection to it, County  
19 may deduct from Rent payable by County under this Lease the amount set forth in the invoice,  
20 plus interest at the interest rate described above from the date these costs are incurred until  
21 the date of County's Rent set off.

#### 22 **10.4 Emergency Repairs.**

23 **10.4.1** An "Emergency Repair Situation" is defined as the  
24 existence of any condition that requires prompt repair, replacement or service to minimize the  
25 impact of an event or situation which affects County's ability to conduct business in a neat,  
26 clean, safe and functional environment.

27 **10.4.2** If County notifies Lessor of an Emergency Repair  
28 Situation which occurs in or about the Premises which is the responsibility of the Lessor to  
29 repair or maintain, then Lessor shall commence appropriate repairs or maintenance  
30 immediately after notice of the condition is given by County, which notice may be via  
31 telephone, facsimile, personal contact or any other means, and Lessor shall thereafter  
32 diligently pursue to completion said repairs or maintenance.

33 **10.4.3** If Lessor fails to commence repairs within twenty-four  
34 (24) hours of the aforementioned notice, or if the County is unable to contact Lessor or any  
35 designated agent within a reasonable time based upon the seriousness of the event or  
36 situation, County may, but shall not be so obligated to, cause said repairs or replacements to  
37 be made or such maintenance to be performed. Upon demand by County, Lessor shall  
38 promptly reimburse County the actual cost and expenses thereof, provided said costs and  
39 expenses are reasonable. Should Lessor fail to promptly pay the cost and expenses, County  
40 may deduct and offset that amount from Rent payable under this Lease.

#### 41 **10.5 Periodic Services.** Lessor shall provide, or cause to be provided,

1 and pay for all Periodic Services, including, interior painting of common areas every three  
2 years, if so requested by County; monthly pest control services; quarterly HVAC standard  
3 preventative maintenance and changing of air filters; annual fire extinguisher inspections; reset  
4 interior and exterior time clocks for time changes; annual roof inspections and maintenance to  
include roof repairs/replacement; cleaning of roof gutters, drains, and down spouts prior to  
rainy season.

4 **11. Alterations and Additions.**

5 **11.1 Improvements by Lessor.**

6 **11.1.1** Lessor recognizes and understands that any County  
7 improvements requested by the County to be completed by Lessor during the term of this  
8 Lease shall be undertaken according to Exhibit "B", Leasehold Improvement Agreement, and  
Exhibit "F", General Construction Specifications for Leased Facilities.

9 **11.1.2** Lessor recognizes and understands that any County  
10 improvements requested by County may be subject to the provisions contained in the  
11 California Labor Code (commencing with Section 1720) relating to general prevailing wage  
rates and other pertinent provisions therein. Lessor and Lessor's contractors may be subject  
to audit to confirm compliance with wage scale regulations.

12 **11.1.3** Lessor shall comply and stay current with all applicable  
13 local, state and federal building codes and laws as from time to time amended, including, but  
14 not limited to, the Americans with Disabilities Act requirements in providing the County with  
any requested County improvements.

15 **11.1.4** If any agency, division or department of any  
16 governmental entity with appropriate jurisdiction condemns the Premises or any part of the  
17 Premises as unsafe or not in conformity with any of the laws or regulations controlling their  
18 construction, occupation or use, or orders or requires any alteration, repair or reconstruction of  
the Premises the responsible party shall be the Lessor, who at its sole cost and expense (and  
without any right of reimbursement from County) immediately effect all necessary alterations  
and repairs required for the Premises full and exact compliance.

19 **11.1.5** Lessor shall cause all County improvements to be lien  
20 free, completed at Lessor's cost in a workmanlike manner and in compliance with all  
applicable law.

21 **11.1.6** County agrees when requested by Lessor to execute and  
22 deliver any applications, consents or other instruments required to permit Lessor to complete  
such County improvements or to obtain permits for the work.

23 **11.1.7** Post occupancy tenant improvements requested by  
24 County and completed by Lessor shall be reimbursed by County at Lessor's cost plus ten  
percent (10%). Lessor's invoices for such improvements shall be itemized according to  
material, sales tax, labor, and Lessor's ten percent (10%) overhead handling charge.

25 **11.1.8** Due to County fiscal year funding and accounting

1 practices, any costs due to Lessor for reimbursement of tenant improvements during the term  
2 must be invoiced and received by the County prior to May 1<sup>st</sup> of each fiscal year in which  
services to County were provided to ensure payment.

3 **11.2 Improvements by County.**

4 **11.2.1** Any alterations, improvements or installation of fixtures to  
5 be undertaken by County shall have the prior written consent of Lessor. Such consent shall  
not be unreasonably withheld, conditioned or delayed by Lessor.

6 **11.2.2** All alterations and improvements made, and fixtures  
7 installed, by County shall remain County property and may be removed by County at or prior  
to the expiration of this Lease; provided, however, that such removal does not cause injury or  
8 damage to the Leased Premises beyond normal wear and tear.

9 **11.3 Communications Equipment.** County may, from time to time, install  
maintain, replace and/or remove any satellite dishes, links, duct bank or antennas on the  
10 grounds, roof and/or exterior walls or parapet of the Premises as County deems reasonably  
necessary or desirable, provided County shall first obtain Lessor's written approval, which  
11 approval shall not be unreasonably withheld, conditioned, or delayed. Upon the removal by  
County of any such satellite dishes, links or antennas, County shall repair any damage  
12 incurred in connection with such removal.

13 **12. Indemnification, and Insurance.**

14 **12.1 Indemnification and Hold Harmless.**

15 **12.1.1** Lessor shall indemnify and hold harmless the County  
Parties from any liability, including, but not limited to, property damage, bodily damage, bodily  
16 injury, or death, or from any services provided by Lessor Parties or any act, error, omission, of  
Lessor Parties or of any invitee, guest, or licensee of Lessor in, on, or about the Project arising  
17 out of, from or in any way relating to this Lease. When indemnifying County Parties, Lessor  
shall defend at its sole cost and expense, including, but not limited to, attorney fees, cost of  
18 investigation, defense and settlements or awards, on behalf of the County Parties in any  
claim or action based upon such liability. Lessor Parties shall not be indemnifying County  
19 Parties for liability arising within the County Leased Premises when such liability arose out of  
or from County's responsibilities under the term of this Lease.

20 **12.1.2** County shall indemnify and hold harmless the Lessor  
Parties from any liability whatsoever, including, but not limited to, property damage, bodily  
21 injury, or death, based or asserted on events which may occur within the County Leased  
Premises and is under the control of the County arising out of or from its use and occupancy  
22 relating to this Lease. County Parties shall not indemnify Lessor Parties for liability arising  
within the County Leased Premises when such liability arose out of or from Lessor's  
23 responsibilities under the terms of this Lease. County shall defend at its sole cost and  
expense, including, but not limited to, attorney fees, cost of investigation, defense and  
24 settlements or awards, on behalf of the Lessor Parties in any claim or action based upon such  
liability.

25 ///

1                   **12.1.3**       With respect to any action or claim subject to  
2 indemnification herein, the indemnifying party shall, at their sole cost, have the right to use  
3 counsel of their choice and shall have the right to adjust, settle, or compromise any such  
4 action or claim without the prior consent of the indemnified party; provided, however, that any  
5 such adjustment, settlement or compromise in no manner whatsoever limits or circumscribes  
6 the indemnifying party's obligation to indemnify as set forth herein.

7                   **12.1.4**       The indemnifying party's obligation hereunder shall be  
8 satisfied when they have provided the indemnified party the appropriate form of dismissal  
9 relieving the indemnified party from any liability for the action or claim involved.

10                   **12.1.5**       The specified insurance limits required in this Lease shall  
11 in no way limit or circumscribe the indemnifying party's obligation to indemnify as set forth  
12 herein.

13                   **12.1.6**       In the event there is conflict between this clause and  
14 California Civil Code Section 2782, this clause shall be interpreted to comply with Civil Code  
15 2782. Such interpretation shall not relieve the indemnifying party's obligation to provide  
16 indemnification to the fullest extent allowed by law.

17                   **12.1.7       Survival of Indemnification.** The paragraphs of this  
18 Section 12 shall survive the expiration or earlier termination of this Lease until all claims  
19 against County Parties involving any of the indemnified matters are fully, finally, and absolutely  
20 barred by the applicable statutes of limitations.

## 21                   **12.2       Insurance**

22                   **12.2.1       Lessor's Insurance.** Without limiting or diminishing any  
23 indemnification contained within this Lease, Lessor and/or their authorized representatives,  
24 including, if any, a property management company, shall procure and maintain or cause to be  
25 maintained, at its sole cost and expense, the following insurance coverage during the term of  
this Lease:

**12.2.1.1       Workers' Compensation.** If the Lessor has  
employees as defined by the State of California, the Lessor shall maintain statutory Workers'  
Compensation Insurance (Coverage A) as prescribed by the laws of the State of California.  
Policy shall include Employers' Liability (Coverage B) including Occupational Disease with  
limits not less than One Million Dollars (\$1,000,000) per person per accident.

**12.2.1.2       Commercial General Liability.** Commercial  
General Liability Insurance coverage, including, but not limited to, premises liability,  
contractual liability, products/completed operations, personal and advertising injury, cross  
liability coverage and employment practices liability covering bodily injury, property damage,  
and personal injury arising out of or relating, directly or indirectly, to the design, construction,  
maintenance, repair, alteration and ownership of the Premises and all areas appurtenant  
thereto including claims which may arise from or out of Lessor's operations, use, and  
management of the Premises, or the performance of its obligations hereunder. Policy limits  
shall not be less than One Million Dollars (\$1,000,000) per occurrence. If such insurance

1 contains a general aggregate limit, it shall apply separately to this Lease or be no less than  
2 two (2) times the occurrence limit.

3 **12.2.1.3 Vehicle Liability.** If vehicles or licensed mobile  
4 equipment are used on the Project, Lessor shall maintain auto liability insurance for all owned,  
5 non-owned or hired automobiles in an amount not less than One Million Dollars (\$1,000,000)  
6 per occurrence combined single limit.

7 **12.2.1.4 Property (Physical Damage).** All-Risk real  
8 property insurance coverage, including earthquake and flood, if applicable, for the full  
9 replacement cost value of buildings, structures, fixtures, all improvements therein, and building  
10 systems on the Project as the same exists at each early anniversary of the term. Policy shall  
11 include Business Interruption coverage.

12 **12.2.1.5 General Insurance Provisions – All Lines.**

13 (a) Any insurance carrier providing Lessor's insurance  
14 coverage hereunder shall be admitted to the State of California and have an A.M. BEST rating  
15 of not less than an A:VIII (A:8) unless such requirements are waived, in writing, by the County  
16 Risk Manager. If the County's Risk Manager waives a requirement for a particular insurer  
17 such waiver is only valid for that specific insurer and only for one policy term.

18 (b) The Lessor or Lessor's insurance carrier(s) must declare  
19 its insurance deductibles or self-insured retentions. If such deductibles or self-insured  
20 retentions exceed Five Hundred Thousand Dollars (\$500,000) per occurrence such  
21 deductibles and/or retentions shall have the prior written consent of the County Risk Manager  
22 before the commencement of the Lease term.

23 (c) At the inception of this Lease and annually at the  
24 Lessor's insurance policy renewal date(s), the Lessor shall cause their insurance carrier(s) to  
25 furnish the County of Riverside with a properly executed copy of the Certificate(s) of Insurance  
and copies of Endorsements effecting coverage as required herein. Further, said Certificate(s)  
and policies of insurance shall contain the covenant of the insurance carrier(s) shall provide no  
less than thirty (30) days written notice be given to the County of Riverside prior to any  
material modification or cancellation of such insurance. In the event of a material modification  
or cancellation of coverage, this Lease shall terminate forthwith, unless the County of  
Riverside receives, prior to such effective date, another properly executed copy of the  
Certificate of Insurance and copies of the endorsements or policies, including all  
endorsements and attachments thereto evidencing coverage and the insurance required  
herein is in full force and effect. The Lease term shall not commence until the County of  
Riverside has been furnished copies of the Certificates(s) of Insurance and copies of the  
Endorsements or policies of insurance including all endorsements and any and all other  
attachments as required in this Section.

(d) It is understood and agreed by the Parties hereto and the  
Lessor's insurance company(s) that the Certificate(s) of Insurance and policies shall so  
covenant and shall be construed as primary insurance, and the County's insurance and/or  
deductibles and/or self-insured retentions or self-insured programs shall not be construed as  
contributory.

1  
2 **12.2.2 County's Insurance:** County maintains funded  
3 programs of Self-Insurance. County shall provide to Lessor a Certificate of Self-Insurance  
4 evidencing the County's Self-Insurance for the following coverage, if so requested by Lessor:

5

12.2.2.1 Workers' Compensation	\$1,000,000 per occurrence
12.2.2.2 Commercial General Liability	\$1,000,000 per occurrence
12.2.2.3 Automobile Liability	\$1,000,000 per occurrence

6

7 **13. Damage and Destruction.**

8 **13.1 Repair of Damage.** County agrees to notify Lessor in writing promptly  
9 of any damage to the Premises resulting from fire, earthquake, or any other identifiable event  
10 of a sudden, unexpected, or unusual nature ("Casualty"). If the Premises, whether covered by  
11 insurance or not, are damaged by a Casualty, or the Casualty results in the Premises not  
12 being provided with Base Building Systems or parking facilities, and if neither Lessor nor  
13 County has elected to terminate this Lease under this Section 13, Lessor shall promptly and  
14 diligently restore Premises, the County Improvements originally constructed by Lessor, Base  
15 Building Systems, and County's parking facilities to substantially the same condition as existed  
16 before the Casualty, subject to modifications required by building codes and other laws. If  
17 County requests that Lessor make any modifications to the County Improvements in  
18 connection with the rebuilding, Lessor may condition its consent to those modifications on: (a)  
19 confirmation by Lessor's contractor that the modifications shall not increase the time needed to  
20 complete the County Improvements; or (b) an agreement by County that the additional  
21 construction period shall not extend the rent abatement period.

22 **13.2 Repair Period Notice.** Lessor shall, within thirty (30) days after the  
23 date of the Casualty, provide written notice to County indicating the anticipated period for  
24 repairing the Casualty ("Repair Period Notice"). The Repair Period Notice shall be  
25 accompanied by a certified statement executed by the Contractor retained by Lessor to  
complete the repairs or, if Lessor has not retained a Contractor, a licensed Contractor not  
affiliated with Lessor, certifying the Contractor's opinion about the anticipated period for  
repairing the Casualty. The Repair Period Notice shall also state, if applicable, Lessor's  
election either to repair or to terminate the Lease under Section 13.3.

26 **13.3 Lessor's Option to Terminate or Repair.** Lessor may elect either to  
27 terminate this Lease or to effectuate repairs if: (a) the Repair Period Notice estimates that the  
28 period for repairing the Casualty exceeds ninety (90) days from the date of the Casualty; or (b)  
29 the estimated repair cost of the Premises, even though covered by insurance, exceeds fifty  
30 percent (50%) of the full replacement cost.

31 **13.4 County's Option to Terminate.** If (a) the Repair Period Notice  
32 provided by Lessor indicates that the anticipated period for repairing the Casualty exceeds one  
33 hundred twenty (120) days, or (b) notwithstanding the above, in the event of a substantial or  
34 total casualty to the Premises or improvements, County may by written notice to Lessor within  
35 thirty (30) days after such damage or destruction of its intention to terminate this Lease, elect  
to terminate this Lease by providing written notice (County's Termination Notice) to Lessor  
within thirty (30) days after receiving the Repair Period Notice. If County does not elect to  
terminate within said thirty (30) day period, County shall be considered to have waived its'

1 option to terminate.

2 **13.5 Rent Abatement Due to Casualty.** Lessor and County agree that  
3 County's Rent shall be fully abated during the period beginning on the later of: (a) the date of  
4 the Casualty; or (b) the date on which County ceases to occupy the Premises and ending on  
5 the date of Substantial Completion of Lessor's restoration obligations as provided in this  
6 Section 13 ("Abatement Period"). If, however, County is able to occupy and does occupy a  
7 portion of the Premises, Rent shall be abated during the Abatement Period only for the portion  
8 of the Premises not occupied by County.

9 **13.6 Damage Near End of Term.** Despite any other provision of this  
10 Section 13, if the Premises are destroyed or damaged by a Casualty during the last eighteen  
11 (18) months of the original Lease Term, Lessor and County shall each have the option to  
12 terminate this Lease by giving written notice to the other of the exercise of that option within  
13 thirty (30) days after that damage or destruction, provided, however, County may negate  
14 Lessor's election to terminate under this Section 13.6 by electing, within ten (10) days after  
15 receipt of Lessor's termination notice, to exercise any unexercised option to extend this Lease.  
16 If County negates Lessor's election, this Lease shall continue in effect unless Lessor has the  
17 right to, and elects to, terminate this Lease under Section 13.3.

18 **13.7 Effective Date of Termination; Rent Apportionment.** If Lessor or  
19 County elects to terminate this Lease under this Section 13 in connection with a Casualty, this  
20 termination shall be effective thirty (30) days after delivery of notice of such election. County  
21 shall pay Rent, properly apportioned up to the date of the Casualty. After the effective date of  
22 the termination, Lessor and County shall be discharged of all future obligations under this  
23 Lease, except for those provisions that, by their terms, survive the expiration or earlier  
24 termination of the Lease.

25 **13.8 Waiver of Statutory Provisions.** The provisions of this Lease,  
including those in this Section 13, constitute an express agreement between Lessor and  
County that applies in the event of any Casualty to the Premises. Lessor and County,  
therefore, fully waive the provisions of any statute or regulation, for any rights or obligations  
concerning a Casualty including California Civil Code Sections 1932(2) and 1933(4).

**13.9 Release on Termination.** In the event of any termination of this  
Lease in accordance with Section 13, the Parties shall be released therefrom without further  
obligation to the other Party, except as may otherwise be specifically set forth in this Lease  
and items that have accrued and are unpaid.

**14. Eminent Domain.**

**14.1 Total Condemnation.** If all of the Premises are condemned by  
eminent domain, inversely condemned, or sold in lieu of condemnation for any public or quasi-  
public use or purpose, this Lease will terminate as of the date of title vesting in that proceeding  
and the Rent will be abated from the date of termination.

**14.2 Partial Condemnation.** If any portion of the Premises is condemned  
by eminent domain, inversely condemned, or sold in lieu of condemnation for any public or  
quasi-public use or purpose and the partial condemnation renders the Premises unusable for

1 County's business, this Lease will terminate as of the date of title vesting or order of immediate  
2 possession in that proceeding and the Rent will be abated to the date of termination. If the  
3 partial condemnation does not render the Premises unusable for the business of County and  
4 less than a substantial portion of the Premises is condemned, Lessor must promptly restore  
5 the Premises to the extent of any condemnation proceeds recovered by Lessor, excluding the  
6 portion lost in the condemnation, and this Lease will continue in full force, except that after the  
7 date of the title vesting, the Rent will be adjusted, as reasonably determined by Lessor and  
8 County.

9 **14.3 Award.** If the Premises are wholly or partially condemned, Lessor will  
10 be entitled to the entire award paid for the condemnation, and County waives any claim to any  
11 part of the award from Lessor or the condemning authority. County, however, will have the  
12 right to recover from the condemning authority any compensation that may be separately  
13 awarded to County in connection with costs in removing County's merchandise, furniture,  
14 fixtures, leasehold improvements, and equipment to a new location.

15 **14.4 Temporary Condemnation.** In the event of a temporary  
16 condemnation, this Lease will remain in effect, County will continue to pay Rent, and County  
17 will receive any award made for the condemnation. If a temporary condemnation remains in  
18 effect at the expiration or earlier termination of this Lease, County will pay Lessor the  
19 reasonable cost of performing any obligations required of County with respect to the surrender  
20 of the Premises. If a temporary condemnation is for a period that extends beyond the Term,  
21 this Lease will terminate as of the date of occupancy by the condemning authority and any  
22 award will be distributed in accordance with Section 14.3.

## 23 **15. Estoppel Certificates.**

24 **15.1** Within twenty (20) business days after receipt of a written request by  
25 either party, the other party shall execute and deliver to the requesting party an Estoppel  
Certificate, in the form of the attached Exhibit "G", indicating in the certificate any exceptions to  
the statements in the certificate that may exist at that time.

## 1 **16. Subordination, Non-Disturbance, and Attornment.**

2 **16.1 Subordination, Non-Disturbance, and Attornment Agreement.** To  
3 carry out the purposes of Section 16.2 and Section 16.3, the Parties agree to execute a  
4 Subordination, Non-Disturbance and Attornment Agreement in the form set forth in the  
5 attached Exhibit "H".

6 **16.2 Subordination.** County agrees that within forty-five (45) business  
7 days after Lessor's written request, it shall execute the agreement referred to in Section 16.1  
8 that Lessor reasonably considers necessary to evidence or confirm the subordination or  
9 inferiority of this Lease to the lien of any mortgage, deed of trust or other encumbrance of the  
10 Premises or any renewal, extension, modification, replacement thereof, provided however, that  
11 such Subordination Agreement shall be strictly limited to matters contained in the Agreement  
12 referred to in Section 16.1 and no such Subordination Agreement shall materially increase any  
13 of County's obligations or materially decrease any of County's rights under this Lease, nor  
14 shall the possession of County be disturbed, by reason of any foreclosure, sale or other action  
15 under any such trust deed, mortgage or other encumbrance.



1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25

**16.3 Attornment.** If Lessor's interest in the Premises passes to a successor, and provided County has received the Non-Disturbance agreement referred to in Section 16.1, County shall, within forty five (45) business days after Lessor's transferee's request, execute the agreement referred to in Section 16.1, thereby agreeing to attorn and to recognize the transferee as the Lessor under this Lease; provided the transfer of Lessor's interest in the Premises was by sale, lease, foreclosure, deed in lieu of foreclosure, exercise of any remedy provided in any encumbrance or operation of law.

**17. Breach by Lessor.**

**17.1 Lessor's Default.** Except as provided to the contrary in this Lease, Lessor's failure to perform any of its obligations under this Lease shall constitute a default by Lessor under the Lease if the failure continues for thirty (30) days after written notice of the failure from County to Lessor. If the required performance cannot be completed within thirty (30) days, Lessor's failure to perform shall constitute a default under the Lease unless Lessor undertakes to cure the failure within thirty (30) days and diligently and continuously attempts to complete this cure as soon as reasonably possible.

**17.2 County's Right to Cure Lessor's Default and Deduct Cost.** Except as provided to the contrary in this Lease, if County provides notice to Lessor of Lessor's failure to perform any of its obligations under this Lease and Lessor fails to provide such action as required by the terms of this Lease within the period specified, County may take the required action if: (a) County delivers to Lessor an additional written notice advising Lessor that County intends to take the required action if Lessor does not begin the required action within ten (10) days after the written notice; and (b) Lessor fails to begin the required action within this ten (10) day period.

**17.3 Rent Setoff.** If, within thirty (30) days after receipt of County's written demand for payment of County's costs incurred in taking such action on Lessor's behalf, Lessor has not paid the invoice or delivered to County a detailed written objection to it, County may deduct from Rent payable by County under this Lease the amount set forth in the invoice, including transaction costs and attorneys' fees, plus interest at the then legal rate of interest from the date these costs are incurred until the date of County's Rent setoff.

**18. Lessor's Representations and Warranties.** Lessor represents and warrants to County that:

**18.1 Title.** County's Leasehold interest in the Premises is free and clear of restrictions which would restrict County's rights under this Lease.

**18.2 Certificate of Authority.** Lessor covenants that it is a duly constituted under the laws of the state of its organization, and that the person(s) who is acting as its signatory in this Lease is duly authorized and empowered to act for and on behalf of the Lessor. Lessor shall furnish County prior to the execution hereof with evidence of the authority of the signatory to bind the entity or trust as contemplated herein.

**18.3 No Litigation.** There are no judicial, quasi-judicial, administrative or other orders, injunctions, moratoria or pending proceedings against Lessor or the Premises

1 which preclude or interfere with, or would preclude or interfere with, the construction  
2 contemplated herein or the occupancy and use of the Premises by County for the purposes  
herein contemplated.

3 **18.4 Easements.** Lessor shall not (a) subdivide, parcel or otherwise divide  
4 the Premises, (b) create, modify or terminate any ingress or egress to or from the premises, or  
5 (c) create any easements in the Premises, that would preclude or interfere with County's  
intended use of the premises, without County's prior written approval.

6 **19. Miscellaneous.**

7 **19.1 Quiet Enjoyment.** Lessor covenants that County shall at all times  
8 during the term of this Lease peaceably and quietly have, hold and enjoy the use of the  
9 Premises so long as County shall fully and faithfully perform the terms and conditions that it is  
10 required to do under this Lease. If the Premises are part of a building shared with other  
11 tenants of Lessor, during County's tenancy, Lessor may make or permit other tenants to make  
alterations, renovations and improvements to those portions of the building not occupied by  
County. Lessor covenants for itself and anyone deriving title from or holding title under Lessor  
that County's access, ingress, loading and unloading and sufficient parking for County's  
business shall not unreasonably be obstructed nor shall the daily business of County be  
disrupted as a result of such alterations, renovations and improvements.

12 **19.2 Non-Waiver.** No waiver of any provision of this Lease shall be implied  
13 by any failure of either party to enforce any remedy for the violation of that provision, even if  
14 that violation continues or is repeated. Any waiver by a party of any provision of this Lease  
must be in writing. Such written waiver shall affect only the provision specified and only for the  
time and in the manner stated in the writing.

15 **19.3 Binding on Successors.** The terms and conditions herein contained  
16 shall apply to and bind the heirs, successors in interest, executors, administrators,  
representatives and assigns of all the Parties hereto.

17 **19.4 Severability.** The invalidity of any provision in this Lease as  
18 determined by a court of competent jurisdiction shall in no way affect the validity of any other  
provision hereof.

19 **19.5 Venue.** Any action at law or in equity brought by either of the Parties  
20 hereto for the purpose of enforcing a right or rights provided for by this Lease shall be tried in a  
21 court of competent jurisdiction in the County of Riverside, State of California, and the Parties  
hereto waive all provisions of law providing for a change of venue in such proceedings to any  
other county.

22 **19.6 Attorneys' Fees.** In the event of any litigation or arbitration between  
23 Lessor and County to enforce any of the provisions of this Lease or any right of either party  
24 hereto, the unsuccessful party to such litigation or arbitration agrees to pay to the successful  
25 party all costs and expenses, including reasonable attorneys' fees, incurred therein by the  
successful party, all of which shall be included in and as a part of the judgment rendered in  
such litigation or arbitration.

///

1                   **19.7 County's Representative.** County hereby appoints the Assistant  
2 County Executive Officer of the Economic Development Agency as its authorized  
representative to administer this Lease.

3                   **19.8 Agent for Service of Process.** It is expressly understood and agreed  
4 that in the event Lessor is not a resident of the State of California or it is an association or  
partnership without a member or partner resident of the State of California, or it is a foreign  
5 corporation, then in any such event, Lessor shall file with County's Director of Facilities  
Management, upon its execution hereof, a designation of a natural person residing in the State  
6 of California, giving his or her name, residence and business addresses, as its agent for the  
purpose of service of process in any court action arising out of or based upon this Lease, and  
7 the delivery to such agent of a copy of any process in any such action shall constitute valid  
service upon Lessor. It is further expressly understood and agreed that if for any reason  
8 service of such process upon such agent is not feasible, then in such event, Lessor may be  
personally served with such process out of this county and that such service shall constitute  
9 valid service upon Lessor. It is further expressly understood and agreed that Lessor is  
amenable to the process so served, submits to the jurisdiction of the court so obtained and  
waives any and all objections and protests thereto.

10                   **19.9 Entire Lease.** This Lease is intended by the Parties hereto as a final  
11 expression of their understanding with respect to the subject matter hereof and as a complete  
and exclusive statement of the terms and conditions thereof and supersedes any and all prior  
12 and contemporaneous leases, agreements and understandings, oral or written, in connection  
therewith. This Lease may be changed or modified only upon the written consent of the  
13 Parties hereto.

14                   **19.10 Interpretation.** The Parties hereto have negotiated this Lease at  
arms length and have been advised by their respective attorneys, or if not represented by an  
15 attorney, represent that they had an opportunity to be so represented and no provision  
contained herein shall be construed against County solely because it prepared this Lease in its  
16 executed form.

17                   **19.11 Time of Essence.** Time is of the essence with respect to the  
performance of all obligations to be performed or observed by the Parties under this Lease.

18                   **19.12 Recording.** Either Lessor or County shall, upon request of the other,  
19 execute, acknowledge and deliver to the other a short form memorandum of this Lease for  
recording purposes. The Party requesting recordation shall be responsible for payment of any  
20 fees applicable thereto.

21                   **19.13 Consent.** Whenever Lessor's or County's consent is required under  
any provision of this Lease, it shall not be unreasonably withheld, conditioned or delayed.

22                   **19.14 Title.** Lessor covenants that Lessor is well seized of and has good  
23 title to the Premises, and Lessor does warrant and will defend the title thereto, and will  
indemnify County against any damage and expense which County may suffer by reason of  
24 any lien, encumbrance, restriction or defect in title or description herein of the Premises. If, at  
any time, Lessor's title or right to receive Rent and any other sums due hereunder is disputed,  
25 County may withhold such sums thereafter accruing until County is furnished satisfactory

1 evidence as to the Party entitled thereto.

2           **19.15 Conveyance by Lessor.** Should Lessor convey the Premises, all  
3 rights and obligations inuring to the Lessor by virtue of this Lease shall pass to the grantee  
4 named in such conveyance, and the grantor shall be relieved of all obligations or liabilities  
5 hereunder, except those theretofore accrued and not discharged.

6           **19.16 Mechanic's Liens.** If any mechanic's or materialmen's lien or liens  
7 shall be filed against the Premises for work done or materials furnished to a Party, that Party  
8 shall, at its own cost and expense, cause such lien or liens to be discharged within fifteen (15)  
9 days after notice thereof by filing or causing to be filed a bond or bonds for that purpose. In  
10 the event any notice preliminary to establishing such a lien (such as the California Preliminary  
11 20-Day Notice) is served on Lessor for work done on the Premises, Lessor shall immediately  
12 forward a copy of such notice to Lessee.

13           **19.17 Surrender.** County shall, after the last day of the term or any  
14 extension thereof or upon any earlier termination of such term, surrender and yield up to  
15 Lessor the Premises in good order, condition and state of repair, reasonable wear and tear  
16 and damage by fire or other casualty excepted. County may, but shall not be required to: (a)  
17 patch or paint any walls/surfaces; (b) remove any leasehold improvements constructed or  
18 installed prior to or during the term of this Lease or any extension thereof; or (c) remove any  
19 fixtures or equipment installed prior to or during the term of this Lease or any extension  
20 thereof.

21           **19.18 Notice.** Except as expressly provided elsewhere in this Lease, all  
22 notices and other communication required under this Lease shall be in writing and delivered  
23 by: (a) Certified Mail, postage prepaid, return receipt requested, in the United States mail; or  
24 (b) via an overnight courier that provides written evidence of delivery and addressed to the  
25 Party hereto to whom the same is directed at the addresses set forth in Section 19.18 herein.  
Either Party hereto may from time to time change its mailing address by written notice to the  
other Party.

26           **County's Notification Address:**

27           County of Riverside  
28           Economic Development Agency  
29           3133 Mission Inn Avenue  
30           Riverside, California 92507-4199  
31           Attention: Deputy Director of Real Estate

32           **Lessor's Notification Address:**

33           T W Investments  
34           c/o Capri Realty  
35           78100 Main St., Ste. 205  
36           La Quinta, CA 92253

37           **19.19 Authority.** If Lessor is a corporation, general or limited partnership or  
38 individual owner, each individual executing this Lease on behalf of said corporation,

1 partnership, or individual represents and warrants that he or she is duly authorized to execute  
2 and deliver this Lease on behalf of said corporation, in accordance with bylaws of said  
3 corporation, or as a partner or individual is authorized to execute this Lease and that this  
4 Lease is binding upon said corporation and/or partnership or individual.

5 **19.20 Approval of Supervisors.** Anything to the contrary notwithstanding,  
6 this Lease shall not be binding or effective until its approval and execution by the Chairman of  
7 the Riverside County Board of Supervisors.

8 **MAR 23 2010**


9 Dated: \_\_\_\_\_

10 **T W INVESTMENTS**

11 By:   
12 Terry William Ireland


13 **COUNTY OF RIVERSIDE**

14 **ATTEST:**  
15 Kecia Harper-Ihem  
16 Clerk of the Board

17 By:   
18 Marion Ashley, Chairman  
19 Board of Supervisors

20 By:   
21 Deputy

22 **APPROVED AS TO FORM:**  
23 Pamela J. Walls  
24 County Counsel

25 By:   
Synthia M. Gunzel  
Deputy County Counsel

HR:jw  
02/09/10  
CC008  
12.991



PEREZ RD.

Parking

Future Development

68625 Perez Building

76/63

Parking

Secured Parking  
County

68616


76/65

68615

Pajaro Business Park  
68625 Perez Rd.  
Cathedral City, CA

EXHIBIT A

CATHEDRAL CANYON DR



LEASEHOLD IMPROVEMENT AGREEMENT  
(68615A Perez Road, Suites 5, 6 & 7  
62625 Perez Road, Suites 9B & 10B  
Cathedral City, CA)

This Leasehold Improvement Agreement shall set forth the terms and conditions relating to the construction of the County improvements in the Premises. This Leasehold Improvement Agreement is essentially organized chronologically and addresses the issues of the construction of the Premises, in sequence, as such issues will arise during the actual construction of the Premises. All references in this Leasehold Improvement Agreement to Paragraphs or Sections of the "Lease" shall mean the relevant portion of that certain Office Lease to which this Leasehold Improvement Agreement is attached as Exhibit "B" and of which this Leasehold Improvement Agreement forms a part, and all references in the Lease to Sections of "Leasehold Improvement Agreement" shall mean the relevant portion of this Leasehold Improvement Agreement and all references in this Leasehold Improvement Agreement to Sections of this Leasehold Improvement Agreement shall mean the relevant portion of this Leasehold Improvement Agreement.

**SECTION 1 - LESSOR'S INITIAL CONSTRUCTION OF PREMISES**

1.1 Lessor will cause the construction of, at its sole cost and expense, or has acquired or constructed, that certain free standing building described in Section 2 of the Lease, hereinafter referred to as the "Base Building."

**SECTION 2 - CONSTRUCTION DRAWINGS FOR THE PREMISES**

2.1 Lessor shall, at its sole cost and expense, and subject to reimbursement as hereinafter set forth, construct the improvements in the Premises (the "Leasehold Improvements") pursuant to those certain blueprints, floor and space plans, specification and finalize construction prices, collectively, the approved "Working drawings" prepared by Lessor's architect. Lessor shall make no changes or modifications to the Approved Working Drawings without the prior written consent of County, which consent may be withheld if such change or modification would directly or indirectly delay the "Substantial Completion," as that term is defined in Section 6.1 of this Leasehold Improvement Agreement, of the Premises or increase the cost of designing or constructing the Leasehold Improvements. Any changes or modifications approved by the County shall be at Lessor's sole cost and expense.

**SECTION 3 - CONSTRUCTION DRAWINGS**

3.1 Selection of Architect/Construction Drawings. Lessor shall retain an architect or space planner (the "Architect") to prepare the Construction Drawings. Lessor shall retain the engineering consultants (the "Engineers") to prepare all plans and engineering working drawings relating to the structural, mechanical, electrical, plumbing, HVAC, life safety, and sprinkler work of the Leasehold Improvements. The plans and

drawings to be prepared by Architect and the Engineers hereunder shall be known collectively as the "Construction Drawings." All Construction Drawings shall comply with the drawing format and specifications as determined by Lessor, and shall be subject to County's approval. Lessor and Architect shall verify, in the field, the dimensions and conditions as shown on the relevant portions of the Base Building Plans, and Lessor and Architect shall be solely responsible for the same, and County shall have no responsibility in connection therewith. County's review of the Construction Drawings as set forth in this Section 3, shall be for its sole purpose and shall not imply County's review of the same, or obligate Lessor to review the same, for quality, design, Code compliance or other like matters. Accordingly, notwithstanding that any Construction Drawings are reviewed by County or its agents and consultants, and notwithstanding any advice or assistance which may be rendered to Lessor by County or County's agents or consultants, County shall have no liability whatsoever in connection therewith and shall not be responsible for any omissions or errors contained in the Construction Drawings, and Lessor's waiver and indemnity set forth in this Lease shall specifically apply to the Construction Drawings.

3.2 Final Space Plan. Prior to execution of the Lease by County, Lessor and the Architect shall prepare the final space plan for Leasehold Improvements in the Premises (collectively, the "Final Space Plan"), which Final Space Plan shall include a layout and designation of all offices, rooms and other partitioning, their intended use, and equipment to be contained therein, and shall deliver the Final Space Plan County for County's approval.

3.3 Final Working Drawings. Within ten (10) working days after execution of the Lease by County and delivery of a copy of the Lease to Lessor, Lessor, the Architect and the Engineers shall complete the architectural and engineering drawings for the Leasehold Improvements, and the final architectural working drawings in a form which is complete to allow subcontractors to perform the work and to obtain all applicable permits (collectively, the "Final Working Drawings") and shall submit the same to County for County's approval.

3.4 Permits. The Final Working Drawings shall be approved by County (the "Approved Working Drawings") prior to the commencement of the construction of the Leasehold Improvements. Lessor shall immediately submit the Approved Working Drawings to the appropriate municipal authorities for all applicable building permits necessary to commence and fully complete the construction of the Leasehold Improvements (the "Permits"). Lessor hereby agrees that neither County nor County's agents or consultants shall be responsible for obtaining any building permit or certificate of occupancy for the Premises and that the obtaining of the same shall be Lessor's responsibility; provided however that County shall, in any event, cooperate with Lessor in executing permit applications and performing other ministerial acts reasonably necessary to enable Lessor to obtain any such permit or certificate of occupancy. No changes, modifications or alterations in the Approved Working Drawings may be made without the prior written consent of County, provided that County may withhold its consent, in its sole discretion, to any change in the Approved Working Drawings if such



change would directly or indirectly delay the "Substantial Completion" of the Premises as that term is defined in Section 6.1 of this Leasehold Improvement Agreement.

3.5 County shall use its best, good faith, efforts and all due diligence to cooperate with the Architect, the Engineers, and Lessor to complete all phases of the Construction Drawings and the permitting process and to receive the permits, and approval of the "Construction Costs," as set forth in Section 7.1 below, as soon as possible after the execution of the Lease, and, in that regard, shall meet with Lessor on a scheduled basis to be determined by County, to discuss Lessor's progress in connection with the same. Upon County's execution of this Lease, Lessor shall provide County with a construction schedule including time projections for planning, entitlement process, related preparation and construction of the Leasehold Improvements.

#### **SECTION 4 – CHANGE ORDERS**

As outlined in Section 3 above, Lessor and County shall work with the Project Architect to complete the "Approved Working Drawings". If prior to commencement, or during the construction process, County wishes to make changes to the "Approved Working Drawings", County shall provide details of the requested change to the Project Architect. Architect shall then prepare the necessary plan of such material or construction change and submit to General Contractor for pricing. General Contractor shall prepare change order with price to complete the change order. County shall be responsible for the total cost of all approved change orders and shall pay to Lessor the total amount of all approved change orders within thirty (30) days from "Substantial Completion" of the premises.

#### **SECTION 5 - LESSOR COVENANTS**

5.1 Lessor recognizes, understands and covenants that any and all improvements shall be undertaken according to Exhibit "F", General Construction Specifications for Leased Facilities, attached thereto and made a part of the Lease.

5.2 Lessor recognizes, understands and covenants that improvements contemplated herein may be subject to the provisions contained in the California Labor Code (commencing with Section 1720) relating to general prevailing wage rates and other pertinent provisions therein.

5.3 Lessor shall comply and stay current with all applicable building standards, which may change from time to time, including but not limited to, the Americans with Disabilities Act of 1990 and any regulations issued pursuant thereto in providing improvements contemplated herein.

#### **SECTION 6 - CONSTRUCTION**

6.1 Lessor shall diligently pursue the planning, entitlement process, related preparation and construction of the Leasehold Improvements. Lessor shall provide

County with periodic written progress reports, which reports shall contain, without limitation, updated information relative to permit approvals and construction for the following leasehold improvements:

Lobby – Room #30:

Installation of carpet squares. VCT installed in lobby bathrooms and under drinking fountain. Security door to remain as keyed buzzer door. New window blinds. Possible wainscoating in bathrooms.

Nursery – Room #1:

New blinds installed. VCT throughout room. Cabinets (upper and lower cabinets) currently located in copy room in Suite 2A to be moved to nursery north wall next to windows.

Pantry in Nursery – Room #3:

New VCT installed.

Bathrooms – Rooms #2, #4, #20, #27, #28, #29:

VCT to be installed in all rooms.

#2 – no change in designation.

#4 – designated as Unisex Testing Restroom.

#20 – designated as Unisex Staff Only Restroom

#27 – designated as Unisex Testing Restroom

#28 – designated as Women's Restroom.

#29 – designated as Men's Restroom.

Hallways:

Carpet squares installed throughout all hallways (heavy traffic areas).

Group Rooms - #1 and #2:

Offices currently designated Office 2, 3, 5, 6, 8, & 9 will be split equally in footage and converted into two large group rooms with doors leading to the north and south hallways. Chair rails and carpet squares installed in both group rooms.

Moms Group Room – Room #7:

Carpet squares installed. Eraser boards removed for painting. Chairs rails installed.

Records Room – Room #22:

Carpet squares installed. Door on south side of Records Room to be removed and replaced with drywall. Dutch door located in copy room in Suite 2A to be moved and reinstalled on east wall of Records Room facing Break room for access to testing bathroom in adjacent hall and Supervisor's office. Cabinets (upper and lower) from Office #4 in Suite 2A reinstalled in Suite 6A to the Records Room west wall.

Clerical Area – Room #25:

Carpet squares installed in clerical area. Current furniture will remain. Countertops at

reception window to be resurfaced or replaced.

Storage and Copy Rooms – Rooms #23 and #24:  
VCT installed.

Offices – Rooms #9, #10, #11, #12, #13, #14, #15, #16, #17, #18, #21:  
All offices installed with “rolled goods” carpet.

Office #17:  
Remove barrier wall to convert to an office.

Office #21:  
Cabinets from Supervisor’s office in Suite 2A removed and reinstalled in Office #21.  
Two cabinets with countertop need to be installed on north wall under the window and two cabinets with countertop to be installed on south wall by door.

Break Room - #19:  
VCT installed. Cabinets under sink are water stained. Replace any damaged cabinets.  
Hinges on upper cabinets to be repaired to close properly.

Paint:  
All suites to be painted.

Suite 9B & 10B:  
Carpet squares installed throughout, except bathroom and kitchen. New VCT in kitchen. Paint both suites. Chair rails to be installed in the group room.

Flooring Base: All carpeted areas to have carpet base installed. All VCT areas to have rubber base installed.

6.2 Lessor shall notify County, in writing, forthwith when such planning, entitlement process, related preparation and construction of the Leasehold Improvements have been completed, a Certificate of Occupancy has been issued by the City of Cathedral City, or if no new Certificate of Occupancy is required, then upon acceptance of the improvements by the City of Cathedral City upon final inspection all required permits have been obtained and electrical power has been turned on. Within ten (10) days thereafter, County shall schedule and conduct a “job walk” with Lessor for the purpose of accepting the Premises for occupancy. County shall accept the Premises if the improvements are Substantially Complete and the Premises are available for useful occupancy, as hereinafter defined. County reserves the right to determine if the Premises are Substantially Complete and available for useful occupancy.

6.3 In addition, immediately after the Substantial Completion of the Premises, Lessor shall have prepared and delivered to the County (1) a complete set of "As-Built" drawings showing every detail, latent or otherwise, of such improvements, including but not limited to electrical circuitry and plumbing, and (2) the same complete set of "As-Built" drawings on a computer disk in a CADD format.

## **SECTION 7 - COMPLETION OF THE COUNTY IMPROVEMENTS; LEASE COMMENCEMENT DATE**

7.1 For purposes of this Lease, "Substantial Completion" of the Premises shall occur upon the completion of construction of the Leasehold Improvements in the Premises pursuant to the Approved Working Drawings, with the exception of any punch list items and any County fixtures, work-stations, built-in furniture, or equipment to be installed by County. Provided however, that such punch list items do not preclude the useful occupancy of the Premises. Useful occupancy herein defined as the Premises being safe, free of hazard, free of any risk to the safety of County employees and available for the use set forth in the Lease.

7.2 The Lease Commencement Date shall occur as set forth in Section 7.1, above.

## **SECTION 8 - CONSTRUCTION COSTS**

8.1 Prior to County's execution of this Lease, Lessor shall provide County an itemized cost breakdown of the construction costs of the leasehold improvements, attached hereto and made a part hereof as Exhibit B-1. The total costs of all the Leasehold Improvements subject to reimbursement, including but not limited to fixtures, equipment, architectural fees and permits, and as reflected in the cost breakdowns, shall not exceed the sum of \$116,488.00 which sum represents Lessor's estimate of such construction costs shown on Exhibit B-1 in the amount \$91,488.00 plus a contingency amount budgeted by the County for the sole purpose of paying for extra items requested by County during the course of construction or installation of leasehold improvements.

8.2 Upon completion of the Leasehold Improvements and within fourteen (14) days of Substantial Completion and acceptance of the Premises by County, Lessor shall provide County with an itemized statement, similar to the cost breakdown form attached as Addendum 1, of the actual costs of the Leasehold Improvements incurred by Lessor, accompanied by vendor, contractor, subcontractor, material man invoices if requested by the County along with request for reimbursement of actual costs incurred.

## **SECTION 9 - REIMBURSEMENT FOR LEASEHOLD IMPROVEMENTS**

9.1 County shall reimburse Lessor, as hereinafter set forth, within thirty (30) days, the actual cost of the Leasehold Improvements as substantiated by the itemized

statement required in Section 8.2 above and related supporting documentation as requested by the County. In no event shall Lessor be reimbursed an amount in excess of actual costs pursuant to Section 8.2 nor in excess of the total amount set forth in Section 8.1, whichever is less.

## **SECTION 10 - MISCELLANEOUS**

10.1 County's Entry Prior to Substantial Completion. Provided that County and its agents do not interfere with Lessor's work in the Premises, Lessor shall allow County access to the Premises prior to the Substantial Completion of the Premises for the purpose of County installing over standard equipment or fixtures (including County's data and telephone equipment) in the Premises. Prior to County's entry into the Premises as permitted by the terms of this Section 9.1, County shall submit a schedule to Lessor, for approval, which schedule shall detail the timing and purpose of County's entry. County shall hold Lessor harmless from and indemnify, protect and defend Lessor against any loss or damage to the Premises and against injury to any persons caused by County's actions pursuant to this Section 9.1.

10.2 County's Representative. County has designated its Assistant County Executive Office of the Economic Development Agency as its sole representative with respect to the matters set forth in this Leasehold Improvement Agreement, who, until further notice to Lessor, shall have full authority and responsibility to act on behalf of the County as required in this Leasehold Improvement Agreement.

10.3 Lessor's Representative. Lessor has designated Larry Langner as its sole representative with respect to the matters set forth in this Leasehold Improvement Agreement, who, until further notice to County, shall have full authority and responsibility to act on behalf of the Lessor as required in this Leasehold Improvement Agreement.

10.4 County's Agents. All subcontractors, laborers, material men, and suppliers retained directly by County shall conduct their activities in and around the Premises, in a harmonious relationship with all other subcontractors, laborers, material men and suppliers at the Premises.

10.5 Time of the Essence in this Leasehold Improvement Agreement. Unless otherwise indicated, all references herein to a "number of days" shall mean and refer to calendar days. In all instances where County is required to approve, if no written notice of approval is given within the stated time period, at the end of such period the item shall automatically be deemed not approved

10.6 Lessor's Lease Default. Notwithstanding any provision to the contrary contained in this Lease, if an event of default by Lessor of this Leasehold Improvement Agreement, and said default has occurred at any time on or before the Substantial

Completion of the Premises, then (i) in addition to all other rights and remedies granted to County pursuant to the Lease, County shall have the right to cause Lessor to cease the construction of the Leasehold Improvements and (ii) all other obligations of County under the terms of this Leasehold Improvement Agreement shall be forgiven until such time as such default is cured pursuant to the terms of the Lease or this Leasehold Improvement Agreement.


HR:jw  
01/14/10  
CC008  
13.135

County Drug Court  
 Cathedral City, CA  
 68625 Perez 9A 10B  
 68615 Perez 5,6,7

**IMPROVEMENT COST BREAKDOWN**

Item		Cost
Arch & Engr		\$3,500.00
Permits & Fees		\$1,000.00
Demo		\$750.00
Temporary Services		
Window Coverings		\$1,400.00
Roofing		
Steel Studs/Drywall		\$1,600.00
Insulation & Sound board		\$300.00
Ceilings		\$2,250.00
FRP Marlite		
Doors (Frames/Hardware/Install)		\$1,500.00
Miscellaneous		\$1,000.00
HVAC		\$2,500.00
Plumbing		\$500.00
Electrical		\$2,500.00
Fire/Life/Safety		\$2,500.00
Toilet Partions/Accessories		\$2,500.00
Glass/Mirrors/Storefronts		
Flooring		
Units 5,6,7 - VCT	\$3,150.00	
Units 5,6,7 - Broadloom	\$4,270.00	
Units 5,6,7 - carpet squares	\$12,420.00	
Units 5,6,7 - Base	\$3,150.00	
Units 9B & 10B - carpet squares	\$7,825.00	
Units 9B & 10B - VCT	\$350.00	
Units 9B & 10B - Base	\$2,000.00	
Total Flooring		\$33,165.00
Cabinets/Millwork		
Units 5,6,7	\$4,700.00	
Units 9B & 10B	\$1,800.00	
Total Cabinets/Millwork		\$6,500.00
Plaster		
Painting		
units 5,6,7	\$8,500.00	
units 9B, 10B	\$3,400.00	
Total Painting		\$11,900.00
Concrete sawing		
Clean-up		\$500.00
Signs		\$375.00
Construction Cost		\$76,240.00
Contingency - 10%		\$7,624.00
Supervision & Overhead		\$7,624.00
<b>Total Project Cost</b>		<b>\$91,488.00</b>

**EXHIBIT B**



NOT A PART OF THE WORK

Minimal Space Plan  
 58675 A Perez Rd.  
 Cathedral City, CA  
 Units 5,6,7

REVISED T.I. FLOOR PLAN

SCALE 1/8" = 1'-0"

A NEW T.I. OFFICE REMODEL  
 COUNTRY OF RIVERSIDE  
 MENTAL HEALTH OFFICES

EXHIBIT B



## ASBESTOS

- A. Lessor shall operate and maintain the below described spaces free of hazard from asbestos containing construction materials (ACCM's) as defined in Title 15, Sections 1601 and 2607 of the United States Code. An asbestos hazard will be recognized if an average concentration exceeds 0.01 fibers longer than five microns per cubic centimeter of air measured over an eight hour period as determined by the Transmission Electron Microscopy (TEM) method. TEM testing will be mandatory if samples tested by the Phase Contrast Microscopy (PCM) method indicate .1 or more fibers per cc of air.
1. Space leased to the County and plenums in the same HVAC zone.
  2. Common public areas which County employees or its invitees would normally/reasonably use.
  3. Building maintenance areas, utility spaces, and elevator shafts within or serving areas described in items 1 and 2 above.
- B. In the event construction of the building wherein leased premises are located was completed prior to 1979, the Lessor shall provide the County with certification that the areas referred to above are free of asbestos hazard from ACCM's prior to the execution of this lease. If said premises were constructed after 1979, Lessor shall provide County with a written statement to that effect.
- C. Certification shall be in the form of an ACCM's Survey and Evaluation Report prepared by a qualified Industrial Hygienist who shall be certified by the American Board of Industrial Hygiene (ABIH) or an Environmental Protection Agency (EPA) – Asbestos Hazard Emergency Response Act (AHERA) certified inspector. Said survey shall include those areas listed in paragraph (A). Survey requirements are: visual walk-through inspection and testing of suspected ACCM's. Bulk samples of suspected ACCM's shall be analyzed by a laboratory certified by the Department of Health Services and recognized by the EPA Quality Assurance Program using the polarized light microscopy (PLM) method. If friable asbestos is found or the physical condition of suspected ACCM's indicate possible fiber release, air sampling and testing by the Phase Contrast Microscopy (PCM) method must be performed. If asbestos fiber concentrations of .1 fibers per cc of air or greater are found, further testing by the Transmission Electron Microscopy (TEM) method is mandatory. Said survey and evaluation report shall identify all ACCM's found and recommend abatement procedures. If necessary, the report shall also specify guidelines for the implementation of an operation and maintenance plan inclusive of any required monitoring and testing intervals. The report is subject to review and approval by the County and the Lessor shall agree to all conditions contained therein.

- D. If at any time during the term of this lease, or during any extension or renewal hereof, previously unidentified ACCM's hazard is discovered, or airborne asbestos fibers above the maximum allowable limits are found to be entering the County-leased space from any other area within the building or buildings in which the County-leased space is located, the Lessor shall immediately, at Lessor's sole cost and expense, control such release and perform abatement of all hazardous ACCM's that are determined to be affecting the County-leased space.
- E. Lessor shall perform asbestos notification as required by Chapter 10.4 of the Health and Safety Code and shall guarantee that all abatement work as required under the conditions of this lease is performed by a licensed contractor certified by the Contractors State License Board and registered with the Division of Occupational Safety and Health. The County reserves the right to establish consultant oversight of any asbestos related work program at its expense.
- F. Additionally, Lessor shall be responsible for any and all direct or indirect costs associated with the abatement of the above described ACCM's which include, but is not limited to the actual costs to the Lessor for ACCM's abatement and for all required monitoring reports before, during, and after abatement. In effect, all costs shall be borne by the Lessor that are in any way associated with the abatement of ACCM's from the Lessor's building including clean up of contaminated County-owned equipment, furnishings, and materials. Copies of the air monitoring reports shall be furnished to the County together with certification by an Industrial Hygienist Consultant registered with Cal/OSHA that the area is free of hazard from ACCM's.
- G. If it is determined that for safety reasons its employees should be relocated at any time prior to or during the abatement of ACCM's, the Lessor shall provide comparable accommodating space (at no cost to the County) throughout the abatement process. Said determination shall be made by a qualified representative of Cal/OSHA. The Lessor specifically agrees to pay for all costs associated with this move or reimburse the County, if the County paid for this cost, including all reasonable administrative costs and cost of moving or renting furniture, data processing, and telephone equipment.
- H. In the event, after written notice is provided by the County, the Lessor fails, refuses, or neglects to diligently pursue abatement of above described asbestos hazard from ACCM's, the County may effect such abatement; and, in addition to any other remedies it may have, deduct all reasonable costs of such abatement and all costs associated in any way with the abatement of the above described ACCM's from the rent that may then be or thereafter become due throughout the term of this lease. For this purpose and as a condition of this lease agreement, the Lessor shall obtain an EPA generator number and grant license to the County for its use.

- I. In addition to any other remedies it may have, in the event the Lessor fails to diligently pursue abatement of asbestos hazard from ACCM's, as required under the provisions of this lease, the County may, by notice in writing, terminate this lease. Lessor shall be liable to the County for all expenses, losses, and damages reasonably incurred by the County as a result of such termination; including, but not limited to additional rental necessary to pay for an available similar replacement facility over the period of what would have been the remaining balance of the lease term plus any option periods, costs of any necessary alterations to the replacement facility, administrative costs, and costs of moving furniture, data processing, and telephone equipment.
  
- J. The Lessor shall indemnify, defend, and hold the County of Riverside, its officers, and employees harmless from and against any and all losses, damages, judgements, expenses (including court costs and reasonable attorney fees), or claims whatsoever, arising out of, or in any way connected with or related to, directly or indirectly, the presence of asbestos hazard from ACCM's within the County-leased space or the building in which the leased premises are located.

**EXHIBIT "D"**  
**CONFIRMATION OF LEASE INFORMATION**

1. LEASE REFERENCE DATE: \_\_\_\_\_
2. DEPARTMENT: \_\_\_\_\_  
PREMISES: \_\_\_\_\_
3. COMMENCEMENT DATE: Construction of the leasehold improvements is substantially complete and the lease term shall commence as of \_\_\_\_\_. The official anniversary of this Lease as provided under the rent provision shall be \_\_\_\_\_ 1, \_\_\_\_\_. The original term of the Lease expires \_\_\_\_\_, unless extended as provided in the Lease.
4. RENT: In accordance with the Lease, Rent began to accrue on \_\_\_\_\_, in the initial amount of \_\_\_\_\_. Rent is due and payable in advance on the first day of each month during the Lease Term.

AGREED and ACCEPTED

**LESSOR:**

**COUNTY:**

\_\_\_\_\_  
Dated: \_\_\_\_\_

\_\_\_\_\_  
Dated: \_\_\_\_\_

**EXHIBIT D**

**COUNTY OF RIVERSIDE**  
**Department of Facilities Management**  
**Real Estate Division**

**CUSTODIAL SERVICES REQUIREMENTS**  
**FOR LEASED FACILITIES**

1. Background checks shall be performed, in a manner specified by County, of all qualified permanent and temporary employees.
2. Provide all required services and supplies.
3. Perform services five days a week during the hours of 5:00 pm to 1:00 am only.
4. Provide and replace all fluorescent light tubes and incandescent light bulbs using only those types of tubes and bulbs that are energy efficient as indicated by manufacturer. Fixture reflectors shall be wiped clean with each relamping.
5. Lessor and custodial staff shall be responsible for key control. Issuing keys to workers, collecting said keys at shift end and retrieving keys at the end of custodian's employment. If keys are lost, stolen or misplaced, rekeying costs are landlord's responsibility.
6. **SPECIFIC SERVICES** – Frequency and coverage:
  - A. **Daily:**
    1. Rest Rooms:

Empty all trash containers, refill dispensers, damp mop floors, clean, sanitize and polish all plumbing fixtures, chrome fittings, flush rings, drain and overflow outlets, clean and polish mirrors, clean wall adjacent to hand basins/urinals, dust metal partitions, remove finger prints from walls, switches, etc.
    2. Lobby Area – Main Corridors – Stairways:

Remove trash, vacuum, vacuum/damp mop tile, clean lobby and entrance doors, clean and sanitize drinking fountains.
    3. Employee Break Rooms/Kitchen:

Remove trash from building and deposit in dumpster, vacuum rugs and carpet, wipe spills, mop tile floor, remove fingerprints from doors, light switches, etc., and refill dispensers.
    4. General and Private Areas:

Remove trash, vacuum carpets, mop tile floors, spot clean interior partition glass, clean counter tops and blackboards, dust desks, conference tables, credenza/file cabinets and bookcases.

5. Building Security:

- a. Turn off all lights (except security and night lights).
- b. Close windows.
- c. Reset alarms and lock all doors.

**B. Weekly – All Areas:**

Polish buff hard resilient floors in traffic areas, spot clean carpeted areas.

Dust all high and low horizontal surfaces, including sills, ledges, moldings, shelves, locker tops, frames and file cabinets, damp wipe plastic and leather furniture.

Remove fingerprints from doors, elevator walls and controls, frames and light switches in office areas, clean and polish bright metal to 70" height, clean and sanitize waste containers in rest rooms and break rooms.

**C. Monthly – All Areas:**

Clean interior glass partitions/doors, dry dust wood paneling, remove dust/cobwebs from ceiling areas.

Spray buff resilient/hard floor areas, detail vacuum carpet edges, under desk/office furniture.

**D. Quarterly – All Areas:**

Spray buff resilient and hard surface floors and apply floor finish.

Clean interior/exterior windows, clean/polish office furniture, damp clean diffuser outlets in ceiling/wall, wash waste containers, clean/dust blinds, wash sanitize.

**E. Semi-Annually – All Areas:**

1. All Areas:
  - a. Clean and polish all baseboards.
  - b. Damp clean lobby and reception chairs.
  - c. Clean carpeted surfaces-use a water extraction method.

**F. Annually – All Areas:**

1. All resilient and hard surface floors:
  - a. Move furniture, strip, seal and apply floor finish to all resilient and hard surface floors.

**COUNTY OF RIVERSIDE  
DEPARTMENT OF FACILITIES MANAGEMENT  
Real Estate Division**

**GENERAL CONSTRUCTION SPECIFICATIONS  
FOR LEASED FACILITIES**

**A. INTENT**

1. It is the intent of these instructions to convey to the Lessor and his bidders the construction requirements for obtaining a complete and usable facility under lease agreement. These instructions apply to all new construction (build-to-suit), alterations and repair and/or renovation in facilities leased to the County of Riverside.
2. All references to the County in this or any other specification means the Director of Facilities Management or his designee.
3. All work in accordance with these specifications or any other specifications and plans must be coordinated with the Director of Facilities Management or his designee. Specifications contained on or with specific plans for construction may contain more stringent provisions than the minimum requirements stated herein. The more stringent requirements shall govern.
4. When fully justified, Lessor may request waiver of any portion of these specifications. Such requests must be submitted in writing to the Department of Facilities Management with full justification. All specifications will be enforced unless specifically waived by the Department of Facilities Management in writing.

**B. COMPLIANCE WITH LOCAL REGULATIONS**

1. In the absence of such codes, ordinances or regulations, the Lessor's contractor shall use the latest edition of the "Uniform Building Code". However, when such local, County or State requirements contain more stringent provisions than the minimum requirements stated herein, the more stringent requirements shall govern.
2. The Lessor shall, without additional expense to the County, be responsible for obtaining and paying for any necessary construction fees, licenses and permits required for privately owned buildings. Lessor shall comply with any applicable Federal, State and Municipal laws, codes, and regulations in connection with the prosecution of the work, and shall take proper safety and health precautions to protect work, the workers, the public, and the property of others.
3. All work in accordance with these specifications must be done in strict compliance with the Americans with Disabilities Act of 1990 and any regulations issued pursuant thereto.

**C. DRAWINGS**

1. A site plan, clearly indicating employee, visitor and open parking spaces, shall be prepared. Floor plans, elevations, mechanical and electrical drawings shall be prepared, preferably at one eighth inch (1/8") scale.
2. The Department of Facilities Management shall be provided four (4) complete sets of the aforementioned drawings and specifications for review and approval.
3. Prior to start of construction, two (2) complete approved sets of construction plans and specifications shall be provided to the Department of Facilities Management. These sets shall be

signed to indicate approval by Information Technology and the user department. One set will be returned to Lessor for construction, the second set shall be retained by Department of Facilities Management.

4. Any changes or deviation from the approved plans and specifications will not be accepted without prior written approval from the Department of Facilities Management.

D. **CONSTRUCTION**

1. A pre-construction conference with Lessor, contractor and County shall be conducted at a mutually agreed-upon site for reviewing and defining the construction requirements.
2. Inspections by the Department of Facilities Management will be conducted at random times during the course of construction. The successful bidder shall maintain, on the job site, a complete set of approved final drawings and specifications marked up to show any changes and as-built conditions. Normally, three (3) unscheduled and one (1) final inspection will be conducted. At the final inspection, a punch list will be developed, and any deficiencies noted will be corrected prior to County's acceptance of the facility.

E. **SPECIFICATIONS**

1. The Lessor shall be responsible, in all cases, for the proper design and coordination of architectural, structural, plumbing, electrical, heating, ventilation, air conditioning, site elements, etc., of the proposed facility. Accessibility for physically handicapped is required, unless specifically waived in writing by the Department of Facilities Management.
2. Lessor shall verify the accuracy of all dimensions, and he shall be responsible for correcting and recording any discrepancies.

**(SITE REQUIREMENTS)**

A. **SITE**

1. The Lessor shall be responsible for determining site conditions, including sub-surface soil conditions, adequate public utilities and load-bearing characteristics, the installation of retaining walls, demolition, relocation of utilities, and other site improvements.

B. **GRADING**

1. The finish grades and contours shall be correlated with street and sidewalk grades established by the local municipality. Floors, driveways, etc., shall be adjusted by the Lessor's architect as necessary, to insure property clearances, surface drainage, slope gradients, storm and sanitary sewer gradients and connections. All paved areas shall be graded as necessary to provide positive drainage of surface runoff water away from the buildings.

C. **DRAINAGE**

1. Walks, parking areas, driveways and maneuvering areas shall be provided with positive natural drainage whenever possible. The floor of the building and adjacent grades may be raised sufficiently to provide natural drainage.

D. **RETAINING WALLS**

1. The determination of the location and extent of retaining walls required is the responsibility of the



Lessor.

**E. LANDSCAPING**

1. Suitable regionally appropriate, water conserving, low-maintenance planting shall be provided. Preservation of existing vegetation and the providing of additional landscaping shall meet local environmental requirements.

**F. CLEANUP**

1. Upon completion of the facility and prior to move-in and acceptance for lease by the County, the Lessor shall clean, seal and wax floors, clean windows, fixtures and finishes, interior and exterior, and remove surplus materials and debris from the site.

**(ARCHITECTURAL REQUIREMENTS)**

**A. FLOORS**

1. Floor elevations shall be at least eight inches above finished exterior grade whenever possible. When floor slab is below grade, it shall be waterproof.
2. Floors shall be designed in accordance with uniform, concentrated and special loads given in the "Uniform Building Code", chapter 23.
3. Carpet – One hundred percent (100%) continuous filament nylon or olefin with static control; minimum yarn weight - 28 oz. Require statement of pile weight from vendor or manufacturer. Minimum five (5) year warranty excluding the use of protective chair pads against ten percent (10%) surface wears when properly maintained. Four inch (4") rubber cove base shall be used for base in all carpeted areas. Colors/patterns must be approved by the Department of Facilities Management.
4. Carpet tiles may be used. Pile weight 28 oz. static control 2.0 K.V. or less. Color shall meet County color standards.
5. Non-carpeted floors - rest rooms, coffee rooms, etc., shall have sheet vinyl covering, including base. Vinyl tile may be used in other non-carpeted areas. Vinyl shall be commercial grade with colors and patterns full depth. Colors/patterns of sheet vinyl and vinyl tile must be approved by the Department of Facilities Management.

**B. WALLS**

1. Interior walls - all interior partition construction shall comply with applicable Federal, State, County and City codes. The types of interior partitions to be used must be approved by the Department of Facilities Management. Systems furniture may be used.
2. Toilet room walls adjacent to occupied spaces shall be sound insulating double-wall construction and filled with sound-absorbing materials.
3. Exterior walls - Exterior walls constructed of wood or steel stud shall be insulated to R-11 specifications.

**C. ROOF AND INSULATION**

1. Roof construction and insulation shall be appropriate to the overall design of the building and

prevailing weather conditions. Light colored materials are encouraged.

2. All roof designs shall include a minimum one-half inch (½") to one foot (1') slopes for positive drainage.
3. Roofs on existing buildings shall be subject to (a) an inspection by a licensed roofing contractor, (b) County's review of roofing contractor's findings and (c) proof of corrective action.

D. **TIMBER AND WOOD**

1. All lumber used structurally shall be stress-graded with the stamp of the Lumber Association indicated on each piece showing the stress grade.

E. **CEILING CONSTRUCTION**

1. All ceilings shall be placed at nine feet (9'0") above finish floor level, unless otherwise specified.
2. A suspended acoustical ceiling system with integrated lighting shall be installed in all occupied areas.
3. Rest rooms and coffee rooms shall have solid ceilings (drywall, etc.).

F. **WINDOWS**

1. Windows shall generally be limited to the lobby area and offices.
2. Glazing that extends below thirty-two inches (32") above the floor shall be protected with a horizontal railing or similar safety barrier. Individual windows may be metal or wood of commercial quality. All window openings shall be properly flashed to prevent moisture intrusion.
3. Low energy and reflective glazing shall be used in high heat gain areas.

G. **DOORS**

1. Exterior doors - all wood doors will be solid core. Exterior doors will be weather-stripped and have stops. Exterior doors to be not less than thirty-six inches (36") wide. Appropriate metal doors are acceptable.
2. Exterior doors shall have automatic closers.

H. **CABINET WORK**

1. Cabinet work shall conform to the standards as defined in the Woodwork Institute of California, Manual of Millwork, (reference "WIC #102", standard cabinet design).
2. Acceptable cabinet work quality is laminated plastic covered deluxe (D) grade, or wood factory finished deluxe (D) grade, except utility (U) grade in utility storage areas.
3. Countertops and splashes shall be laminated plastic, custom grade, self-edge trim. Minimum four inch (4") high splashes where abutting vertical wall surfaces.
4. Cabinet work to be complete with knobs, pulls, hinges, catches, etc.
5. Colors/patterns of laminated plastic and finishes of casework must be approved by the

I. **HARDWARE**

1. Hardware will be of good commercial quality grade and type. Automatic door closers shall be provided on public and employee entrance doors, toilet room doors, and coffee room doors. Public entrance and glazed partition lobby doors shall be equipped with push bars with integral PUSH AND PULL signs. Toilet and coffee room doors will have push plates and door pulls. When public entrance, lobby, toilet or coffee room doors are wood or metal with enameled finish, kickplates shall be provided. At buildings where only one (1) toilet is provided, the door closer will be omitted and the door fitted with a privacy lockset. Door locks will be operable by a master key system. Panic hardware must be installed where required by code. Simplex cipher locks (or equal) may be used in lieu of keyed locks when approved by the Department of Facilities Management.
2. Exterior doors with hinges exposed to the public (out- swinging doors) will be equipped with door butts that have "fast" pins to prevent removal or tampering.
3. All doors to be provided with adequate hardware. Interior door locksets to be provided only where indicated on plans. Interior doors to be provided with doorstops.
4. Double doors (pair) - shall be avoided on exterior openings wherever possible. When pair is required by design, use removable mullion, unless specifically approved otherwise.
5. Exterior doors - all exterior doors must have a deadbolt lock, except where panic hardware is required.
6. Door lock keying - Simplex or equal may be substituted for keyed locks when approved by the County.
  - a. All keyed locks shall be equipped with six (6) pin keyways.
  - b. Three (3) keys shall be furnished for each lock.
  - c. All locks shall be keyed as specified by County, except that all locks within the following individual groups shall be keyed alike:
    - (1) Mechanical equipment rooms.
    - (2) Janitor's closets.
    - (3) Employee entrances (interior & exterior).
    - (4) Bulletin boards.
    - (5) Electrical panel boxes.
  - d. A master key system shall be provided and three (3) master keys shall be furnished, unless otherwise specified.
  - e. Keying - locks will incorporate a security system to assure that keys used during construction will not open doors after County occupancy. The key side of all locks will be on the public side.

J. **TOILET ENCLOSURES AND ACCESSORIES**

Facilities must comply with all existing codes.

1. All toilet and urinal enclosures shall be secured to the floor and ceiling.
2. Doors shall be installed in men's and women's restrooms. Entrance doors to toilet enclosures shall be fitted with specific locking devices. Toilet enclosures for non ADA stalls shall be 34" wide, or more, on all new construction.
3. Each toilet compartment shall be provided with a metal coat hook and double roll toilet paper holder, suitable for dispensing rolled tissue.
4. Install one single-fold paper towel or roll towel dispensing cabinet for each multiple of two (2) lavatories or less in all rest rooms. Towel dispensers shall be designed to dispense paper towels.
5. Each pair of lavatories in all rest rooms shall be provided with soap dispensers.
6. Each lavatory in all rest rooms shall be provided with a 24" x 30" wall-mounted mirror. Provide a stainless steel shelf at each mirror.
7. Women's rest rooms shall be provided with feminine napkin dispenser. Women's toilet compartments shall be provided with one (1) feminine napkin disposal container.
8. Trash bins shall be provided in rest rooms.
9. Both men's and women's toilets shall be designed and constructed to accommodate the physically handicapped. One water closet compartment shall be sized to meet handicapped requirements, provided with out swinging door and grab bars. The toilet fixtures, lavatory, mirrors, etc., shall be located at the correct height for handicapped.

K. **PAINTING**

1. All exterior painted surfaces shall be given a minimum of two (2) coats. Colors must be approved by the Department of Facilities Management.
2. Interior surfaces and trim shall be given two (2) coats minimum. One hundred percent (100%) coverage required. Prefinished acoustical ceiling shall not be painted. Finish coat shall be in accordance with colors as prescribed by County and shall match color chips.
3. Paint colors must be approved by the Department of Facilities Management.
4. All interior painted surfaces shall receive two (2) coats of semi-gloss enamel.
5. Wall coverings other than painted surfaces (i.e., wood paneling, vinyl material, etc.) shall be permitted. Location and colors must be approved by the Department of Facilities Management.
6. Parking strips four inches (4") wide of highway traffic paint are to be provided.
7. Street number - Minimum six inches (6") high number - by Lessor.

L. **WINDOW TREATMENT**

1. Minimum treatment - Vertical blinds or other as specified by the Department of Facilities Management.

**M. SIGNS**

1. Identification sign to be installed on exterior of building. Sign will be specifically identified by the Department of Facilities Management. Placement and specific size of letters will be determined according to layout and location of structure. Letters will be black injection molded plastic, Helvetica in style.
2. Interior signs to be black phenolic material laminated with white letters. Signs will be specifically identified by the Department of Facilities Management.
3. Lettering on entrance doors will be specifically identified by the Department of Facilities Management.

**N. ASBESTOS & LEAD BASED PAINT**

1. All buildings constructed prior to 1978 will have asbestos and lead based paint check to ascertain that no friable asbestos or flaking lead based paint is in evidence. A copy of the report is to be filed with the Department of Facilities Management.

**O. PLUMBING FIXTURES AND FITTINGS**

1. All rest room lavatories shall have self-closing faucets.
2. All toilets and urinals shall be equipped with flush valves.
3. Refrigerated water fountains - provide refrigerated water fountains at location indicated.
4. "Water-Saver" toilets will not be acceptable.
5. Provide hot water in rest rooms and break rooms.
6. Health Clinics-provide hot water in examination rooms, labs, rest rooms and break rooms.
7. All work in accordance with these specifications must be done in strict compliance with the Americans with Disabilities Act of 1990, the California Title 24 section which implements it, and any regulations issued pursuant thereto.

**P. FIRE PROTECTION**

1. Provide all necessary fire extinguishers as required by local fire regulations.
2. Provide sprinkler inspection and test prior to occupancy.
3. Provide all other necessary protective devices and equipment as required by local fire regulations.
4. Building alarms and fire monitoring equipment shall not be installed in the telephone/data room without written permission of the IT Department.

**Q. ELEVATORS**

1. Provide documentation of inspection and routine maintenance prior to and during occupancy.

**SPACE CONDITIONING**  
**(Heating, Ventilation and Air Conditioning)**

**A. GENERAL REQUIREMENTS**

1. Space conditioning shall be considered the year-round control of temperature, humidity, air circulation, ventilation and air cleaning to the degree required to assure satisfactory and efficient use of the space for occupants and equipment. Follow good accepted practices as reflected in the latest issue of the American Society of Heating, Refrigeration and Air Conditioning Engineer's Guide (ASHRAE).

**B. VENTILATION**

1. Ventilation for air-conditioning system - Provide ventilation makeup air in the amount of 10% of total air requirement for cooling or two (2) air changes per hour, whichever is greatest, plus all exhaust air requirements.
2. Prior to construction of office space over 5,000 square feet, existing systems over ten (10) years of age shall be inspected by a licensed HVAC company and a statement of condition detailing the reliability and efficiency of the systems shall be provided.

**C. EXHAUST SYSTEMS**

1. Exhaust toilet areas - the exhaust fan shall be connected to the light switch or interconnected with the air conditioning time clock.
2. Air shall not be directly exhausted, except in the following instances:
  - a. Air used to make up exhaust for toilet rooms.
  - b. Air exhausted specifically for cooking, food preparation or removal of excessive heat generated by vending or various other machines.
  - c. When specified for coffee rooms.

**D. SPACE TEMPERATURE CONTROLS**

1. Central control system for the various areas or provide a thermostat for each heating and/or air-conditioning system. Use separate slide lever adjustments for heating and cooling with lock covers.
2. All systems shall be controlled by seven (7) day, twenty-four (24) hour time clocks set to the Department of Facilities Management requirements.
3. Thermostats controlling space conditions during occupied hours shall be adjustable from sixty eight degrees (68°) to eighty degrees (80°) with the normal set at seventy degrees (70°) for heating and seventy-six degrees (76°) for cooling.
4. Simultaneous heating and cooling will not be acceptable.
5. Lessor shall comply with existing codes.
6. Heat-generated equipment shall be of adequate capacity to heat the building under design conditions.

7. All gas furnaces shall be approved by the American Gas Association.
8. All electric components shall be UL-approved and comply with the California Electric Code.
9. Electric strip heating is not acceptable.

E. **AIR FILTERS**

1. All recirculated and outside air shall pass through filters before entering air-handling units.
2. Filters shall be replaceable types and changed a minimum of four (4) times a year.
3. A location map showing filter locations shall be provided to County.

F. **PIPING**

1. Piping in finished areas, such as lobbies and offices, shall be concealed. No water piping of any description shall be installed near electrical switchgear. Provide shutoff valves at all locations necessary to isolate separate zones of the system served.
2. All hot and chilled water piping shall be insulated.

G. **AIR DISTRIBUTION**

1. Ductwork shall be provided, as required, for proper air distribution with supply outlets spaced so as to avoid excessive throws and dead spots. In order to maintain sound privacy, door louvers will not be used to return air from offices. Sound-attenuating, acoustically lined transfer ducts or return air ducts must be used. All supply and return air ductwork shall be constructed and installed in accordance with ASHRAE Standards and shall comply with state and local building codes.
2. All air handling units, except unit heaters, must be provided with outside air intakes. Intakes shall be located to avoid the introduction of boiler flue gases or vehicle and condenser unit exhausts.
3. Diffusers shall be selected and spaced so that, at the occupied level, the movement of air will be uniform and not be less than ten (10) cubic feet per minute, nor more than fifty (50) cubic feet per minute when measured at four feet (4") above the floor. They shall be selected so that the throw from an air diffuser does not impinge on walls, columns, or the throws from other diffusers based on a terminal velocity of one hundred feet (100') per minute. Diffusers located in offices shall be of the fully adjustable air pattern type.

H. **BALANCING AND ADJUSTING**

1. Space conditioning equipment shall be balanced and adjusted by persons certified to perform such functions prior to occupancy.
2. Copy of air balance report shall be provided to the Department of Facilities Management.

I. **NOISE AND VIBRATION**

1. Particular care shall be exercised in the design, selection and installation of all mechanical equipment and components to attain reasonable noise levels in occupied space. In general, sound levels for various spaces shall be maintained in accordance with the recommendations of

the ASHRAE Guide.

**J. OPERATING INSTRUCTIONS**

1. The Lessor shall provide simplified consolidated equipment and control diagrams with specific operating instructions posted on a readily accessible label on each utility system, such as furnaces, refrigeration equipment, air handling systems, and pumping systems. These instructions shall clearly indicate how to stop and start systems, what adjustments must or may be made by County personnel to assure proper operation, and what action shall be taken in emergencies.

**(ELECTRICAL)**

**A. GENERAL REQUIREMENTS**

1. All electrical work shall be designed and installed in accordance with the plan requirements.
2. Codes and ordinances - shall conform to standards of the National Electrical Code (NEC), O.S.H.A., serving public telephone company, State Fire Marshal and local ordinances.
3. Service equipment shall be located in separate electrical/mechanical room with proper working clearances and grounding. All breakers shall be clearly identified.

**B. INTERIOR LIGHTING**

1. Fluorescent lamps shall generally be 34 watt, 430-milli-amp, rapid-start, cool-white, including energy efficient ballasts.
2. The lighting shall be designed to maintain a uniform level of illumination of the minimum foot - candles designated. Lighting levels shall be based on working plan thirty inches (30") above floor, appropriate coefficient of utilization for the fixture and maintenance factor. Conform to Title 24, Division 9 for lighting requirements. Provide not less than ten foot-candles in halls, thirty foot-candles in rest rooms and fifty foot-candles in all other areas, unless specifically noted otherwise. (eighty foot-candles in drafting room areas).
3. Each working space, utility or storage room shall have at least one receptacle. Each office shall have a minimum of one (1) receptacle on each twelve feet (12') of wall space. See plans for additional and/or special outlets.
4. Provide twenty-four (24) hour lighting for security.
5. Emergency lighting - Shall be provided where required by applicable codes, or natural lighting will not provide sufficient lumens for emergency exiting of building.

**C. EXTERIOR LIGHTING**

1. Install sufficient lighting to provide a minimum of five (5) foot-candles of illumination at each building entrance, around the perimeter of the building, in the parking and maneuvering areas and on driveways.
2. All exterior lighting shall be high or low-pressure sodium as specified by the County. Fixtures shall be controlled by photocell, time clocks, or combinations of both.



## (TELEPHONE AND COMMUNICATIONS)

(Updated November 10, 2008)

### A. GENERAL REQUIREMENTS

1. All communications requirements shall conform to the standards of Riverside County Information Technology (RCIT) and the serving public telephone company as noted below.
2. **The RIVERSIDE COUNTY INFORMATION TECHNOLOGY (RCIT) COMMUNICATIONS BUREAU TELECOMMUNICATIONS ENGINEER shall be consulted during the Programming, Conceptual Design, Design Development, and Construction Design stages to plan the design and provide input for the Telecommunications Infrastructure.**

### B. TELECOMMUNICATIONS ROOM SPECIFICATIONS

1. **Dedicated Use: Telecommunications Rooms must be dedicated to the telecommunications function and related support facilities.** Equipment not related to the support of the Telecommunications Room, such as piping, duct work, and distribution of building power, must not be located in, or pass through the room. The Telecommunications Room may not be shared with building or custodial services. Cleaning materials such as mops, buckets or solvents must not be located or stored in the Telecommunications Room. Building alarms, fire monitoring equipment and building automation equipment shall not be installed in the Telecommunications Room without written permission of the RCIT Communications Bureau Telecommunications Engineer. In the event the RCIT Communications Bureau Telecommunications Engineer grants such permission, all building alarms and fire-monitoring equipment shall be installed only in the location designated.
2. **Room Physical Specifications - the room must be completed a minimum of thirty (30) days prior to occupancy.** Large projects (more than 20,000 sq. ft.) will require the Telecommunications Room (s) to be completed a minimum of 45 days or as directed by RCIT Communications Bureau Telecommunications Engineer prior to beneficial occupancy. All specifications for said room as outlined in this agreement shall be completed, including, but not limited to, installation of plywood, lighting, electrical circuits, HVAC, ceiling tiles, ground, floor tile and door with lock and three (3) sets of keys.

**It should be understood that the contractor will have to schedule various trades in sooner than the normal construction schedule to complete the Telecommunications Room (HVAC, Electrician, Painter, etc.) as required by the RCIT Communications Bureau Telecommunications Engineer.**

- a. **Location:** The Telecommunications Room shall be as close to the geographic center of the occupied space as possible. **Maximum distance from the center of the Telecommunications Room to the farthest WAO location shall not exceed a radius of 175 feet** unless reviewed by RCIT Communications Bureau Telecommunications Engineer. If occupying more than one floor of a building, **a separate Telecommunications Room shall be required on each floor**, preferably stacked above one another. Provisions shall be made available for easy access into the Telecommunications Room for telephone and data wiring and shall be dedicated for telephone and data use only. Telecommunications Rooms should not be planned next to elevators, restrooms, electrical rooms, air shafts, mechanical rooms, and outside walls. If occupying more than one building, each building will require Telecommunications Rooms that meet the above requirements.
- b. **Minimum Room Sizes:** The Telecommunications Room shall be rectangular in shape

and conform to the following inside room dimensions:

<u>Leased Premises – sq. ft.</u>	<u>Room Size</u>
5,000 sq. ft. or less	12' x 9'
5,000 – 10,000 sq. ft.	12' x 12'
10,000 – 30,000 sq. ft.*	12' x 14'
30,000 sq. ft. or larger**	12' x 14'

\* May require more than one room

\*\* Will require more than one room.

- c. **Plywood Wall Lining:** All walls will be lined with AC grade or better, void-free, 4'x8' sheets of 3/4" plywood. Plywood sheets shall be mounted vertically from ceiling height towards floor. Plywood must be painted on all sides with one coat of primer and two coats of white fire resistant paint. The plywood should be installed with the grade "C" surface facing the wall.
- d. **Doors:** The door will be a minimum of three (3) feet wide and 80 inches tall and be located as near as possible to a room corner. The door shall be equipped with a lock. Where practical, the door should open outward to provide additional usable space.
- e. **Air Conditioning:** The environmental control systems for the Telecommunications Room should be able to maintain a room temperature between 18°C and 24°C (64°F and 75°F) at all times (24 hours per day, 365 days per year). All building supplied HCAC inlets to the Telecommunications Room shall be controlled using a Variable Air Valve (VAV) with its own thermostat to prohibit heating the Telecommunications Room. The VAV will be installed in such a fashion to introduce conditioned air if the primary split A/C unit fails to cool the room. It will serve two purposes:
1. Provide ventilation air to the room, cooling only.
  2. Serve as a additional backup.
- If a building's HVAC system cannot ensure continuous operation (including weekends and holidays), provide a standalone HVAC unit with independent controls for the Telecommunications Room. If an emergency power source is available in the building, connect the HVAC system that serves the Telecommunications Room to the emergency power source. Sensors and controls must be located in the Telecommunications Room, ideally placed 5 feet AFF (thermostat location will be specified on the Telecommunications Room drawing provided by RCIT Communications Bureau Telecommunications Engineer). If an in-room air conditioner is installed, the air conditioner will be hard wired to the thermostat and the location must be approved by RCIT Communications Bureau Telecommunications Engineer before installation. If remote-monitoring equipment is available, this room should have its own independent sensor. Average heat load for equipment is approximately 150 BTU/SQ Ft of Telecommunications Room space (specific heat load will be provided for each room).
- f. If **fire sprinklers** are located in the Telecommunications Room, the sprinkler shall have a high temperature standard response full circle head with a heavy-duty cover. Sprinkler lines located inside the TR shall not be "charged" under normal conditions. Coordinate placement of the sprinklers with RCIT Communications Bureau Telecommunications Engineer. Sprinkler heads must be a minimum of 10 ft. AFF.
- g. **Room Lighting** – Lighting to provide a minimum of 500 lux (50 foot candles) measured 3 ft. AFF. Coordinate placement of light fixtures with RCIT Communications Bureau Telecommunications Engineer to avoid interference with low voltage equipment. Light

fixtures must be a minimum of 10 ft. AFF. Use white paint on the walls and ceiling to enhance room lighting. Power for the lighting should not come from the power panel located inside the Telecommunications Room.

- h. **Emergency Lighting** – Emergency lighting within the Telecommunication Room shall be provided to ensure that the loss of power to normal lights will not hamper an emergency exit from the room.
- i. **Floors:** The floor shall be capable of supporting a minimum load bearing of one hundred (100) pounds per square foot and maximum concentration loading of 2,000 lbs. per foot. Standard VCT floor covering shall be installed unless otherwise specified.
- j. **Ceiling:** If a ceiling will be installed in the Telecommunications Room it must be installed at a **minimum of 10' AFF**. Ceiling protrusions (e.g. sprinkler heads) must be placed to assure a minimum clear height of 10 feet that is clear of obstructions, to provide space over the equipment frames for cables and suspended cable trays. Ceiling finish must minimize dust and be light colored to enhance the room lighting. A hard ceiling shall not be allowed in the Telecommunications Room.

### C. ELECTRICAL REQUIREMENTS

- a. **Dedicated Power Feeder** – The Telecommunications Room will have its own dedicated power feeder terminated in an electrical panel located inside the room and flush mounted in the wall. **Location of this electrical sub-panel shall be closely coordinated with RCIT Communications Bureau Telecommunications Engineer to ensure it does not impact the overall design and use of the space within the room. Power required for other equipment in the room (e.g. fluorescent lighting, motors, air conditioning equipment) should be supplied by a separate feeder, conduit, and distribution panel.** If an emergency power source is available, connect the Telecommunications Room electrical sub-panel into it.
- b. **General Purpose Outlets:** Provide 110 Volt, 20 Amp duplex outlets installed at standard height on all walls of the Telecommunications Room; maximum spacing between outlets shall not exceed 12 feet.
- c. **Telephone System:** Install one (1) dedicated 208 VAC, 20 Amp circuits terminated into a single surface mounted 4S electrical box with a NEMA L6-20 outlet at a height of 18 inches AFF from center. The circuit will have its own separate hot, neutral, and ground wire all the way back to the power distribution panel. The circuit will be clearly labeled on the cover plate and sub-panel.
- d. **Equipment Racks:** Install two (2) dedicated 20 Amp, 110 VAC circuit with isolated ground for each equipment rack (9' x 12' room – 2 racks, 12' x 12' room – 3 racks, 12' x 14' room – 4 racks). Install one (1) dedicated 30 Amp, 208 VAC circuit with isolated ground for every two equipment racks. The breaker number shall be identified on each of these outlets. Terminate each circuit on double duplex outlets in a surface mounted 4S box in the vertical cable manager 23" above the floor. Equipment Rack locations, circuit locations and quantity will be specified in the room layout provided by the RCIT Communications Bureau Telecommunications Engineer.
- e. **Paging – AV: If required, install** one dedicated 20 Amp, 110 VAC circuit with isolated ground. Terminate on a double duplex outlet in a 4S box. The location of the outlet will be specified in the Telecommunications Room layout provided by the RCIT Communications Bureau Telecommunications Engineer.

- f. **Security:** Install one dedicated 20 Amp, 110 VAC circuit with isolated ground. Terminate on double duplex outlets in a 4S box. The location of the outlet(s) will be specified in the Telecommunications Room layout provided by the RCIT Communications Bureau Telecommunications Engineer.
- g. **Emergency Air Conditioner Outlet (To Support IT Telephone System):** Install one dedicated 208/220 VAC, 20 Amp circuit terminated on a single NEMA 6-20 receptacle. The location of the outlet will be specified in the Telecommunications Room layout provided by the RCIT Communications Bureau Telecommunications Engineer.
- h. **Grounding** – A Telecommunications Main Grounding Busbar (TMGB) shall be installed in the Telecommunications Room at the location specified in the room layout that will be provided by the RCIT Communications Bureau Telecommunications Engineer. **The Grounding Busbar must be CPI Chatsworth Products, part #13622-020.** The Busbar shall be insulated from its supporting structure by at least two inches of separation. Bond the Busbar to the building AC grounding electrode system. The minimum size of the bonding conductor should be #3 AWG and be sized to carry the maximum short time rating Amps of the building grounding electrode conductor. A supplemental bonding connection is required to be Exothermically Welded to the structural steel of the building and local AC sub-panel located inside the Telecommunications Room. Resistance should be no more than .1 ohms between the TMGB and the building main grounding source measured following the two-point bonding test method using an earth ground resistance tester. All grounding conductors shall be run in rigid conduit.

D. **CONDUIT REQUIREMENTS**

1. **Work Area Outlets (WAO):**

- a. **General Specifications:** Each WAO shall consist of one 4 in. by 4 in. by 2.5 in. deep outlet box with a 2 in. by 4 in. reducing adapter installed.
- b. **Height Requirements:** Each WAO shall be installed at the same height as the adjacent electrical outlet. The height of jacks for wall telephones shall conform to any ADA rules pertaining to handicapped use. This height is typically 44 inches AFF to the center of the outlet box.
- c. **Conduits Specifications:**
  - (1) **Accessible Ceilings:** When there is an accessible ceiling such as suspended acoustical tile, provide a rigid trade size 1 conduit (**flex not allowed**) stubbed into the ceiling space from the outlet box. Ceiling must be accessible from the WAO location back to the Telecommunications Room. If a WAO location is at wall phone height (+44"), install an additional outlet box at standard floor height. Connect a rigid 1-inch conduit from the bottom of the wall height box to the top of the standard floor height box. Ream all conduit ends and fit with insulated bushings.
  - (2) **Non-Accessible Ceilings:** When the ceiling is not accessible, provide a rigid 1¼-inch conduit (**flex not allowed**) run from the WAO location all the way to the Telecommunications Room or to the nearest accessible ceiling space. Runs cannot have more than the equivalent of two 90-degree bends without installing a pull box (pull box must be accessible upon completion of construction). **All conduits will have a pull string installed.** Where multiple outlets are installed, each location will have its own dedicated conduit run; no daisy chaining is allowed.

2. **System Furniture Wall In-feeds:** Wall in-feeds will be one rigid 1.25 in. conduit per 3 WAO locations of systems furniture. The conduit shall be stubbed into the ceiling area from a 4 in. by 4 in. by 2.5 in. deep outlet box. Ream all conduit ends and fit with insulated bushings. In-feed location will be accessible either by cutout or access panel in furniture or placed next to furniture where location will be accessible for service. Consult RCIT Communications Bureau Telecommunications Engineer for location, quantity, and size of in-feeds. Exact location will be verified with furniture vendor.
3. **System Furniture Floor Poke-Thru In-feeds:** Poke-Thru locations requiring power/voice/data will require Wiremold P/N RC9FFTC Poke-Thru's with EMT 1.25 in. conduit per 3 WAO locations of systems furniture. Color to be specified by Architect. The conduit shall be continuous and stubbed into the ceiling area of that floor being serviced with pull string installed. No more than two 90's will be allowed, J-Box for furniture supplier power whip connections to be anchored to the ceiling of the floor below with unistrut. J-Box must be with-in 6' of furniture whip connection. Ream all conduit ends and fit with insulated bushings. Consult RCIT Communications Bureau Telecommunications Engineer for location, and quantity. Exact location will be verified with furniture vendor.
4. **System Furniture Power and Data Floor Boxes:** Floor Box locations requiring power/voice/data will require Wiremold P/N RFB4-C1-1 Floor Box with EMT 1.25 in conduit per 3 WAO locations of systems furniture for communications. Color to be specified by Architect. The conduit shall be continuous and stubbed into the ceiling area of that floor being serviced with pull string installed. No more than two 90's will be allowed. All boxes shall be configured for dual service which will require accessory items for separation of power and data. All boxes shall include (1) internal duplex receptacle for power, (1) Wiremold P/N RFB-2-SSRT for communications and (1) flanged cover P/N S28BBTCAL. Ream all conduit ends and fit with insulated bushings. Consult RCIT Communications Bureau Telecommunications Engineer for location, and quantity. Exact location will be verified with furniture vendor.
5. **Hard Wall Office Floor Poke-Thru:** Poke-Thru locations requiring power/voice/data will require Wiremold P/N RC4ATC Poke-Thru's with the optional Communications Adapter P/N Com75 installed for Voice and Data conduits. Install two (2) EMT 0.75 in. conduits per location. The conduits shall be continuous and stubbed into the ceiling area of that floor being serviced with pull string installed. No more than two 90's will be allowed. Ream all conduit ends and fit with insulated bushings. Consult RCIT Communications Bureau Telecommunications Engineer for location, quantity, and size of in-feeds. Exact location will be verified with furniture vendor.
6. **Hard Wall Power and Data Floor Boxes:** Floor Box locations required power/voice data will require Wiremold P/N RFB4-C1-1 Floor Box with (1) EMT 1.25 in. conduit for communications. Color to be specified by Architect. The conduit shall be continuous and stubbed into the ceiling area of that floor being serviced with pull string installed. No more than two 90's will be allowed. All boxes shall be configured for dual service which will require accessory items for separation of power and data. All boxes shall include (1) internal duplex receptacle for power, (1) Wiremold P/N RFB-2-SSRT for communications and (1) flanged cover P/N S38BBTCAL. Ream all conduits ends and fit with insulated bushings. Consult RCIT Communications Bureau Telecommunications Engineer for location, and quantity. Exact location will be verified with furniture vendor.
7. **Backbone Pathways:**
  - a. **Telecommunications Rooms On the Same Floor:** When two or more Telecommunications Rooms exist on the same floor, provide two (2) rigid metallic trade size 4 conduits between the main Telecommunications Room and each secondary Telecommunications Room. Conduits are to be run in the most direct route possible with

no more than the equivalent of two 90-degree sweeps without a pull box. The minimum size of a pull box shall be 24" W x 36" L x 12" D. Ream all conduit ends and fit with insulated bushings. Conduits are to be bonded to ground in accordance with all local and national requirements. Location of conduits will be identified on drawings provided by the RCIT Communications Bureau Telecommunications Engineer and provided on a site-by-site basis. The bend radius of the conduit shall be 10 times the outside conduit diameter. **Install a pull string with minimum tensile strength of 30 lbs in each conduit.**

- b. **Telecommunications Rooms On Different Floors:** When two or more Telecommunications Rooms exist on different floors, provide a minimum of two (2) rigid trade size 4 conduits between the main Telecommunications Room and each secondary Telecommunications Room. Conduits are to be run in the most direct route possible with no more than the equivalent of two 90-degree bends without a pull box. The minimum size of a pull box shall be 24" W x 36" L x 12" D. Ream all conduit ends and fit with insulated bushings. Conduits are to be bonded to ground in accordance with all local and national requirements. The bend radius of the conduit shall be 10 times the outside conduit diameter. **Install a pull string with minimum tensile strength of 30 lbs in each conduit.** In multi-level buildings with **stacked Telecommunications Rooms**, sleeves shall be provided from the ceiling of the lowest level to the floor of the top level. Size, quantity, and location will be provided by the RCIT Communications Bureau Telecommunications Engineer.
- c. **MPOE:** If the MPOE (minimum point of entry) is not physically located in the Telecommunications Room it shall be necessary to install two (2) trade size 4 conduits from the MPOE to the Telecommunications Room. Conduits are to be run in the most direct route possible with no more than the equivalent of two 90-degree bends without a pull box. The minimum size of a pull box shall be 24" W x 36" L x 12" D. Ream all conduit ends and fit with insulated bushings. Conduits are to be bonded to ground in accordance with all local and national requirements. Location of conduits will be identified on drawings provided by the RCIT Communications Bureau Telecommunications Engineer and provided on a site-by-site basis. The bend radius of the conduit shall be 10 times the outside conduit diameter. **Install a pull string with minimum tensile strength of 30 lbs in each conduit.**
- d. **Telecommunications Rooms in Multiple Buildings on Same or Adjacent Properties:** The number of conduits will be determined by the **size and scope of each project**. **The items listed below are BASIC** requirements only as the scope of the project increases, some or all of the items listed below may undergo major changes:
  - (1) Conduits shall be rigid and shall be four (4) trade size 4. A **minimum** of two (2) conduits will be installed from the primary Telecommunications Room and each building as defined by the RCIT Communications Bureau Telecommunications Engineer. Conduits shall be installed in the most direct route possible.
  - (2) Conduits shall be buried a minimum of 36 inches below finish grade.
  - (3) Conduits shall be encased in 2,000 PSI concrete where vehicle traffic occurs and encased in slurry everywhere else for the entire length.
  - (4) Tracer tape shall be installed the entire conduit length. Tracer tape shall be 12 inches wide, flat, and metallic and shall be installed 12 inches above concrete encasement. Tape shall be imprinted with the words "WARNING – FIBER OPTIC CABLE" spaced at a minimum of 24 inches on center.
  - (5) No more than the equivalent of two (2) 90-degree bends shall be installed without

the addition of a pull box, vault, or maintenance hole, which size and requirements will be defined by the RCIT Communications Bureau Telecommunications Engineer.

- (6) Conduit runs in excess of 500 feet shall have a pull box, vault, or maintenance hole installed, which size and requirements will be defined by the RCIT Communications Bureau Telecommunications Engineer. All sweeps shall have a minimum bending-radius of 10 times the diameter of the conduit.
  - (7) All four inch conduits should have a minimum ¼-inch nylon pull rope. All four inch conduits over 400 feet should have a minimum 3/8-inch nylon pull rope. The size and requirements of pull boxes, vaults, or maintenance holes can only be determined by the scope of the project and will be defined by the RCIT Communications Bureau Telecommunications Engineer.
8. **Firewalls:** If any firewalls are present, conduit/sleeve access through the wall must be provided by the contractor. The ends of any conduit/sleeve penetrating a firewall will be sealed with the appropriate fire stop. Identification of the areas that must be sealed shall be identified by the contractor at the time of wiring. Size and location of the sleeves will be determined by the RCIT Communications Bureau Telecommunications Engineer. Sleeves should penetrate the wall a minimum of 3 inches. Ream each end of conduit and fit with insulated bushing.
9. **Primary Service Conduit Requirements (New Construction):**
- a. The number of all primary service conduits will be determined by the **size and scope of each project. The items listed below are BASIC** requirements only and as the scope of the job increases, some or all of the items listed below may undergo major changes:
    - (1) Entrance conduits shall be rigid and shall be four (4) trade size 4. **A minimum of two (2) conduits** will be installed into the Telecommunications Room. Conduits shall be installed in the most direct route possible.
    - (2) Conduits shall be buried a minimum of 36 inches below finish grade.
    - (3) Conduits shall be encased in slurry for sections identified by RCIT Communications Bureau Telecommunications Engineer as no traffic or low risk.
    - (4) Conduits shall be encased in 2,000 PSI concrete for sections not identified in section 5a3.
    - (5) Tracer tape shall be installed the entire conduit length. Tracer tape shall be 12 inches wide, flat, and metallic and shall be installed 12 inches above concrete encasement. Tape shall be imprinted with the words "WARNING – FIBER OPTIC CABLE" spaced at a minimum of 24 inches on center.
    - (6) No more than the equivalent of two (2) 90-degree sweeps shall be installed without the addition of a pull box, vault, or maintenance hole, which size and requirements will be defined by the RCIT Communications Bureau Telecommunications Engineer.
    - (7) Conduit runs in excess of 500 feet shall have a pull box, vault, or maintenance hole installed, which size and requirements will be defined by the RCIT Communications Bureau Telecommunications Engineer. All bends shall have a minimum-bending radius of 10 times the diameter of the conduit.

- (8) All four-inch conduits should have a minimum ¼-inch nylon pull rope. All four-inch conduits over 400 feet should have a minimum 3/8-inch nylon pull rope. The size and requirements of pull boxes, vaults, or maintenance holes can only be determined by the scope of the project and will be defined by the RCIT Communications Bureau Telecommunications Engineer.

**E. CABLE TRAYS:**

1. If the structural ceiling height is greater than 16' AFF or the occupied space is greater than 25,000 square feet, a cable tray system will be required to support the voice and data wiring. Consult with the RCIT Communications Bureau Telecommunications Engineer requirements to assist in the design of the cable tray system. A structural Engineer will be required to design the cable tray system to code and manufacturer specification and submit design to the RCIT Communications Bureau Telecommunications Engineer for approval.

**RCIT  
System's Furniture  
Telecommunications Standards  
June 16, 2004**

**1. Work Area Outlets**

- 1.1. **Definition: Work Area Outlet (WAO)** – consists of a telecommunications faceplate and its component (s) – what telephones and PC's are plugged into at a user's desk location or work area.
- 1.2. Furniture communications outlet openings shall accommodate the installation of an industry-standard, single gang faceplate, with a minimum opening of 2 inches by 3 inches.
  - 1.2.1. Two (2) factor or field-installed threaded openings shall be provided for single gang faceplate mounting and shall accommodate a 10x22 screw.
- 1.3. Furniture communications outlet openings shall provide a minimum mounting depth of 44.5 mm (1.75 in).
- 1.4. Extender plates shall be provided for WAO's (Work Area Outlet's) within furniture system – one for each workstation space, fax location, and printer location.
  - 1.4.1. Extender plates shall be a minimum 7/8 inch deep.

**2. Cabling Pathways**

- 2.1. Furniture pathways shall have capacity for a minimum of (12) communications cables with an outside diameter of .25 inches and not exceed 40% of pathway capacity.
  - 2.1.1. Remaining pathway capacity will be utilized to accommodate future moves, adds, and changes (MAC's).
  - 2.1.2. This requirement applies to ALL areas of the furniture pathway INCLUDING corners, panel to panel pathways, etc.
  - 2.1.3. Consideration will include space used in furniture for connecting hardware.
- 2.2. Furniture system shall completely conceal all communications cabling in all cabling



pathways.

- 2.3. Entire communications cabling pathway shall contain a continuous and rigid support infrastructure within each panel.
- 2.4. When communications cabling pathways run parallel to electrical pathways:
  - 2.4.1. A metallic barrier shall be provided (i.e. metallic divider, conduit, corrugated or solid) and shall be bonded to ground.
  - 2.4.2. Electrical components shall not impede on communications cabling pathways so as to restrict in any way the fill requirements noted above.
- 2.5. The minimum size pathway shall not force the cable bend radius to be less than 25 mm (1 in) under conditions of maximum cable fill.
- 2.6. Metallic pathway edges shall utilize protective bushings.
- 2.7. All panels shall be equipped with at least one (1) of the following raceways and shall singularly conform to all of the above noted cabling pathway requirements:
  - 2.7.1. Base Raceway
  - 2.7.2. Top Raceway

### **3. Furniture In-Feeds**

- 3.1. Furniture in-feeds shall have capacity for a minimum of (12) communications cables with an outside diameter of .25 inches and not exceed 40% of pathway capacity.
  - 3.1.1. Remaining pathway capacity will be utilized to accommodate future moves, adds, and changes (MAC's).
  - 3.1.2. Consideration will include space used in furniture for connecting hardware.
- 3.2. Furniture in-feeds shall have the ability to provide for separate entry points for power and communications cabling.
  - 3.2.1. Where entry points are closer than 6 inches, a physical / mechanical barrier shall be provided to separate cabling entry points.
- 3.3. Metallic in-feed edges shall utilize protective bushings.
- 3.4. One furniture in-feed shall be provided for every four (4) WAO's (Work Area Outlets).
- 3.5. Placement of furniture in-feeds shall be coordinated and verified by County IT.

## ESTOPPEL CERTIFICATE

1. The County of Riverside, as Tenant, for the purpose of providing office space for use by \_\_\_\_\_ and \_\_\_\_\_, as Lessor, entered into a written office lease dated \_\_\_\_\_ in which Lessor leased to County and County leased from Lessor those certain premises consisting of approximately \_\_\_\_\_ square feet of office space located at \_\_\_\_\_. The office lease, as amended, modified, and supplemented, is referred to in this Certificate as the "Lease".
2. The Lease has not been amended, modified, nor supplemented, except \_\_\_\_\_.
3. County has paid Rent through \_\_\_\_\_. The next payment of Rent is due on \_\_\_\_\_. The current rent is \_\_\_\_\_. County has not paid Lessor a security deposit.
4. Under the Lease, the term began on \_\_\_\_\_, and the expiration date of the Lease is \_\_\_\_\_ subject to County's right to terminate the Lease and any options the County may have to extend the term as identified in this Certificate.
5. The Lease provides for \_\_\_\_\_ option(s) to extend the term of the Lease for \_\_\_\_\_ years each. The rental rate for each extension period is \_\_\_\_\_.
6. The County has the right of first refusal to renew the Lease, after the original term and any options to extend have expired, on the same terms and conditions as are then being offered by Lessor to bona fide third party prospective lessees.
7. The County has the right to early termination of this Lease if funding is reduced or becomes unavailable or if the County determines for any reason or cause that the Premises are no longer suitable for its use.
8. There are no oral or written amendments, modifications, or supplements to the Lease except as previously stated in this Certificate. A true, correct, and complete copy of the Lease, including all amendments, modifications, and supplements, is attached to this Certificate. The Lease, as amended, modified and supplemented, is in full force and effect and represents the entire agreement between Lessor and the County pertaining to the Premises.
9. All space and improvements leased by County have been completed and furnished in accordance with the provisions of the Lease, and County has accepted and taken possession of the Premises. All contributions required to be paid by Lessor to date for improvements to the Premises have been paid in full.
10. Lessor and County are not in default in the performance of any of the terms and provisions of the Lease. To the best knowledge of each Party, no event or condition has occurred that, with the giving of notice or passage of time, or both, would constitute such default by Lessor or County.

11. Lessor has not assigned, transferred, or hypothecated the Real Property or any interest in the Real Property.
12. The County has not assigned, transferred, or hypothecated the Lease or any interest in the Lease or subleased all or part of the Premises.
13. There are no mortgagees, beneficiaries under deeds of trust, or other holders of a security interest in the Real Property, except as follows: \_\_\_\_\_.
14. There are no setoffs or credits against Rent payable under the Lease. No free periods or rental abatements, rebates, or concessions have been granted to County, except as follows: \_\_\_\_\_.
15. There are no pending actions, voluntary or involuntary, under any bankruptcy or insolvency laws of the United States or any state against either Lessor or County
16. The execution of this Certificate by Lessor and the County does not amend the Lease or waive any of Lessor's or County's rights under the Lease except as specifically provided in this Certificate.
17. This Certificate is given to \_\_\_\_\_ with the understanding that as a lender or purchaser of the above described real property or assignee of either Lessor or County \_\_\_\_\_ may rely on it in connection with either the assignment or acquisition of the above described real property or making a loan secured by the above described real property. Following that acquisition, assignment by Lessor or loan, County agrees that the Lease shall remain in full force and effect and shall bind and inure to the benefit of \_\_\_\_\_ and its successor in interest.

LESSOR:

\_\_\_\_\_

COUNTY:

\_\_\_\_\_  
ROBERT FIELD, Director  
Department of Facilities Management

RECORDED AT REQUEST OF AND WHEN  
RECORDED RETURN TO:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Attention: \_\_\_\_\_

**SUBORDINATION, NON-DISTURBANCE, AND ATTORNMENT AGREEMENT**

This Subordination, Non-disturbance, and Attornment Agreement ("Agreement") is made as of \_\_\_\_\_ between \_\_\_\_\_ (Lender), a \_\_\_\_\_, having its principal place of business at \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and the County of Riverside (County), by its authorized representative the Director of Facilities Management having its address for notification at 3133 Mission Inn Avenue, Riverside, California 92507-4199.

**Recitals:**

A. Lender has agreed to make a loan to \_\_\_\_\_, a \_\_\_\_\_ (Lessor), to be secured by a deed of trust, dated \_\_\_\_\_, \_\_\_\_\_, and recorded on \_\_\_\_\_, \_\_\_\_\_, as Instrument No. \_\_\_\_\_, in the Official Records of \_\_\_\_\_ County, California (together with all amendments, increases, renewals, modifications, consolidations, replacements, substitutions, and extensions, either current or future, referred to hereafter as the "Mortgage") encumbering Lessor's ownership interest in real property located in \_\_\_\_\_, \_\_\_\_\_, State of California. The legal description of the encumbered real property (the "Mortgage Premises") is set forth in Exhibit A, attached to this Agreement. The Mortgage, together with the promissory note or notes, the loan agreement(s), and other documents executed in connection with it are hereafter collectively referred to as the "Loan Documents".

B. On \_\_\_\_\_, \_\_\_\_\_, County and Lessor entered into a lease for the Mortgage Premises (the Lease). The Lease creates a leasehold estate in favor of County for space (the "Premises") located on the Mortgage Premises.

C. In connection with execution of the Mortgage, Lessor also executed and delivered to Lender an Assignment of Leases, Rents and Profits dated \_\_\_\_\_, \_\_\_\_\_, and recorded on \_\_\_\_\_, \_\_\_\_\_, as Instrument No. \_\_\_\_\_, in the Official Records of the County Recorder of \_\_\_\_\_, California concerning all rents, issues and profits from the Mortgage Premises. This document, together with all amendments, renewals, modifications consolidations, replacements, substitutions and extensions, is hereafter referred to as the "Assignment of Rents."

To confirm their understanding concerning the legal effect of the Mortgage and the Lease, in consideration of the mutual covenants and agreements contained in this Agreement and other valuable consideration, the receipt and sufficiency of which are hereby acknowledged, Lender and County, intending to be legally bound, agree and covenant as follows:

1. **Representations and Warranties.** County warrants and represents that the Lease is in full force and effect and that, as of the date of this Agreement and to the best of County's knowledge, there is no default under the Lease by Lessor or County.

2. **County Subordination.**

2.1. Subject to the provisions of Section 3, the Loan Documents shall constitute a lien or charge on the Mortgage Premises that is prior and superior to the Lease, to the leasehold estate created by it, and to all rights and privileges of County under it; by this Agreement, the Lease, the leasehold estate created by it, together with all rights and privileges of County under it, is subordinated, at all times, to the lien or charge of the Loan Documents in favor of Lender.

2.2. By executing this Agreement, County subordinates the Lease and County's interest under it to the lien right and security title, and terms of the Loan Documents, and to all advances or payments made, or to be made, under any Loan Document.

3. **Non-disturbance.**

3.1. Lender consents to the Lease.

3.2. Despite County's subordination under Section 2, County's peaceful and quiet possession of the Premises shall not be disturbed and County's rights and privileges under the Lease, including its right to early termination, its right to extend the term of the Lease, its right of first refusal to lease the property after expiration of the original term and any extensions thereof, shall not be diminished by Lender's exercise of its rights or remedies under the Loan Documents, provided that County has not canceled or terminated the Lease, nor surrendered, or abandoned the Premises.

3.3. If (a) Lender shall acquire title to, and possession of, the Premises on foreclosure in an action in which Lender shall have been required to name County as a party defendant, and (b) County is not in default under the Lease beyond any applicable cure or grace periods, has not canceled or terminated the Lease, nor surrendered, vacated or abandoned the Premises and remains in actual possession of the Premises at the time Lender shall so acquire title to, and possession of, the Premises, Lender and County shall enter into a new lease on the same terms and conditions as were contained in the Lease, except that:

(a) The obligations and liabilities of Lender under a new lease shall be subject to the terms and conditions of this Agreement (including the provisions of Sections 5-7);

(b) Lender shall have no obligations or liabilities to County under any such new lease beyond those of Lessor as were contained in the Lease; and

(c) The expiration date of any new lease shall coincide with the original expiration date of the Lease.

3.4. County shall not be named or joined in any foreclosure, trustee's sale, or other proceeding to enforce the Loan Documents unless such joinder shall be legally required to perfect the foreclosure, trustee's sale, or other proceeding.

4. **Attornment.**

4.1. If Lender shall succeed to Lessor's interest in the Mortgage Premises by foreclosure of the Mortgage, by deed in lieu of foreclosure, or in any other manner, County shall be bound to Lender under all the terms, covenants and conditions of the Lease for the balance of its term with the same force and effect as if Lender were the Lessor under the Lease. County shall be deemed to have full and complete attornment to, and to have established direct privity between County and:

- (a) Lender when in possession of the Mortgage Premises;
- (b) a receiver appointed in any action or proceeding to foreclose the Mortgage;
- (c) any party acquiring title to the Mortgage Premises; or
- (d) any successor to Lessor.

4.2. County's attornment is self-operating, and it shall continue to be effective without execution of any further instrument by any of the parties to this Agreement or the Lease. Lender agrees to give County written notice if Lender has succeeded to the interest of the Lessor under the Lease. The terms of the Lease are incorporated into this Agreement by reference.

4.3. If the interests of Lessor under the Lease are transferred by foreclosure of the Mortgage, deed in lieu of foreclosure, or otherwise, to a party other than Lender (Transferee), in consideration of, and as condition precedent to, County's agreement to attorn to any such Transferee, Transferee shall be deemed to have assumed all terms, covenants, and conditions of the Lease to be observed or performed by Lessor from the date on which the Transferee succeeds to Lessor's interests under the Lease.

5. **Lender as Lessor.** If Lender shall succeed to the interest of Lessor under the Lease, Lender shall be bound to County under all the terms, covenants and conditions of the Lease, and County shall, from the date of Lender's succession to the Lessor's interest under the Lease, have the same remedies against Lender for breach of the Lease that County would have had under the Lease against Lessor; provided, however, that despite anything to the contrary in this Agreement or the Lease, Lender, as successor to the Lessor's interest, shall be:

- (a) liable for any act or omission of the Lessor; provided that the Lender may elect either to perform the pre-existing obligation or to permit the County to perform it and to recover the cost out of Rent;
- (b) subject to any offsets or defenses expressly permitted under the Lease, including abatement rights which County might have had against Lessor;
- (c) bound by any rent or additional rent that County might have paid for more than one month in advance to Lessor; or
- (d) bound by an amendment or modification of the Lease even though made without Lender's written consent and whether or not the amendment or modification materially adversely affect any right of Lessor under the Lease.
- (e) subject to the County's right to assert continuing claims, such as material interference with the County's use and enjoyment of the premises, against the Lender.

6. **Right To Cure.** County agrees that, before County exercises any of its rights or remedies under the Lease, Lender shall have the right, but not the obligation, to cure the default within the same time given Lessor in the lease to cure the default, plus an additional thirty (30) days or ten (10) days in the case of defaults in the payment of money from Lessor to County. County agrees that the cure period shall be extended by the time necessary for Lender to commence foreclosure proceedings and to obtain possession of the Mortgage Premises, provided that:

- (a) Lender shall notify County of Lender's intent to effect its remedy;
- (b) Lender initiates immediate steps to foreclose on or to recover possession of the Mortgage Premises;
- (c) Lender initiates immediate legal proceedings to appoint a receiver for the Mortgage Premises or to foreclose on or recover possession of the Mortgage Premises within the thirty (30) day period; and
- (d) Lender prosecutes such proceedings and remedies with due diligence and continuity to completion.

7. **Assignment of Rents.** If Lessor defaults in its performance of the terms of the Loan Documents, County agrees to recognize the Assignment of Rents made by Lessor to Lender and shall pay to Lender, as assignee, from the time Lender gives County notice that Lessor is in default under the terms of the Loan Documents, the rents under the Lease, but only those rents that are due or that become due under the terms of the Lease after notice by Lender. Payments of rents to Lender by County under the assignment of rents and Lessor's default shall continue until the first of the following occurs:

- (a) No further rent is due or payable under the Lease;
- (b) Lender gives County notice that the Lessor's default under the Loan Documents has been cured and instructs County that the rents shall thereafter be payable to Lessor;
- (c) The lien of the Mortgage has been foreclosed and the purchaser at the foreclosure sale (whether Lender or a Transferee) gives County notice of the foreclosure sale. On giving notice, the purchaser shall succeed to Lessor's interests under the Lease, after which time the rents and other benefits due Lessor under the Lease shall be payable to the purchaser as the owner of the Mortgage Premises.

8. **County's Reliance.** When complying with the provisions of Section 7, County shall be entitled to rely on the notices given by Lender under Section 7, and Lessor agrees to release, relieve, and protect County from and against any and all loss, claim, damage, or liability (including reasonable attorney's fees) arising out of County's compliance with such notice.

County shall be entitled to full credit under the Lease for any rents paid to Lender in accordance with Section 7 to the same extent as if such rents were paid directly to Lessor. Any dispute between Lender (or Lender's Transferee) and Lessor as to the existence of a default by Lessor under the terms of the Mortgage, the extent or nature of such default, or Lender's right to foreclosure of the Mortgage, shall be dealt with and adjusted solely between Lender (or Transferee)

and Lessor, and County shall not be made a party to any such dispute (unless required by law).

9. **Lender's Status.** Nothing in this Agreement shall be construed to be an agreement by Lender to perform any covenant of the Lessor under the Lease unless and until it obtains title to the Mortgage Premises by power of sale, judicial foreclosure, or deed in lieu of foreclosure, or obtains possession of the Mortgage Premises under the terms of the Loan Documents.

10. **Cancellation of Lease.** County agrees that it will not cancel, terminate, or surrender the Lease, except at the normal expiration of the Lease term or as provided in the Lease.

11. **Special Covenants.** Despite anything in this Agreement or the Lease to the contrary, if Lender acquires title to the Mortgage Premises, County agrees that: Lender shall have the right at any time in connection with the sale or other transfer of the Mortgage Premises to assign the Lease or Lender's rights under it to any person or entity, and that Lender, its officers, directors, shareholders, agents, and employees shall be released from any further liability under the Lease arising after the date of such transfer, provided that the assignee of Lender's interest assumes Lender's obligations under the Lease, in writing, from the date of such transfer.

12. **Transferee's Liability (Non Recourse).** If a Transferee acquires title to the Mortgage Premises:

(a) County's recourse against Transferee for default under the Lease shall be limited to the Mortgage Premises or any sale, insurance, or condemnation proceeds from the Mortgage Premises;

(b) County shall look exclusively to Transferee's interests described in (a) above for the payment and discharge of any obligations imposed on Transferee under this Agreement or the Lease ; and

(i) Transferee, its officers, directors, shareholders, agents, and employees are released and relieved of any personal liability under the Lease;

(ii) County shall look solely to the interests of Transferee set forth in (a) above, and

(iii) County shall not collect or attempt to collect any judgment out of any other assets, or from any general or limited partners or shareholders of Transferee.

13. **Transferee's Performance Obligations.** Subject to the limitations provided in Sections 11 and 12, if a Transferee acquires title to the Mortgage Premises, the Transferee shall perform and recognize all County improvement allowance provisions, all rent-free and rent rebate provisions, and all options and rights of offer, in addition to Lessor's other obligations under the Lease.

14. **Notice.** All notices required by this Agreement shall be given in writing and shall be deemed to have been duly given for all purposes when:

(a) deposited in the United States mail (by registered or certified mail, return receipt requested, postage prepaid); or

(b) deposited with a nationally recognized overnight delivery service such as Federal Express or Airborne.



Each notice must be directed to the party to receive it at its address stated below or at such other address as may be substituted by notice given as provided in this section.

The addresses are:

Lender: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Attention: \_\_\_\_\_

Copy to: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Attention: \_\_\_\_\_

County: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Attention: \_\_\_\_\_

Copy to: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Attention: \_\_\_\_\_

Copies of notices sent to the parties' attorneys or other parties are courtesy copies, and failure to provide such copies shall not affect the effectiveness of a notice given hereunder.

**15. Miscellaneous Provisions.**

15.1. This Agreement may not be modified orally; it may be modified only by an agreement in writing signed by the parties or their successors-in-interest. This Agreement shall inure to the benefit of and bind the parties and their successors and assignees.

15.2. The captions contained in this Agreement are for convenience only and in no way limit or alter the terms and conditions of the Agreement.

15.3. This Agreement has been executed under and shall be construed, governed, and enforced, in accordance with the laws of the State of California except to the extent that California law is preempted by the U.S. federal law. The invalidity or unenforceability of one or more provisions of this Agreement does not affect the validity or enforceability of any other provisions.

15.4. This Agreement has been executed in duplicate. Lender and County agree that one (1) copy of the Agreement will be recorded.

15.5. This Agreement shall be the entire and only agreement concerning subordination of the Lease and the leasehold estate created by it, together with all rights and privileges of County under it, to the lien or charge of the Loan Documents and shall supersede and cancel, to the extent that it would affect priority between the Lease and the Loan Documents, any previous subordination agreements, including provisions, if any, contained in the Lease that provide for the subordination of the Lease and the leasehold estate created by it to a deed of trust or mortgage. This Agreement supersedes any inconsistent provision of the Lease.

15.6. This Agreement may be executed in any number of counterparts, each of which when so executed and delivered shall be deemed to be an original and all of which copies, taken together, shall constitute but one and the same instrument. Signature and acknowledgment pages may be detached from the copies and attached to a single copy of this Agreement to physically form one original document, which may be recorded without an attached copy of the Lease.

15.7. If any legal action or proceeding is commenced to interpret or enforce the terms of this Agreement or obligations arising out of it, or to recover damages for the breach of the Agreement, the party prevailing in such action or proceeding shall be entitled to recover from the non-prevailing party or parties all reasonable attorneys' fees, costs, and expenses it has incurred.

15.8. Word Usage. Unless the context clearly requires otherwise, (a) the plural and singular numbers will each be deemed to include the other; (b) the masculine, feminine, and neuter genders will each be deemed to include the others; (c) "shall," "will," "must," "agrees," and "covenants" are each mandatory; (d) "may" is permissive; (e) "or" is not exclusive; and (f) "includes" and "including" are not limiting.

Executed on the date first above written.

**Lender:**

\_\_\_\_\_

a \_\_\_\_\_

By: \_\_\_[signature]\_\_\_\_\_

Its: \_\_\_[state title]\_\_\_\_\_

**County:**

\_\_\_\_\_

a \_\_\_\_\_

By: \_\_\_[signature]\_\_\_\_\_

Its: \_\_\_[state title]\_\_\_\_\_

Accepted and Agreed To:

**Lessor:**

\_\_\_\_\_

a \_\_\_\_\_

By: \_\_\_\_ [signature] \_\_\_\_\_

Its: \_\_\_\_ [state title] \_\_\_\_\_

[Exhibit A: Legal description of Mortgage Premises]