

Water Slurry

At the option of the Contractor, water may be used as slurry when casing is used for the entire length of the drilled hole.

Water slurry shall be tested for conformance to the requirements shown in the following table:

WATER SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (pcf) - before final cleaning - just before placing concrete	63.5*	Mud Weight (Density) API 13B-1 Section 1
Sand Content (percent) - before final cleaning - just before placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, salt water slurry may be used and the allowable densities may be increased up to 2 pcf.		

CONSTRUCTION

General

CIDH concrete piling 24 inches in diameter or larger may be constructed by excavation and depositing concrete under slurry.

Portions of CIDH concrete piling shown on the plans to be formed shall be formed and finished in conformance with the provisions for concrete structures in Section 51, "Concrete Structures," of the Standard Specifications.

Placing Concrete

Concrete deposited under slurry shall be carefully placed in a compact, monolithic mass and by a method that will prevent washing of the concrete. Concrete deposited under slurry need not be vibrated. Placing concrete shall be a continuous operation lasting not more than the time required for each concrete placing operation at each pile, as submitted in the placing plan, unless otherwise approved in writing by the Engineer. Concrete shall be placed with concrete pumps and delivery tube system of adequate number and size to complete the placing of concrete in the time specified. The delivery tube system shall consist of one of the following:

- A. A tremie tube or tubes, each of which are at least 10 inches in diameter, fed by one or more concrete pumps.
- B. One or more concrete pump tubes, each fed by a single concrete pump.

The delivery tube system shall consist of watertight tubes with sufficient rigidity to keep the ends always in the mass of concrete placed. If only one delivery tube is utilized to place the concrete, the tube shall be placed near the center of the drilled hole. Multiple tubes shall be

uniformly spaced in the hole. Internal bracing for the steel reinforcing cage shall accommodate the delivery tube system. Tremies shall not be used for piles without space for a 10-inch tube.

Spillage of concrete into the slurry during concrete placing operations shall not be allowed. Delivery tubes shall be capped with a watertight cap, or plugged above the slurry level with a good quality, tight fitting, moving plug that will expel the slurry from the tube as the tube is charged with concrete. The cap or plug shall be designed to be released as the tube is charged. The pump discharge or tremie tube shall extend to the bottom of the hole before charging the tube with concrete. After charging the delivery tube system with concrete, the flow of concrete through a tube shall be induced by slightly raising the discharge end. During concrete placement, the tip of the delivery tube shall be maintained as follows to prevent reentry of the slurry into the tube. Until at least 10 feet of concrete has been placed, the tip of the delivery tube shall be within 6 inches of the bottom of the drilled hole, and then the embedment of the tip shall be maintained at least 10 feet below the top surface of the concrete. Rapid raising or lowering of the delivery tube shall not be permitted. If the seal is lost or the delivery tube becomes plugged and must be removed, the tube shall be withdrawn, the tube cleaned, the tip of the tube capped to prevent entrance of the slurry, and the operation restarted by pushing the capped tube 10 feet into the concrete and then reinitiating the flow of concrete.

When slurry is used, a fully operational standby concrete pump, adequate to complete the work in the time specified, shall be provided at the site during concrete placement. The slurry level shall be maintained 10 feet above the piezometric head or within 12 inches of the top of the drilled hole, whichever is higher.

A log of concrete placement for each drilled hole shall be maintained by the Contractor when concrete is deposited under slurry. The log shall show the pile location, tip elevation, dates of excavation and concrete placement, total quantity of concrete deposited, length and tip elevation of any casing, and details of any hole stabilization method and materials used. The log shall include a 8-1/2" x 11" sized graph of the concrete placed versus depth of hole filled. The graph shall be plotted continuously throughout placing of concrete. The depth of drilled hole filled shall be plotted vertically with the pile tip oriented at the bottom and the quantity of concrete shall be plotted horizontally. Readings shall be made at least at each 5 feet of pile depth, and the time of the reading shall be indicated. The graph shall be labeled with the pile location, tip elevation, cutoff elevation, and the dates of excavation and concrete placement. The log shall be delivered to the Engineer within 1 working day of completion of placing concrete in the pile.

After placing reinforcement and before placing concrete in the drilled hole, if drill cuttings settle out of the slurry, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

If a temporary casing is used, concrete placed under slurry shall be maintained at a level at least 5 feet above the bottom of the casing. The withdrawal of the casing shall not cause contamination of the concrete with slurry. If slurry is not used, the temporary casing shall not be withdrawn until the concrete head in the casing is greater than the groundwater outside of the casing. This positive concrete head shall be maintained during the withdrawal of the casing.

Material resulting from using slurry shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Acceptance Testing and Mitigation

Vertical inspection pipes for acceptance testing shall be provided in all CIDH concrete piling 24 inches in diameter or larger, except when the holes are dry or when the holes are dewatered without the use of temporary casing in a manner that controls ground water.

The furnishing and placing of inspection pipes shall conform to the following:

- A. Inspection pipes shall be Schedule 40 PVC pipe with a nominal inside diameter of 2 inches. Watertight PVC couplers are permitted to facilitate pipe lengths in excess of those which are commercially available. The Contractor shall log the location of the inspection pipe couplers with respect to the plane of pile cut off, and these logs shall be delivered to the Engineer upon completion of the placement of concrete in the drilled hole.
- B. Each inspection pipe shall be capped at the bottom and shall extend from 3 feet above the pile cutoff down to the bottom of the reinforcing cage. A temporary top cap or similar means shall be provided to keep the pipes clean before testing. If pile cutoff is below the ground surface or working platform, inspection pipes shall be extended to 3 feet above the ground surface or working platform. Approved covers or railings shall be provided and inspection pipes shall be located as necessary to minimize exposure of testing personnel to potential falling hazards.
- C. Inspection pipes shall be completely clean, dry, and unobstructed at the time of testing providing a 2-inch diameter clear opening.
- D. The inspection pipes shall be installed in straight alignment, parallel to the main reinforcement, and securely fastened in place to prevent misalignment during installation of the reinforcement and placing of concrete in the hole. The CIDH concrete piling shall be constructed so that the relative distance of inspection pipes to vertical steel reinforcement shall remain constant.
- E. When any changes are made to the tip of CIDH concrete piling, the Contractor shall also extend the inspection pipes to the bottom of the reinforcing cage.

The following additional requirements apply if inspection pipes are not shown on the plans:

- A. Inspection pipes shall be placed radially around the pile, inside the outermost spiral or hoop reinforcement and no more than 1 inch clear of the outermost spiral or hoop reinforcement.
- B. Inspection pipes shall be placed around the pile at a uniform spacing not exceeding 33 inches measured along the circle passing through the centers of inspection pipes. A minimum of 2 inspection pipes per pile shall be used. Inspection pipes shall be placed to provide the maximum diameter circle that passes through the centers of the inspection pipes while maintaining the spacing required herein.
- C. Inspection pipes shall be placed a minimum of 3 inches clear of the vertical reinforcement. When the vertical reinforcement configuration does not permit this clearance while achieving radial location requirements, distance to vertical rebar shall be maximized while still maintaining the requirement for radial location.
- D. Where the dimensions of the pile reinforcement do not permit inspection pipes to be placed per these requirements, a plan for tube placement shall be submitted to the Engineer for approval in the Pile Placement Plan with a request for deviation before fabricating pile reinforcement.

After placing concrete and before requesting acceptance tests, each inspection pipe shall be tested by the Contractor in the presence of the Engineer by passing a 1-1/4-inch-diameter rigid cylinder 4.5 feet long through the length of pipe. If an inspection pipe fails to pass the 1-1/4-inch-diameter cylinder, the Contractor shall immediately fill all inspection pipes in the pile with water.

For each inspection pipe that does not pass the 1-1/4-inch-diameter cylinder, the Contractor shall core a nominal 2-inch diameter hole through the concrete for the entire length of the pile. Cored holes shall be located as close as possible to the inspection pipes they are replacing and shall be no more than 5 inches clear from the reinforcement.

Coring shall not damage the pile reinforcement. Cored holes shall be made with a double wall core barrel system utilizing a split tube type inner barrel. Coring with a solid type inner barrel will not be allowed. Coring methods and equipment shall provide intact cores for the entire length of the pile. Coring operation shall be logged by an Engineering Geologist or Civil Engineer licensed in the State of California and experienced in core logging. Coring logs shall be in conformance with the Department's "Soil and Rock Logging, Classification, and Presentation Manual." Coring logs shall include Core Recovery (REC), Rock Quality Designation (RQD), locations of breaks, and complete descriptions of inclusions and voids encountered during coring, and shall be delivered to the Engineer upon completion. Concrete cores shall be preserved, identified with the exact location the core was recovered from within the pile, and delivered to the Engineer upon completion. The Engineer will evaluate the portion of the pile represented by the cored hole based on the submitted core logs.

Acceptance tests of the concrete will be made by the Engineer, without cost to the Contractor. Acceptance tests will evaluate the homogeneity of the placed concrete. Tests will include gamma-gamma logging conducted in conformance with California Test 233. The Contractor shall not conduct operations within 25 feet of the gamma-gamma logging operations. The Contractor shall separate reinforcing steel as necessary to allow the Engineer access to the inspection pipes to perform gamma-gamma logging or other acceptance testing. After requesting acceptance tests and providing access to the piles, the Contractor shall allow 20 days for the Engineer to conduct these tests and make determination of acceptance. Should the Engineer fail to complete these tests within the time allowance, and if in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in inspection, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Engineer may elect to perform additional tests to further evaluate a pile. These tests may include crosshole sonic logging and other means of inspection selected by the Engineer. When the Engineer elects to perform additional tests to further evaluate anomalies for a rejected pile, no time requirement exists for performing these tests. The Contractor may progress with the mitigation plan process without waiting for these supplemental results.

Inspection pipes and cored holes shall be dewatered and filled with grout after notification by the Engineer that the pile is acceptable. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. Inspection pipes and holes shall be filled using grout tubes that extend to the bottom of the pipe or hole or into the grout already placed.

If acceptance testing performed by the Engineer determines that a pile does not meet the requirements of the specifications and California Test 233, Part 5C, then that pile will be rejected and all depositing of concrete under slurry or concrete placed using temporary casing for the purpose of controlling groundwater shall be suspended until written changes to the methods of pile construction are approved in writing by the Engineer.

The Engineer will determine whether the rejected pile requires mitigation due to structural, geotechnical, or corrosion concerns. The Engineer will consider the estimated size and location of the anomaly and potential effects upon the design. The Engineer will provide the conclusions of this analysis to the Contractor for development of a mitigation plan, if required. The Contractor shall allow 35 days for the Engineer to determine whether the pile requires mitigation and provide information to the Contractor. Day 1 of the 35 days shall be the 1st day after access has been provided to the Engineer to perform acceptance testing. If additional information is submitted to the Engineer that modifies the size, shape, or nature of the anomaly, the Contractor shall allow 15 additional days for the subsequent analysis.

If the Engineer determines that a rejected pile does not require mitigation, the Contractor may elect to (1) repair the pile per the approved mitigation plan or (2) not repair anomalies found during acceptance testing of that pile. For such unrepaired piles, the Contractor shall pay to the State, \$300 per cubic yard for the portion of the pile affected by the anomalies. The volume, in cubic yards, of the portion of the pile affected by the anomalies, shall be calculated as the area of the cross section of the pile affected by each anomaly, in square yards, as determined by the Engineer, multiplied by the distance, in yards, from the top of each anomaly to the specified tip of the pile. If the volume calculated for one anomaly overlaps the volume calculated for additional anomalies within the pile, the calculated volume for the overlap shall only be counted once. In no case shall the amount of the payment to the State for any such pile be less than \$300. The Department may deduct the amount from any moneys due, or that may become due the Contractor under the contract.

If the Engineer determines that a rejected pile requires mitigation, the Contractor shall submit to the Engineer for approval a mitigation plan for repair, supplementation, or replacement for each rejected CIDH concrete pile conforming to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. If the Engineer determines that it is not feasible to repair the rejected pile, the Contractor shall not include repair as a means of mitigation and shall proceed with the submittal of a mitigation plan for replacement or supplementation of the rejected pile.

Pile mitigation plans shall include the following:

- A. The designation and location of the pile addressed by the mitigation plan.
- B. A review of the structural, geotechnical, and corrosion design requirements of the rejected pile.
- C. A step by step description of the mitigation work to be performed, including drawings if necessary.
- D. An assessment of how the proposed mitigation work will address the structural, geotechnical, and corrosion design requirements of the rejected pile.
- E. Methods for preservation or restoration of existing earthen materials.

- F. A list of affected facilities, if any, with methods and equipment for protection of these facilities during mitigation.
- G. The State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Post Mile, and the Contractor's (and Subcontractor's if applicable) name on each sheet.
- H. A list of materials, with quantity estimates, and personnel, with qualifications, to be used to perform the mitigation work.
- I. The seal and signature of an engineer who is licensed as a Civil Engineer by the State of California. This requirement is waived for approved mitigation plans when either of the following conditions are present:
 - 1. The proposed mitigation will be performed in conformance with the most recent Department approved version of "ADSC Standard Mitigation Plan 'A' - Basic Repair" without exception or modification.
 - 2. The Engineer has determined that the rejected pile does not require mitigation due to structural, geotechnical, or corrosion concerns, and the Contractor elects to repair the pile using most recent Department approved version of "ADSC Standard Mitigation Plan 'B' - Grouting Repair" without exception or modification.

The most recent Department approved version of the "ADSC Standard Mitigation Plan" is available at:

<http://www.dot.ca.gov/hq/esc/geotech/ft/adscmitplan.htm>

For rejected piles to be repaired, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. An assessment of the nature and size of the anomalies in the rejected pile.
- B. Provisions for access for additional pile testing if required by the Engineer.

For rejected piles to be replaced or supplemented, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. The proposed location and size of additional piles.
- B. Structural details and calculations for any modification to the structure to accommodate the replacement or supplemental piles.

All provisions for CIDH concrete piling shall apply to replacement piles.

The Contractor shall allow the Engineer 20 days to review the mitigation plan after a complete submittal has been received.

Should the Engineer fail to review the complete pile mitigation submittal within the time specified, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the pile mitigation plan, an extension of time commensurate with the delay in completion of the work thus caused will be granted in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

When repairs are performed, the Contractor shall submit a mitigation report to the Engineer within 10 days of completion of the repair. This report shall state exactly what repair work was performed and quantify the success of the repairs relative to the submitted mitigation plan. The mitigation report shall be stamped and signed by an engineer that is licensed as a Civil Engineer by the State of California. The mitigation report shall show the State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Post Mile, and the Contractor (and subcontractor if applicable) name on each sheet. The Engineer will be the sole judge as to whether a mitigation proposal is acceptable, the mitigation efforts are successful, and to whether additional repairs, removal and replacement, or construction of a supplemental foundation is required.

MEASUREMENT AND PAYMENT (PILING)

Measurement and payment for the various types and classes of piles shall conform to the provisions in Sections 49-6.01, "Measurement," and 49-6.02, "Payment," of the Standard Specifications and these special provisions.

Payment for cast-in-place concrete piling shall conform to the provisions in Section 49-6.02, "Payment," of the Standard Specifications and these special provisions except that when the diameter of cast-in-place concrete piling is shown on the plans as 24 inches or larger, reinforcement in the piling will be paid for by the pound as bar reinforcing steel (bridge).

Full compensation for slurry, depositing concrete under slurry, test batches, inspection pipes, filling inspection holes and pipes with grout, drilling oversized cast-in-drilled-hole concrete piling, filling cave-ins and oversized piles with concrete, and redrilling through concrete shall be considered as included in the contract prices paid per linear foot for cast-in-drilled-hole concrete piling of the types and sizes listed in the Engineer's Estimate, and no additional compensation will be allowed therefor.

10-1.61 PRESTRESSING CONCRETE

Prestressing concrete shall conform to the provisions in Section 50, "Prestressing Concrete," of the Standard Specifications and these special provisions.

The details shown on the plans for cast-in-place prestressed box girder bridges are based on a bonded full length draped tendon prestressing system. For these bridges the Contractor may, in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications, propose an alternative prestressing system utilizing bonded partial length tendons provided the proposed system and associated details meet the following requirements:

- A. The proposed system and details shall provide moment and shear resistances at least equal to those used for the design of the structure shown on the plans.
- B. The concrete strength shall not be less than that shown on the plans.
- C. Not less than 35 percent of the total prestressing force at any section shall be provided by full length draped tendons.
- D. Anchorage blocks for partial length tendons shall be located so that the blocks will not interfere with the placement of the utility facilities shown on the plans or of any future utilities to be placed through openings shown on the plans.

- E. Temporary prestressing tendons, if used, shall be detensioned, and the temporary ducts shall be filled with grout before completion of the work. Temporary tendons shall be either removed or fully encased in grout before completion of the work.
- F. All details of the proposed system, including supporting checked calculations, shall be included in the drawings submitted in conformance with the provisions in Section 50-1.02, "Drawings," of the Standard Specifications.

Moments and shears for loads used in the design shown on the plans will be made available to the Contractor upon written request to the Engineer.

10-1.62 CONCRETE STRUCTURES

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

GENERAL

Shotcrete shall not be used as an alternative construction method for reinforced concrete members unless otherwise specified.

When a roughened concrete surface is shown on the plans, the existing concrete surface shall be roughened to a full amplitude of approximately 1/4 inch by abrasive blasting, water blasting, or mechanical equipment.

Neoprene strip shall be furnished and installed at abutment backwall joint protection in conformance with the details shown on the plans, the provisions in the Standard Specifications, and these special provisions.

Furnishing and installing neoprene strip shall conform to the requirements for strip waterstops as provided in Section 51-1.145, "Strip Waterstops," of the Standard Specifications, except that the protective board will not be required.

Materials for access opening covers in soffits of new cast-in-place concrete box girder bridges shall conform to the provisions for materials in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

FALSEWORK

Falsework shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

The Contractor's engineer who signs the falsework drawings shall also certify in writing that the falsework is constructed in conformance with the approved drawings and the contract specifications prior to placing concrete. This certification shall include performing any testing necessary to verify the ability of the falsework members to sustain the stresses required by the falsework design. The engineer who signs the drawings may designate a representative to perform this certification. Where falsework contains openings for railroads, vehicular traffic, or pedestrians, the designated representative shall be qualified to perform this work, shall have at least 3 years of combined experience in falsework design or supervising falsework construction, and shall be registered as a Civil Engineer in the State of California. For other falsework, the

designated representative shall be qualified to perform this work and shall have at least 3 years of combined experience in falsework design or supervising falsework construction. The Contractor shall certify the experience of the designated representative in writing and provide supporting documentation demonstrating the required experience if requested by the Engineer.

Welding and Nondestructive Testing

Welding of steel members, except for previously welded splices and except for when fillet welds are used where load demands are less than or equal to 1,000 pounds per inch for each 1/8 inch of fillet weld, shall conform to AWS D1.1 or other recognized welding standard. The welding standard to be utilized shall be specified by the Contractor on the working drawings. Previously welded splices for falsework members are defined as splices made prior to the member being shipped to the project site.

Splices made by field welding of steel beams at the project site shall undergo nondestructive testing (NDT). At the option of the Contractor, either ultrasonic testing (UT) or radiographic testing (RT) shall be used as the method of NDT for each field weld and any repair made to a previously welded splice in a steel beam. Testing shall be performed at locations selected by the Contractor. The length of a splice weld where NDT is to be performed, shall be a cumulative weld length equal to 25 percent of the original splice weld length. The cover pass shall be ground smooth at the locations to be tested. The acceptance criteria shall conform to the requirements of AWS D1.1, Section 6, for cyclically loaded nontubular connections subject to tensile stress. If repairs are required in a portion of the weld, additional NDT shall be performed on the repaired sections. The NDT method chosen shall be used for an entire splice evaluation including any required repairs.

For all field welded splices, the Contractor shall furnish to the Engineer a letter of certification which certifies that all welding and NDT, including visual inspection, are in conformance with the specifications and the welding standard shown on the approved working drawings. This letter of certification shall be signed by an engineer who is registered as a Civil Engineer in the State of California and shall be provided prior to placing any concrete for which the falsework is being erected to support.

For previously welded splices, the Contractor shall determine and perform all necessary testing and inspection required to certify the ability of the falsework members to sustain the stresses required by the falsework design. This welding certification shall (1) itemize the testing and inspection methods used, (2) include the tracking and identifying documents for previously welded members, (3) be signed by an engineer who is registered as a Civil Engineer in the State of California, (4) and shall be provided prior to erecting the members.

COST REDUCTION INCENTIVE PROPOSALS FOR CAST-IN-PLACE PRESTRESSED BOX GIRDER BRIDGES

Except as provided herein, cast-in-place prestressed box girder bridges shall be constructed in conformance with the details shown on the plans and the provisions in Section 50, "Prestressing Concrete," and Section 51, "Concrete Structures," of the Standard Specifications.

If the Contractor submits cost reduction incentive proposals for cast-in-place prestressed box girder bridges, the proposals shall be in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications and these special provisions.

The Engineer may reject any proposal which, in the Engineer's judgment, may not produce a structure which is at least equivalent to the planned structure.

At the time the cost reduction incentive proposal (CRIP) is submitted to the Engineer, the Contractor shall also submit 4 sets of the proposed revisions to the contract plans, design calculations, and calculations from an independent checker for all changes involved in the proposal, including revisions in camber, predicted deck profile at each construction stage, and falsework requirements to the Offices of Structure Design, Documents Unit, P.O. Box 942874, Sacramento, CA 94274-0001 (1801 30th Street, Sacramento, CA 95816), telephone (916) 227-8230. When notified in writing by the Engineer, the Contractor shall submit 12 sets of the CRIP plan revisions and calculations to the Offices of Structure Design for final approval and use during construction. The calculations shall verify that all requirements are satisfied. The CRIP plans and calculations shall be signed by an engineer who is registered as a Civil Engineer in the State of California.

The CRIP plans shall be either 11" x 17", or 22" x 34" in size. Each CRIP plan sheet and calculation sheet shall include the State assigned designations for the contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Post Mile. Each CRIP plan sheet shall be numbered in the lower right hand corner and shall contain a blank space in the upper right hand corner for future contract sheet numbers.

Within 3 weeks after final approval of the CRIP plan sheets, one set of the corrected good quality prints on 20-pound (minimum) bond paper, 22" x 34" in size, of all CRIP plan sheets prepared by the Contractor for each CRIP shall be furnished to the Offices of Structure Design, Documents Unit.

Each CRIP shall be submitted prior to completion of 25 percent of the contract working days and sufficiently in advance of the start of the work that is proposed to be revised by the CRIP to allow time for review by the Engineer and correction by the Contractor of the CRIP plans and calculations without delaying the work. The Contractor shall allow a minimum of 4 weeks for the review of a CRIP. In the event that several CRIPs are submitted simultaneously, or an additional CRIP is submitted for review before the review of a previously submitted CRIP has been completed, the Contractor shall designate the sequence in which the CRIPs are to be reviewed. In this event, the time to be provided for the review of any proposal in the sequence shall be not less than the review time specified herein for that proposal, plus 2 weeks for each CRIP of higher priority which is still under review.

Should the review not be complete by the date specified in the Contractor's CRIP, or such other date as the Engineer and Contractor may subsequently have agreed to in writing and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review of CRIP plans and calculations, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications except that the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications shall not apply.

Permits and approvals required of the State have been obtained for the structures shown on the plans. Proposals which result in a deviation in configuration may require new permits or

approvals. The Contractor shall be responsible for obtaining the new permits and approvals before the Engineer will reach a decision on the proposal. Delays in obtaining permits and approvals will not be reason for granting an extension of contract time.

All proposed modifications shall be designed in conformance with the bridge design specifications and procedures currently employed by the Department. The proposal shall include all related, dependent or incidental changes to the structure and other work affected by the proposal. The proposal will be considered only when all aspects of the design changes are included for the entire structure. Changes, such as but not limited to, additional reinforcement and changes in location of reinforcement, necessary to implement the CRIP after approval by the Engineer, shall be made at the Contractor's expense.

Modifications may be proposed in (1) the thickness of girder stems and deck slabs, (2) the number of girders, (3) the deck overhang dimensions as specified herein, (4) the amount and location of reinforcing steel, (5) the amount and location of prestressing force in the superstructure, and (6) the number of hinges, except that the number of hinges shall not be increased. The strength of the concrete used may be increased but the strength employed for design or analysis shall not exceed 6,000 psi.

Modifications proposed to the minimum amount of prestressing force which must be provided by full length draped tendons are subject to the provisions in "Prestressing Concrete" of these special provisions.

No modifications will be permitted in (1) the foundation type, (2) the span lengths or (3) the exterior dimensions of columns or bridge superstructure, except that the overhang dimension from face of exterior girder to the outside edge of roadway deck may be uniformly increased or decreased by 25 percent on each side of the box girder section. Fixed connections at the tops and bottoms of columns shown on the plans shall not be eliminated.

The Contractor shall be responsible for determining construction camber and obtaining the final profile grade as shown on the plans.

The Contractor shall reimburse the State for the actual cost of investigating CRIPs for cast-in-place prestressed box girder bridges submitted by the Contractor. The Department will deduct this cost from any moneys due, or that may become due the Contractor under the contract, regardless of whether or not the proposal is approved or rejected.

DECK CLOSURE POURS

Where a deck closure pour is shown on the plans, reinforcement protruding into the closure space and forms for the closure pour shall conform to the following:

- A. During the time of placement of concrete in the deck, other than for the closure pour itself, reinforcing steel which protrudes into the closure space shall be completely free from any connection to the reinforcing steel, concrete, or other attachments of the adjacent structure, including forms. The reinforcing steel shall remain free of any connection for a period of not less than 24 hours following completion of the pour.
- B. Forms for the closure pour shall be supported from the superstructure on both sides of the closure space.

SLIDING BEARINGS

Sliding bearings consisting of elastomeric bearing pads lubricated with grease and covered with sheet metal shall conform to the following requirements:

- A. Grease shall conform to the requirements of Society of Automotive Engineers AS 8660. A uniform film of grease shall be applied to the upper surface of the pads prior to placing the sheet metal.
- B. Sheet metal shall be commercial quality galvanized sheet steel. The sheet metal shall be smooth and free of kinks, bends, or burrs.
- C. Construction methods and procedures shall prevent grout or concrete seepage into the sliding bearing assembly.

ELASTOMERIC BEARING PADS

Elastomeric bearing pads shall conform to the provisions in Section 51-1.12H, "Elastomeric Bearing Pads," of the Standard Specifications.

MEASUREMENT AND PAYMENT

Measurement and payment for concrete in structures shall conform to the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for roughening existing concrete surfaces to a full amplitude of approximately 1/4 inch, where shown on the plans, shall be considered as included in the contract price paid per cubic yard for structural concrete, bridge and no separate payment will be made therefor.

Full compensation for public notification and airborne monitoring for deck crack treatment shall be considered as included in the contract price paid per cubic yard for structural concrete, bridge, and no additional compensation will be allowed therefor.

10-1.63 STRUCTURE APPROACH SLABS (TYPE EQ)

GENERAL

Summary

This work includes constructing reinforced concrete approach slabs.

Reinforced concrete approach slabs must comply with Section 51, "Concrete Structures," of the Standard Specifications.

Submittals

Furnish a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the geocomposite drain certifying that the drain complies with these special provisions. The Certificate of Compliance must be accompanied by a flow capability graph for the geocomposite drain showing flow rates and the externally applied pressures and hydraulic gradients. The flow capability graph must be stamped with the verification of an independent testing laboratory.

Notify the Engineer of the type of treated permeable base to be furnished at least 30 days before the start of placement. Once you have notified the Engineer of the selection, the type to be furnished must not be changed without a prior written request to do so and approval thereof by the Engineer.

MATERIALS

Concrete

Concrete for structure approach slabs must contain not less than 675 pounds of cementitious material per cubic yard and must either:

1. Cure for not less than 5 days before opening to public traffic, or
2. Comply with "Rapid Strength Concrete for Structures" of these special provisions.

Drainage Pads

Concrete for use in drainage pads must be minor concrete, except the concrete must contain not less than 505 pounds of cementitious material per cubic yard.

Geocomposite Drain

Geocomposite drain must consist of a manufactured core not less than 0.25 inch thick nor more than 2 inches thick with one or both sides covered with a layer of filter fabric that will provide a drainage void. The drain must produce a flow rate through the drainage void of at least 2 gallons per minute per foot of width at a hydraulic gradient of 1.0 and a minimum externally applied pressure of 3,500 psf.

The manufactured core must be one of the following:

1. Preformed grid of embossed plastic
2. Mat of random shapes of plastic fibers
3. Drainage net consisting of a uniform pattern of polymeric strands forming 2 sets of continuous flow channels
4. System of plastic pillars and interconnections forming a semirigid mat

The core material and filter fabric must be capable of maintaining the drainage void for the entire height of geocomposite drain. Filter fabric must be integrally bonded to the side of the core material with the drainage void.

Filter Fabric

Filter fabric must comply with the specifications for Class A filter fabric in Section 88-1.02, "Filtration," of the Standard Specifications.

Treated Permeable Base

Treated permeable base under structure approach slabs must be an asphalt treated permeable base or a cement treated permeable base as specified in Section 29, "Treated Permeable Bases," of the Standard Specifications.

Miscellaneous Materials

Steel angles, plates, and bars at the concrete barrier joints must comply with Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Hardboard and expanded polystyrene must comply with Section 51-1.12D, "Sheet Packing, Preformed Pads, and Board Fillers," of the Standard Specifications.

CONSTRUCTION

Geocomposite Drain

Install the geocomposite drain with the drainage void and the filter fabric facing the embankment. The fabric facing the embankment side must overlap a minimum of 3 inches at all joints and wrap around the exterior edges a minimum of 3 inches beyond the exterior edge. If additional fabric is needed to provide overlap at joints and wraparound at edges, the added fabric must overlap at least 6 inches and be attached to the fabric on the geocomposite drain.

Place core material manufactured from impermeable plastic sheeting having non-connecting corrugations with the corrugations approximately perpendicular to the drainage collection system.

If the fabric on the geocomposite drain is torn or punctured, replace the damaged section completely or repair it by placing a piece of fabric that is large enough to cover the damaged area and provide a 6-inch overlap.

If asphalt treated permeable base is placed around the slotted plastic pipe at the bottom of the geocomposite drain, it must be placed at a temperature of not less than 180 °F nor more than 230 °F.

Filter Fabric

Place filter fabric immediately after grading and compacting the subgrade to receive the filter fabric.

Align, handle, and place filter fabric in a wrinkle-free manner under the manufacturer's recommendations.

Adjacent borders of the filter fabric must be overlapped from 12 inches to 18 inches or stitched. The preceding roll must overlap the following roll in the direction the material is being spread or must be stitched. When the fabric is joined by stitching, it must be stitched with yarn of a contrasting color. The size and composition of the yarn must be as recommended by the fabric manufacturer. The number of stitches per 1 inch of seam must be 5 to 7.

Equipment or vehicles must not be operated or driven directly on the filter fabric.

Treated Permeable Base

Construct treated permeable base under Section 29, "Treated Permeable Bases," of the Standard Specifications and these special provisions.

Place asphalt treated permeable base at a temperature of not less than 200 °F nor more than 250 °F. Do not use material stored in excess of 2 hours in the work.

Asphalt treated permeable base may be spread in 1 layer. Compact with a vibrating shoe type compactor or a roller weighing at least 1.5 tons but not more than 5 tons. Begin compacting

base as soon as the mixture has cooled sufficiently to support the weight of the equipment without undue displacement.

Cement treated permeable base may be spread in 1 layer. Compact base with a vibrating shoe type compactor or with a steel-drum roller weighing at least 1.5 tons but not more than 5 tons. Compaction must begin within one-half hour of spreading and must consist of 2 complete coverages of the cement treated permeable base.

Finishing Approach Slabs

Finish and treat the top surface of approach slabs under Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications. Edges of slabs must be edger finished.

Cure approach slabs with pigmented curing compound (1) under the specifications for curing structures in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications.

Sealing Joints

Type AL joint seals must comply with Section 51-1.12F, "Sealed Joints," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods.

The sealant may be mixed by hand-held power-driven agitators and placed by hand methods. Immediately before placing the seal, thoroughly clean the joint, including abrasive blast cleaning of the concrete surfaces, so that all foreign material and concrete spillage are removed from all joint surfaces. Joint surfaces must be dry at the time the seal is placed.

MEASUREMENT AND PAYMENT

Structural concrete, approach slab (Type EQ) will be measured and paid for in conformance with the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for miscellaneous bridge metal, pourable seals, and epoxy-coated bar reinforcement, shall be considered as included in the contract price paid per cubic yard for structural concrete, approach slab (Type EQ), and no additional compensation will be allowed therefor.

10-1.64 STRUCTURE APPROACH SLABS (TYPE R)

GENERAL

Summary

This work includes removing portions of existing structures, existing pavement and base including asphalt concrete surfacing, portland cement concrete pavement, subsealing material, and cement treated base, and constructing new reinforced concrete approach slabs at structure approaches.

Reinforced concrete approach slabs must comply with Section 51, "Concrete Structures," of the Standard Specifications.

Quality Control and Assurance

Trial Slab

Before beginning work on approach slabs constructed using RSC, you must successfully complete one or more trial slabs for each concrete mix design to be used in constructing the approach slabs.

Trial slabs must be constructed, finished, cured, and tested with the materials, tools, equipment, personnel, and methods to be used in completing the approach slab. Trial slabs must demonstrate that you are capable of producing approach slabs in conformance with the provisions in this section, within anticipated time periods including delivery, placement, finishing, and curing times, and under similar atmospheric and temperature conditions expected during construction operations. Multiple trial slabs for each approach slab concrete mix design may be required to envelop variable atmospheric conditions.

The minimum trial slab dimensions must be 10' x 20' x 9". Place trial slabs near the job site at a location acceptable to the Engineer except slabs must not be placed on the roadway or within the project limits.

Perform compressive strength testing under Section 90-9, "Compressive Strength," of the Standard Specifications. Trial slab concrete must develop compressive strengths of at least 1200 psi at the age of break used for prequalification of the concrete, and at least 2500 psi at 3 days.

MATERIALS

Concrete

Concrete for structure approach slabs must contain not less than 675 pounds of cementitious material per cubic yard and must either:

1. Cure for not less than 5 days before opening to public traffic, or
2. Comply with "Rapid Strength Concrete for Structures" of these special provisions.

Temporary Structural Section

HMA must consist of commercial quality aggregate and asphalt binder. The grading of the aggregate must comply with the 3/4-inch HMA Types A and B grading specified in Section 39-1.02E, "Aggregate," of the Standard Specifications. The asphalt binder must comply with the requirements for liquid asphalt SC-800 in Section 93, "Liquid Asphalts," of the Standard Specifications. The amount of asphalt binder to be mixed with the aggregate must be approximately 0.3 percent less than the optimum bitumen content as determined by California Test 367.

Aggregate Base (Approach Slab)

Aggregate base (approach slab) for filling voids below the reinforced structure approach slab concrete must be produced from commercial quality aggregates consisting of broken stone, crushed gravel or natural rough-surfaced gravel, and sand, or any combination thereof. The grading of the aggregate base must comply with the 3/4-inch maximum grading specified in Section 26-1.02A, "Class 2 Aggregate Base," of the Standard Specifications.

Miscellaneous Materials

Steel angles, plates, and bars at the concrete barrier joints must comply with Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Hardboard and expanded polystyrene must comply with Section 51-1.12D, "Sheet Packing, Preformed Pads, and Board Fillers," of the Standard Specifications.

CONSTRUCTION

General

The thickness shown on the plans for structure approach slabs is the minimum thickness. The thickness may vary depending on the thickness of the pavement and base materials removed.

Dispose of all materials no longer required in the work under Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Schedule your work so that the pavement and base materials removed during a work period are replaced in that same work period with properly finished and cured approach slab concrete before the time the lane is to be opened to public traffic as specified in "Maintaining Traffic" of these special provisions.

If the existing pavement and base materials are removed, and you are unable to construct, finish, and cure the new approach slab by the time the lane is to be opened to public traffic, you must fill the excavation with a temporary roadway structural section as specified in this section, "Structure Approach Slabs (Type R)."

Temporary Roadway Structural Section

Provide a standby quantity of hot mix asphalt (HMA) and aggregate base at the job site equal to the quantity of pavement removed during the work shift for construction of a temporary roadway structural section. The temporary structural section must consist of a 0.3-foot-thick layer of HMA over aggregate base.

Spread and compact aggregate base and HMA by methods that will produce a well-compacted, uniform base, free from pockets of coarse or fine material and a surfacing of uniform smoothness, texture, and density. The aggregate base and the HMA may each be spread and compacted in one layer. The finished surface of the HMA must not vary more than 0.05 foot from the lower edge of a 12-foot straightedge placed parallel with the centerline and must match the elevation of the existing pavement and structure along the joints between the existing pavement and structure and the temporary surfacing.

Maintain the temporary structural section until you are able to construct and cure the approach slab with the prescribed time limit.

Removing Portions Of Existing Structures

Remove portions of the existing structure under "Existing Highway Facilities" of these special provisions.

Removing Existing Pavement And Base Materials

Sawcut full depth the outline of portland cement concrete to be removed with a power-driven concrete saw.

Cut the outlines of excavations in asphalt concrete on a neat line to a minimum depth of 0.25 foot with a power-driven concrete saw or wheel-type rock cutting excavator before any asphalt

concrete material is removed. These excavations must be permanently or temporarily backfilled to conform to the grade of the adjacent pavement before opening the lane to public traffic. Surplus excavated material may be used as temporary backfill material.

Regardless of the type of equipment used to remove concrete within the sawed outline, do not use power impact tools within 1.5 feet of the pavement that is required to remain in place.

Uniformly grade and compact the existing base material remaining in place after removing the existing pavement and base materials to the required depth. The finished surface of the base material at any point must not extend above the grade approved by the Engineer.

Fill areas of base material that are low as a result of over excavation with structure approach slab concrete in the same operation that the new concrete is placed.

Where pavement subsealing has been performed under existing approach slabs, remove the full depth of subsealing material. Where removal of cement treated base is required to construct the approach slab, remove the full depth of the cement treated base.

Fill voids between the new structure approach slab and the base material remaining in place that are caused by removal of subsealing material or cement treated base with either aggregate base (approach slab) or structure approach slab concrete. If you choose to fill these voids with structure approach slab concrete, fill the voids in the same operation that the new concrete is placed.

Establish a grade line for the new approach slab that will provide a smooth profile grade. The profile grade will be subject to approval by the Engineer.

Aggregate Base (Approach Slab)

Spread and compact aggregate base (approach slab) for filling voids below the reinforced structure approach slab concrete by methods that will produce a well-compacted, uniform base, free from pockets of coarse or fine material to the grade approved by the Engineer. Where the required thickness of aggregate base is 8 inches or less, the base may be spread and compacted in one layer. Where the required thickness of aggregate base is more than 8 inches, the base must be spread and compacted in 2 or more layers of approximately equal thickness. The maximum compacted thickness of any one layer shall not exceed 8 inches.

The finished surface of the base material at any point must not extend above the grade approved by the Engineer. Fill areas of base material that are lower than the grade approved by the Engineer with structure approach slab concrete in the same operation that the new concrete is placed.

Bonding Bar Reinforcement

Bond bar reinforcement in drilled holes under the provisions for drilling and bonding dowels in Section 83-2.02D(1), "General," of the Standard Specifications.

If reinforcement is encountered during drilling before the specified depth is attained, notify the Engineer. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole must be drilled adjacent to the rejected hole to the depth shown on the plans.

Finishing Approach Slabs

Finish the top surface of the approach slab under the provisions for decks in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications. The finished top surface must not vary more than 0.02 foot from the lower edge of a 12-foot straightedge placed parallel with the centerline. Edges of slabs must be edger finished. The provisions for deck crack treatment do not apply to Type R approach slabs.

The surface of the approach slab will not be profiled, and the Profile Index requirements do not apply.

Approach slab concrete shall be cured before the time the lane is to be opened to public traffic as specified in "Maintaining Traffic" of these special provisions.

Sealing Joints

Type AL joint seals must comply with Section 51-1.12F, "Sealed Joints," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods.

MEASUREMENT AND PAYMENT

Structural concrete, approach slab (Type R) will be measured and paid for in conformance with the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for removing and disposing of portions of existing structures and pavement materials, and for furnishing and placing epoxy-coated materials, and pourable seals shall be considered as included in the contract price paid per cubic yard for structural concrete, approach slab (Type R), and no separate payment will be made therefor.

The quantity of aggregate base (approach slab) to be paid for shall include the actual volume of aggregate base (approach slab) used to fill voids below the reinforced structure approach slab concrete, except for the volume of areas low as a result of over excavation. The volume to be paid for will be calculated on the basis of the constructed length, width, and thickness of the filled voids. Structure approach slab concrete used to fill voids lower than the approved grade of the base, except for the areas low as a result of over excavation, will be measured and paid for by the cubic yard as aggregate base (approach slab).

The contract price paid per cubic yard for aggregate base (approach slab) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing aggregate base (approach slab), complete in place, including excavation and removing and disposing of base and subsealing materials, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing, stockpiling, and disposing of standby material for construction of temporary structural sections; and for constructing, maintaining, removing, and disposing of temporary structural sections shall be considered as included in the contract price paid per cubic yard for structural concrete, approach slab (Type R), and no separate payment will be made therefor.

Full compensation for drilling and bonding of bar reinforcement shall be considered as included in the contract price paid per cubic yard for structural concrete, approach slab (Type R), and no separate payment will be made therefor.

Full compensation for constructing, testing, and removing trial slabs shall be considered as included in the contract price paid per cubic yard for structural concrete, approach slab (Type R), and no separate payment will be made therefor.

10-1.65 DRILL AND BOND DOWELS

Drilling and bonding dowels shall conform to the details shown on the plans, the provisions in Section 83-2.02D(1), "General," of the Standard Specifications, and these special provisions.

Dowels shall conform to the provisions for bar reinforcement in "Reinforcement" of these special provisions.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

Unless otherwise provided, dowels to be bonded into drilled holes will be paid for as bar reinforcing steel (bridge).

Unless otherwise provided, drilling and bonding dowels will be measured and paid for by the linear foot determined by the number and the required depth of holes as shown on the plans or as ordered by the Engineer.

MEASUREMENT AND PAYMENT

The contract price paid per linear foot for drill and bond dowel shall include full compensation for furnishing all labor, materials (except reinforcing steel dowels), tools, equipment, and incidentals, and for doing all the work involved in drilling the holes, including coring through reinforcement when approved by the Engineer, and bonding the dowels, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.66 SEALING JOINTS

Joints in concrete bridge decks and joints between concrete structures and concrete approach slabs must be sealed in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

When ordered by the Engineer, a joint seal larger than called for by the Movement Rating shown on the plans must be furnished and installed. Payment to the Contractor for furnishing the larger seal and for saw cutting the increment of additional depth of groove required will be determined as provided in Section 4-1.03, "Changes," of the Standard Specifications.

10-1.67 REFINISHING BRIDGE DECKS

Surfaces of bridge decks that are exposed when existing railings, curbs, or sidewalks are removed shall be prepared and refinished flush with the adjoining deck surface in conformance with these special provisions.

The Contractor may refinish the deck surface using Portland cement concrete or rapid setting concrete.

The exact area to be refinished will be designated by the Engineer.

When work is being performed within 10 feet of a traffic lane or performed over traffic, dust and residue from deck preparation and cleaning shall be removed or controlled by vacuum, water spray, or shield methods approved by the Engineer.

Concrete shall be removed without damage to concrete that is to remain in place. Damage to concrete that is to remain in place shall be repaired to a condition satisfactory to the Engineer.

The concrete in deck areas to be refinished shall be removed to a depth of approximately 3/4 inch below the adjoining deck surface. A 3/4 inch deep saw cut shall be made along the perimeter of deck areas to be refinished before removing the concrete.

Existing areas of the deck more than 3/4 inch below the adjoining deck surface shall be prepared by removing not less than 1/4 inch of surface material to expose sound aggregate.

Concrete removal may be done by abrasive blast cutting, abrasive sawing, impact tool cutting, machine rotary abrading, or by other methods, all to be approved by the Engineer. Cut areas shall be cleaned free of dust and all other loose and deleterious materials by brooming, abrasive blast cleaning, and high pressure air jets. Equipment shall be fitted with suitable traps, filters, drip pans, or other devices to prevent oil or other deleterious matter from being deposited on the deck.

Existing reinforcement, exposed during the removal of concrete, that is to remain in place shall be protected from damage.

Steel dowels shall be cut off 1 inch below the existing concrete deck surface or at the bottom of concrete removal, whichever is lower.

Where refinishing is not required, steel dowels shall be cut off 1 inch below the finished surface and the holes shall be patched with rapid setting concrete.

Refinishing isolated high areas in the existing deck may be accomplished by cutting the concrete down to be flush with the plane of the adjoining deck surface by abrasive sawing, grinding, impact tool cutting, or by other methods approved by the Engineer. When grinding is performed to bring the deck concrete flush with the adjoining deck surface, the resulting surface shall have a coefficient of friction of not less than 0.35 as determined by California Test 342.

PORTLAND CEMENT CONCRETE

An epoxy adhesive shall be applied to the surfaces to be refinished before placing the portland cement concrete. Immediately before applying the adhesive, the area to receive the adhesive shall be cleaned by abrasive blasting and blown clean by compressed air to remove dust and any other loose material. The area to be covered shall be surface dry and the substrate temperature shall be 40° F or above when the adhesive is applied.

The epoxy adhesive shall be furnished and applied in conformance with the provisions in Section 95-1, "General," and Section 95-2.03, "Epoxy Resin Adhesive for Bonding New Concrete to Old Concrete," of the Standard Specifications. The exact rate of applying epoxy adhesive will be determined by the Engineer. The adhesive shall be worked onto the surface with stiff brushes or equal.

Portland cement concrete used to fill the prepared areas shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and the following:

- A. The concrete shall contain a minimum of 675 pounds of cementitious material per cubic yard.
- B. The amount of free water used in concrete shall not exceed 280 pounds per cubic yard.
- C. The aggregate shall contain between 50 and 55 percent fine aggregate and the remainder shall be pea gravel. The grading of pea gravel shall be such that 100 percent passes the 1/2 inch sieve and not more than 5 percent passes the No. 16 sieve, unless a larger size is ordered by the Engineer.
- D. Admixtures shall be furnished and used if directed by the Engineer.
- E. Immediately after depositing on the newly placed adhesive, the portland cement concrete shall be thoroughly consolidated until all voids are filled and free mortar appears on the surface and then struck off to the required grade.
- F. Concrete shall be cured as provided in Section 90-7.03, "Curing Structures," of the Standard Specifications.
- G. No loads of any kind shall be applied to the portland cement concrete for at least 7 days after placing.

RAPID SETTING CONCRETE

Rapid setting concrete used to fill the prepared areas shall be a high-strength material consisting of magnesium phosphate concrete, modified high alumina based concrete, or portland cement based concrete. Magnesium phosphate concrete shall conform to the requirements for magnesium phosphate concrete in Section 83-2.02D(1), "General," of the Standard Specifications. Modified high alumina based concrete and portland cement based concrete shall be water activated and shall conform to the requirements for single component (water activated) magnesium phosphate concrete in Section 83-2.02D(1), "General," of the Standard Specifications.

A clean uniform rounded aggregate filler may be used to extend the rapid setting concrete. The moisture content of the aggregate shall not exceed 0.5 percent. Grading of the aggregate shall conform to the following:

Sieve Size	Percentage Passing
1/2"	100
No. 16	0-5

The amount of aggregate filler shall conform to the manufacturer's recommendation, but in no case shall the concrete strengths be less than that specified for magnesium phosphate concrete in Section 83-2.02D(1), "General," of the Standard Specifications.

Mixing of components of dual component (with a prepackaged liquid activator) magnesium phosphate shall be by complete units, supplied by the manufacturer. Portions of units shall not be used. Water shall not be added to dual component magnesium phosphate.

Immediately before applying the rapid setting concrete, the surface shall be dry and blown clean by compressed air to remove accumulated dust and any other loose material. If the surface becomes contaminated at any time before placing the concrete, the surface shall be cleaned by abrasive blasting. The surface temperature of the areas to be covered shall be 39 F or above when the concrete is applied. Methods proposed to heat said surfaces are subject to approval by the Engineer. The surface for the magnesium phosphate concrete shall be dry. The surfaces for modified high alumina based concrete or portland cement based concrete may be damp but not saturated.

Magnesium phosphate concrete shall not be mixed in containers or worked with tools containing zinc, cadmium, aluminum, or copper. Modified high alumina based concrete shall not be mixed in containers or worked with tools containing aluminum.

Concrete shall not be retempered. Finishing tools that are cleaned with water shall be thoroughly dried before working the concrete.

When placing concrete on slopes exceeding 5 percent, the Engineer may require the Contractor to provide a flow controlled modified material.

Modified high alumina based concrete and portland cement based concrete shall be cured in conformance with the provisions in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications. Magnesium phosphate concrete shall not be cured.

Unless otherwise permitted in writing by the Engineer, public traffic shall not be permitted on the new concrete until at least 24 hours after final set.

FINISHING REQUIREMENTS

In advance of the curing operations, the surface of the concrete shall be textured by brooming with a stiff bristled broom or by other suitable devices that will result in uniform scoring. Brooming shall be performed transversely. The operation shall be performed at a time and in a manner that produces a hardened surface having a uniform texture and a coefficient of friction of not less than 0.35 as determined by California Test 342.

Refinished surfaces that are found to have a coefficient of friction less than 0.35 shall be ground or grooved by the Contractor at his expense in conformance with the applicable provisions in Section 42, "Groove and Grind Pavement," of the Standard Specifications.

In the longitudinal direction, refinished surfaces shall not vary more than 0.02 foot from the lower edge of a 12-foot straightedge. The refinished surface shall be flush with the existing adjoining surface.

MEASUREMENT AND PAYMENT

No adjustment of compensation will be made for any increase or decrease in the quantity of refinish bridge deck, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to the contract item of refinish bridge deck.

The quantity in square feet of refinish bridge deck to be paid for will be determined from the lengths and widths of the refinished areas, measured horizontally, plus 0.2 square foot for patching around each dowel.

The contract price paid per square foot for refinish bridge deck shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in refinishing areas of the existing bridge deck, including cutting steel dowels, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.68 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)

Architectural texture for concrete surfaces shall conform to the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

Architectural textures listed below are required at concrete surfaces shown on the plans:

A. Fractured rib texture

The fractured rib texture shall be an architectural texture simulating the appearance of straight ribs of concrete with a fractured concrete texture imparted to the raised surface between the ribs. Grooves between ribs shall be continuous with no apparent curves or discontinuities. Variation of the groove from straightness shall not exceed 1/4 inch for each 10 feet of groove. The architectural texture shall have random shadow patterns. Broken concrete at adjoining ribs and groups of ribs shall have a random pattern. The architectural texture shall not have secondary patterns imparted by shadows or repetitive fractured surfaces.

TEST PANEL

A test panel at least 4' x 4' in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural textures. The test panel shall be constructed and finished with the materials, tools, equipment, and methods to be used in constructing the architectural texture. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture, and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural texture for concrete-surfaces.

FORM LINERS

Form liners shall be used for textured concrete surfaces and shall be installed in conformance with the manufacturer's recommendations, unless other methods of forming textured concrete surfaces are approved by the Engineer. Form liners shall be manufactured from an elastomeric material or a semi-elastomeric polyurethane material by a manufacturer of commercially available concrete form liners. No substitution of other types of formliner material will be allowed. Form liners shall leave crisp, sharp definition of the architectural surface. Recurring textural configurations exhibited by repeating, recognizable shadow patterns shall be prevented by proper casting of form liner patterns. Textured concrete surfaces with such recurring textural configurations shall be reworked to remove such patterns as approved by the Engineer or the concrete shall be replaced.

Form liners shall have the following properties:

Description	ASTM Designation:	Range
Elastomeric material		
Shore A hardness	D 2240	20 to 65
Tensile strength (psi)	D 412	130 to 900
Semi-elastomeric polyurethane		
Shore D hardness	D 2240	55 to 65
Tensile strength (psi)	D 2370	2600 minimum

Cuts and tears in form liners shall be sealed and repaired in conformance with the manufacturer's recommendations. Form liners that are delaminated from the form shall not be used. Form liners with deformations to the manufactured surface caused by improper storage practices or any other reason shall not be used.

Form liners shall extend the full length of texturing with transverse joints at 8 foot minimum spacing. Small pieces of form liners shall not be used. Grooves shall be aligned straight and true. Grooves shall match at joints between form liners. Joints in the direction of grooves in grooved patterns shall be located only in the depressed portion of the textured concrete. Adjoining liners shall be butted together without distortion, open cracks, or offsets at the joints. Joints between liners shall be cleaned before each use to remove any mortar in the joint.

Adhesives shall be compatible with the form liner material and with concrete. Adhesives shall be approved by the liner manufacturer. Adhesives shall not cause swelling of the liner material.

RELEASING FORM LINERS

Products and application procedures for form release agents shall be approved by the form liner manufacturer. Release agents shall not cause swelling of the liner material or delamination from the forms. Release agents shall not stain the concrete or react with the liner material. For reliefs

simulating fractured concrete or wood grain surfaces the application method shall include the scrubbing method using a natural bristle scrub brush in the direction of grooves or grain. The release agent shall coat the liner with a thin film. Following application of form release agent, the liner surfaces shall be cleaned of excess amounts of agent using compressed air. Buildup of form release agent caused by the reuse of a liner shall be removed at least every 5 uses.

Form liners shall release without leaving particles or pieces of liner material on the concrete and without pulling or breaking concrete from the textured surface. The concrete surfaces exposed by removing forms shall be protected from damage.

ABRASIVE BLASTING

The architectural texture shall be abrasive blasted with fine abrasive to remove the sheen without exposing coarse aggregate.

CURING

Concrete surfaces with architectural texture shall be cured only by the forms-in-place or water methods. Seals and curing compounds shall not be used.

MEASUREMENT AND PAYMENT

Architectural texture will be measured and paid for by the square yard.

The contract price paid per square yard for architectural texture of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in architectural texture, complete in place, including test panels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for architectural texture on Concrete Barrier (Type 26 Mod) shall be considered as included in the contract price paid per linear foot for concrete barrier (Type 26 Mod), and no separate payment will be made therefor.

10-1.69 REINFORCEMENT

Reinforcement shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

The provisions in "Welding Quality Control" of these special provisions do not apply to resistance butt welding.

When joining new reinforcing bars to existing reinforcement, sample splices shall be made using only the deformation pattern of the new reinforcement to be spliced.

The following shall apply to ultimate splices for bar reinforcing cages of columns and cast-in-place piles where the longitudinal bars are spliced vertically at the job site in or above their final positions:

1. Instead of being removed from the completed lot, sample splices may be prepared in the same manner as specified in Section 52-1.08C(2)(a), "Production Test Requirements for

Service Splices," of the Standard Specifications for service sample splices. These sample splices shall be tested in conformance with the requirements in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," of the Standard Specifications.

2. Splices may be encased in concrete prior to having the QCM review, approve, and forward each Production Test Report to the Engineer. Should the Contractor exercise this option, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection.

For bar reinforcing cages measuring 4 feet in diameter and larger:

1. At least 4 vertical bars of each cage, equally spaced around the circumference, shall be tied at all reinforcement intersections with double wire ties.
2. At least 25 percent of remaining reinforcement intersections in each cage shall be tied with single wire ties. Tied intersections shall be staggered from adjacent ties.
3. Bracing shall be provided to avoid collapse of the cage during assembly, transportation, and installation.

Successful completion of these minimum baseline requirements for reinforcement cages 4 feet in diameter and larger will in no way relieve the Contractor of full responsibility for engineering the temporary support and bracing of the cages during construction.

MEASUREMENT AND PAYMENT

Measurement and payment for reinforcement in structures shall conform to the provisions in Section 52-1.10, "Measurement," and Section 52-1.11, "Payment," of the Standard Specifications and these special provisions.

Full compensation for galvanizing steel reinforcement shall be considered as included in the prices paid for the various items of work involved and no additional compensation will be allowed therefor.

10-1.70 WATERPROOFING

Waterproofing shall conform to the provisions in Section 54, "Waterproofing," of the Standard Specifications and these special provisions.

Membrane waterproofing shall be applied to the painted undercoat of steel column casings in the same manner provided for waterproofing concrete surfaces.

The exposed surfaces of the membrane waterproofing applied to steel column casings shall be of uniform height above ground without unsightly bulges, depressions or other imperfections.

At the option of the Contractor, a preformed membrane waterproofing system may be furnished and applied in lieu of the asphalt membrane waterproofing specified above. Preformed membrane waterproofing shall conform to these special provisions.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the preformed membrane sheet. The Certificate of Compliance shall include the following information: (1) type of preformed membrane sheet, and (2) the conditioner or primer application rates.

The preformed membrane waterproofing system shall consist of an adhesive, conditioner or primer applied to a prepared surface; a preformed membrane sheet of rubberized asphalt or polymer modified bitumen; mastic or tape for sealing the edges of the sheet; and a protective covering over the sheet held by an adhesive.

The preformed membrane sheet shall be either permanently applied to a polyethylene film or reinforced with a polypropylene mesh fabric, polyester/polypropylene fabric or a fiberglass mesh fabric. The membrane sheet shall conform to the following requirements:

Property	Test	Requirement	
		Polyethylene Film	Fabric Reinforced
Tensile Strength (min.)(1)	ASTM D 882 (2)	20 lbs/in (3)	20 lbs/in (3)
Percent Elongation at break (min.) (4)	ASTM D 882 (2)	150 percent (3)	25 percent (3)
Pliability	ASTM D 146 (5)	No cracks	No cracks
Thickness (min.) (6)	-----	60 mils	60 mils
Rubberized Asphalt Softening Point (min.)	AASHTO T 53	165° F	165° F
Polymer Modified Bitumen Softening Point (min.)	AASHTO T 53	210° F	210° F

Notes:

- (1) Breaking factor in machine direction.
- (2) Method A, average 5 samples.
- (3) At 73.4° F ±3.6° F
- (4) Machine direction.
- (5) 180-degree bend over a one-inch mandrel at 10° F
- (6) Total thickness of preformed membrane sheet and polyethylene film or fabric reinforcement

Adhesives, conditioners, primers, mastics and sealing tapes shall be manufactured for use with the respective preformed membrane sheet materials and shall be applied according to the manufacturer's recommendations.

The protective covering shall be 1/8 inch minimum thickness hardboard or other material that furnishes equivalent protection. Backfill material and equipment shall not cut, scratch, depress or cause any other damage to the preformed membrane.

Surfaces designated to receive preformed membrane waterproofing shall be thoroughly cleaned of dirt, dust, loose or unsound concrete, and other extraneous material and shall be free from fins, sharp edges, and protrusions that would, in the opinion of the Engineer, puncture or otherwise damage the membrane. Sharp corners to be covered shall be rounded (outside) or chamfered (inside).

Surfaces shall be dry when components of the preformed membrane waterproofing system are applied.

Preformed membrane waterproofing shall not be applied to any surface until the Contractor is prepared to follow its application with the placing of the protective covering and backfill within a sufficiently short time that the membrane will not be damaged by workers or equipment, exposure to weathering, or from any other cause. Damaged membrane or protective covering shall be repaired or replaced by the Contractor at the Contractor's expense.

All projecting pipe, conduits, sleeves or other facilities passing through the preformed membrane waterproofing shall be flashed with prefabricated or field-fabricated boots, fitted coverings or other devices as necessary to provide watertight construction.

All conditioner or primers shall be thoroughly mixed and continuously agitated during application. Conditioner, primers or adhesive shall be allowed to dry to a tack free condition prior to placing membrane sheets.

The surfaces shall be recoated if membrane sheets are not placed over primer, conditioner or adhesive within the time recommended by the manufacturer.

The preformed membrane sheet shall not be applied in wet or foggy weather, nor when the ambient temperature is below 40° F.

Preformed membrane material shall be placed starting at the bottom and lapped by a minimum of 6 inches at splices and at repairs to holes or tears.

Exposed edges of membrane sheets shall have a trowelled bead of manufacturer's recommended mastic or sealing tape applied after the membrane is placed.

The surface of the preformed membrane shall be cleaned free of dirt and other deleterious material before the protective covering is placed.

The protective covering shall be placed on a coating of adhesive of a type recommended by the manufacturer. The adhesive shall be applied at a rate sufficient to hold the protective covering in position until the backfill is placed.

Full compensation for preformed membrane waterproofing shall be considered as included in the prices paid for the various items of work involved and no additional compensation will be allowed therefor.

10-1.71 STEEL STRUCTURES

Construction of steel structures shall conform to the provisions in Section 55, "Steel Structures," of the Standard Specifications and these special provisions.

GENERAL

Attention is directed to "Welding" in Section 8, "Materials," of these special provisions.

MATERIALS

High-strength fastener assemblies and other bolts attached to structural steel with nuts and washers shall be zinc coated. When direct tension indicators are used in these assemblies, the direct tension indicator and all components of the fastener assembly shall be zinc coated by the mechanical deposition process.

ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE

Rotational capacity tests shall be performed on all lots of high-strength fastener assemblies prior to shipment of these lots to the project site. Zinc-coated assemblies shall be tested after all fabrication, coating, and lubrication of components has been completed. One hardened washer shall be used under each nut for the tests.

The requirements of this section do not apply to high-strength cap screws or high-strength bolts used for slip base plates.

Each combination of bolt production lot, nut lot, and washer lot shall be tested as an assembly.

A rotational capacity lot number shall be assigned to each combination of lots tested. Each shipping unit of fastener assemblies shall be plainly marked with the rotational capacity lot number.

Two fastener assemblies from each rotational capacity lot shall be tested.

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of long bolts. Fasteners are considered to be long bolts when full nut thread engagement can be achieved when installed in a bolt tension measuring device:

A. Long Bolt Test Equipment:

1. Calibrated bolt tension measuring device with adequate tension capacity for the bolts being tested.
2. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Long Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F 436.
4. Steel beam or member, such as a girder flange or cross frame, to which the bolt tension measuring device will be attached. The device shall be accessible from the ground.

B Long Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.

2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
3. Insert the bolt into the bolt tension measuring device and install the required number of washers, and additional spacers as needed, directly beneath the nut to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug tension shall not be less than the Table A value but may exceed the Table A value by a maximum of 2 kips.

Table A

High-Strength Fastener Assembly Tension Values to Approximate Snug-Tight Condition	
Bolt Diameter (inches)	Snug Tension (kips)
1/2	1
5/8	2
3/4	3
7/8	4
1	5
1-1/8	6
1-1/4	7
1-3/8	9
1-1/2	10

5. Match-mark the assembly by placing a heavy reference start line on the face plate of the bolt tension measuring device which aligns with (1) a mark placed on one corner of the nut and (2) a radial line placed across the flat on the end of the bolt or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make an additional mark on the face plate, either 2/3 of a turn, one turn, or 1-1/3 turn clockwise from the heavy reference start line, depending on the bolt length being tested as shown in Table B.

Table B

Required Nut Rotation for Rotational Capacity Tests ^{(a)(b)}	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3
Greater than 4 bolt diameters but no more than 8 bolt diameters	1
Greater than 8 bolt diameters, but no more than 12 bolt diameters ^(c)	1-1/3

(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees; for bolts installed by 2/3 turn and more, the tolerance shall be plus or minus 45 degrees.

(b) Applicable only to connections in which all material within grip of the bolt is steel.

(c) When bolt length exceeds 12 diameters, the required rotation shall be determined by actual tests in a suitable tension device simulating the actual conditions.

6. Turn the nut to achieve the applicable minimum bolt tension value listed in Table C. After reaching this tension, record the moving torque, in foot-pounds, required to turn the nut, and also record the corresponding bolt tension value in pounds. Torque shall be measured with the nut in motion. Calculate the value, T, where $T = [(the\ measured\ tension\ in\ pounds) \times (the\ bolt\ diameter\ in\ inches) / 48]$.

Table C

Minimum Tension Values for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Minimum Tension (kips)
1/2	12
5/8	19
3/4	28
7/8	39
1	51
1-1/8	56
1-1/4	71
1-3/8	85
1-1/2	103

7. Turn the nut further to increase bolt tension until the rotation listed in Table B is reached. The rotation is measured from the heavy reference line made on the face plate after the bolt was snug-tight. Record this bolt tension.
8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Long Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: (1) the measured moving torque (Step 6) shall be less than or equal to the calculated value, T (Step 6), (2) the bolt tension measured in Step 7 shall be greater than or equal to the applicable turn test tension value listed in Table D, (3) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, (4) the bolt does not shear from torsion or fail during the test, and (5) the assembly does not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head is expected and will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

Table D

Turn Test Tension Values	
Bolt Diameter (inches)	Turn Test Tension (kips)
1/2	14
5/8	22
3/4	32
7/8	45
1	59
1-1/8	64
1-1/4	82
1-3/8	98
1-1/2	118

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of short bolts. Fasteners are considered to be short bolts when full nut thread engagement cannot be achieved when installed in a bolt tension measuring device:

A. Short Bolt Test Equipment:

1. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Short Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
2. Spud wrench or equivalent.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F 436.
4. Steel plate or girder with a hole to install bolt. The hole size shall be 1/16 inch greater than the nominal diameter of the bolt to be tested. The grip length, including any plates, washers, and additional spacers as needed, shall provide the proper number of threads within the grip, as required in Step 2 of the Short Bolt Test Procedure.

B. Short Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
3. Install the bolt into a hole on the plate or girder and install the required number of washers and additional spacers as needed between the bearing face of the nut and the underside of the bolt head to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug condition shall be the full manual effort applied to the end of a 12-inch long wrench. This applied torque shall not exceed 20 percent of the maximum allowable torque in Table E.

Table E

Maximum Allowable Torque for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Torque (ft-lb)
1/2	145
5/8	285
3/4	500
7/8	820
1	1220
1-1/8	1500
1-1/4	2130
1-3/8	2800
1-1/2	3700

5. Match-mark the assembly by placing a heavy reference start line on the steel plate or girder which aligns with (1) a mark placed on one corner of the nut and (2) a radial

line placed across the flat on the end of the bolt or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make 2 additional small marks on the steel plate or girder, one 1/3 of a turn and one 2/3 of a turn clockwise from the heavy reference start line on the steel plate or girder.

6. Using the torque wrench, tighten the nut to the rotation value listed in Table F. The rotation is measured from the heavy reference line described in Step 5 made after the bolt was snug-tight. A second wrench shall be used to prevent rotation of the bolt head during tightening. Measure and record the moving torque after this rotation has been reached. The torque shall be measured with the nut in motion.

Table F

Nut Rotation Required for Turn-of-Nut Installation ^{(a),(b)}	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	1/3

(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees.

(b) Applicable only to connections in which all material within grip of the bolt is steel.

7. Tighten the nut further to the 2/3-turn mark as indicated in Table G. The rotation is measured from the heavy reference start line made on the plate or girder when the bolt was snug-tight. Verify that the radial line on the bolt end or on the exposed portions of the threads of tension control bolts is still in alignment with the start line.

Table G

Required Nut Rotation for Rotational Capacity Test	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3

8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Short Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: (1) the measured moving torque from Step 6 shall be less than or equal to the maximum allowable torque from Table E, (2) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, (3) the bolt does not shear from torsion or fail during the test, and (4) the assembly shall not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE

Installation tension tests and rotational capacity tests on high-strength fastener assemblies shall be performed by the Contractor prior to acceptance or installation and after arrival of the

fastener assemblies on the project site. Installation tension tests and rotational capacity tests shall be performed at the job site, in the presence of the Engineer, on each rotational capacity lot of fastener assemblies.

The requirements of this section do not apply to high-strength cap screws or high-strength bolts used for slip base plates.

Installation tension tests shall be performed on 3 representative fastener assemblies in conformance with the provisions in Section 8, "Installation," of the RCSC Specification. For short bolts, Section 8.2, "Pretensioned Joints," of the RCSC Specification shall be replaced by the "Pre-Installation Testing Procedures," of the "Structural Bolting Handbook," published by the Steel Structures Technology Center, Incorporated.

The rotational capacity tests shall be performed in conformance with the requirements for rotational capacity tests in "Rotational Capacity Testing Prior to Shipment to Job Site" of these special provisions.

At the Contractor's expense, additional installation tension tests, tests required to determine job inspecting torque, and rotational capacity tests shall be performed by the Contractor on each rotational capacity lot, in the presence of the Engineer, if:

1. Any fastener is not used within 3 months after arrival on the job site,
2. Fasteners are improperly handled, stored, or subjected to inclement weather prior to final tightening,
3. Significant changes are noted in original surface condition of threads, washers, or nut lubricant, or
4. The Contractor's required inspection is not performed within 48 hours after all fasteners in a joint have been tensioned.

Failure of a job-site installation tension test or a rotational capacity test will be cause for rejection of unused fasteners that are part of the rotational capacity lot.

When direct tension indicators are used, installation verification tests shall be performed in conformance with Appendix Section X1.4 of ASTM Designation: F 959, except that bolts shall be initially tensioned to a value 5 percent greater than the minimum required bolt tension.

SURFACE PREPARATION

For all bolted connections, the contact surfaces and inside surfaces of bolt holes shall be cleaned and coated before assembly in conformance with the provisions for cleaning and painting structural steel of these special provisions.

SEALING

When zinc-coated tension control bolts are used, the sheared end of each fastener shall be completely sealed with non-silicone type sealing compound conforming to the provisions in Federal Specification TT-S-230, Type II. The sealant shall be gray in color and shall have a minimum thickness of 50 mils. The sealant shall be applied to a clean sheared surface on the same day that the splined end is sheared off.

WELDING

Table 2.2 of AWS D1.5 is superseded by the following table:

Base Metal Thickness of the Thicker Part Joined, inches	Minimum Effective Partial Joint Penetration Groove Weld Size*, inches
Over 1/4 to 1/2 inclusive	3/16
Over 1/2 to 3/4 inclusive	1/4
Over 3/4 to 1-1/2 inclusive	5/16
Over 1-1/2 to 2-1/4 inclusive	3/8
Over 2-1/4 to 6 inclusive	1/2
Over 6	5/8

* Except the weld size need not exceed the thickness of the thinner part

10-1.72 COLUMN CASINGS

Column casings shall consist of cleaned and painted structural steel shells filled with grout as shown on the plans and conforming to the provisions in Section 55, "Steel Structures," of the Standard Specifications and these special provisions.

Attention is directed to "Welding Quality Control" of these special provisions.

For field welding of column casings, only visual inspection will be required, and the requirements of the second sentence of paragraph 3.13:2 and the first sentence of paragraph 3.13.3 of AWS D1.5 will not apply.

Structural steel for column casings shall conform to the requirements in ASTM Designation: A 36/A 36M, or, at the Contractor's option, ASTM Designation: A 709/A 709M, Grade 36.

Drain extension pipe shall conform to the provisions for drainage piping in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

The spaces to be occupied by the column casing materials shall be cleared of plants and other materials prior to encasing the column.

Removed plants and other materials shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The same information that is on existing columns shall be painted on casings in conformance with the provisions in Section 51-1.21, "Bridge Name, Number and Bent Numbers," of the Standard Specifications.

CLEAN AND PAINT COLUMN CASING

New metal surfaces, except where galvanized, shall be cleaned and painted in conformance with the provisions in Sections 59-2, "Painting Structural Steel," and 91, "Paint," of the Standard Specifications and these special provisions.

Prior to performing any painting or paint removal, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

- A. The name of each Contractor or subcontractor to be used.
- B. One copy each of all current "SSPC: The Society for Protective Coatings" specifications or qualification procedures which are applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
- C. A copy of the coating manufacturer's guidelines and recommendations for surface preparation, painting, drying, curing, handling, shipping, and storage of painted structural steel, including testing methods and maximum allowable levels for soluble salts.
- D. Proposed methods and equipment to be used for any paint application.
- E. Proof of each of any required certifications, SSPC-QP 1, SSPC-QP 3. Where SSPC-QP 3 certification is required, an enclosed shop facility shall be required. Certification of AISC Sophisticated Paint Endorsement Quality Program, P-1 Enclosed endorsement, will be considered equivalent to SSPC-QP 3.
 - 1. In lieu of certification in conformance with the requirements in SSPC-QP 1 for this project, the Contractor may submit written documentation showing conformance with the requirements in Section 3, "General Qualification Requirements," of SSPC-QP 1.
 - 2. In lieu of certification in conformance with the requirements in SSPC-QP 3 for this project, the Contractor may submit written documentation showing conformance with the requirements in Section 3, "General Qualification Requirements," of SSPC-QP 3.
- F. Proposed methods to control environmental conditions in accordance with the manufacturer's recommendations and these special provisions.
- G. Proposed methods to protect the coating during curing, shipping, handling, and storage.
- H. Proposed rinse water collection plan.
- I. A detailed paint repair plan for the repair of damaged areas.
- J. Procedures for containing blast media and water during application of coatings and coating repair of erected steel.
- K. Examples of proposed daily reports for all testing to be performed, including type of testing, location, lot size, time, weather conditions, test personnel, and results.

Prior to submitting the PQWP, a pre-painting meeting between the Engineer, the Contractor, and a representative from each entity performing painting for this project shall be held to discuss the requirements for the PQWP.

The Contractor shall allow the Engineer 3 weeks to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is reviewed by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Engineer's approval of the Contractor's PQWP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformity with the requirements of the plans and specifications.

The Contractor shall provide enclosures to permit cleaning and painting during inclement weather. Provisions shall be made to control atmospheric conditions inside the enclosures within specified limits during cleaning and painting operations, drying to solvent insolubility, and throughout the curing period in accordance with the manufacturer's recommendations and these special provisions. Full compensation for providing and maintaining such enclosures shall be considered as included in the prices paid for the various contract items of work requiring cleaning and painting, and no additional compensation will be allowed therefor.

Fresh, potable water with a maximum chloride content of 75 ppm and a maximum sulfate content of 200 ppm shall be used for water rinsing or pressure washing operations. No continuous recycling of rinse water will be permitted. If rinse water is collected into a tank and subsequent testing determines the collected water conforms to the specified requirements, reuse may be permitted by the Engineer if no collected water is added to the tank after sample collection for determination of conformance to specified requirements.

Column casing surfaces in contact with grout shall not be considered embedded in concrete.

Column casing surfaces to be painted with inorganic zinc coating shall be blast cleaned and painted with the single undercoat prior to shipment to the job site.

Cleaning

The surfaces to be cleaned and painted shall be dry blast cleaned in conformance with the requirements of SSPC-SP 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave surfaces with a dense, uniform, angular anchor pattern of not less than 1.6 mils nor more than 3.5 mils as measured in conformance with the requirements in ASTM Designation: D 4417.

Mineral and slag abrasives used for blast cleaning steel surfaces shall conform to the requirements for Class A, Grade 2 to 3 abrasives contained in SSPC-AB 1, "Mineral and Slag Abrasives," of the "SSPC: The Society for Protective Coatings," and shall not contain hazardous material.

Steel abrasives used for blast cleaning steel surfaces shall comply with the requirements of SSPC-AB 3, "Ferrous Metallic Abrasive," of the "SSPC: The Society for Protective Coatings." If steel abrasive is recycled through shop or field abrasive blast cleaning units, the recycled abrasive shall conform to the requirements of SSPC-AB 2, "Specification for Cleanliness of Recycled Ferrous Metallic Abrasive," of the "SSPC: The Society for Protective Coatings."

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications and a Material Safety Data Sheet shall be furnished prior to use for each shipment of blast cleaning material for steel.

Abrasive blast cleaned surfaces shall be tested by the Contractor for soluble salts using a Class A or B retrieval method as described in Technology Guide 15, "Field Methods for

Retrieval and Analysis of Soluble Salts on Steel and Other Nonporous Substrates," of the "SSPC: The Society for Protective Coatings," and cleaned so the maximum level of soluble salts does not exceed the lesser of the coating manufacturer's written recommendations or 10 micrograms per square centimeter. Areas of abrasive blast cleaned steel shall be tested at the rate of 3 tests for the first 1000 square feet prepared per day, and one test for each additional 1000 square feet or portion thereof, at locations selected by the Engineer. When less than 1000 square feet of surface area is prepared in a shift, at least 2 tests shall be performed. If levels of soluble salts exceed the maximum allowed by these special provisions, the entire area represented by the testing will be rejected. The Contractor shall perform additional cleaning and testing of rejected areas until soluble salt levels conform to these requirements.

Corners shall be chamfered to remove sharp edges.

Thermal cut edges (TCEs) to be painted shall be conditioned before blast cleaning by shallow grinding or other method approved by the Engineer to remove the thin, hardened layer of material resulting from resolidification during cooling.

Visually evident base metal surface irregularities and defects shall be removed in accordance with ASTM Designation: A 6 or AASHTO Designation: M 160 prior to blast cleaning steel. When material defects exposed by blast cleaning are removed, the blast profile shall be restored by either blast cleaning or by using mechanical tools in accordance with SSPC-SP 11, "Power Tool Cleaning to Bare Metal," of the "SSPC: The Society for Protective Coatings."

Painting

Blast cleaned surfaces shall receive a single undercoat, and a final coat where specified, consisting of an inorganic zinc coating conforming to the requirements in AASHTO Designation: M 300, Type I or Type II, except that: 1) the first 3 sentences of Section 5.6, "Primer Field Performance Requirements," shall not apply for Type II coatings, and 2) the entire Section 4.7.1 shall not apply for either type of inorganic zinc coating.

The color of the final coat of inorganic zinc coating shall match Federal Standard 595B No. 36373.

If the Contractor proposes to use a Type I coating, the Contractor shall furnish to the Engineer for review documentation as required in Section 5.6 of AASHTO Designation: M 300. The Contractor shall allow the Engineer 4 weeks to review the proposal.

If the Contractor proposes to use a Type II coating, the coating shall be selected from the qualified products list, which may be obtained from the Transportation Laboratory.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to the provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 8 hours of the start of blast cleaning. Abrasive blast cleaned steel shall not be exposed to relative humidity exceeding 85 percent prior to application of inorganic zinc coating.

The total dry film thickness of all applications of the single undercoat of inorganic zinc coating shall be not less than 4 mils nor more than 8 mils.

Damaged areas and areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Steel surfaces coated with Type II inorganic zinc coating shall be protected from conditions that may cause the coating film to dissolve. The Contractor, at the Contractor's expense, shall repair areas where the coating has dissolved by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed prior to application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

The inorganic zinc coating shall pass the following tests:

- A. The inorganic zinc coating shall have a minimum adhesion to steel of 600 psi when measured using a self-aligning adhesion tester in conformance with the requirements in ASTM Designation: D 4541. The Engineer will select 3 locations per column casing section for adhesion testing. If 2 or more of the locations tested fail to meet adhesion requirements, the section will be rejected. If one of the locations tested fails to meet adhesion requirements, an additional 3 locations shall be tested. Should any of the additional locations fail to meet adhesion requirements, the column casing section will be rejected. The Contractor, at the Contractor's expense, shall repair the rejected area by blast cleaning and repainting with inorganic zinc to the specified thickness. Test locations for areas of inorganic zinc meeting adhesion testing requirements shall be repaired by application of organic zinc primer as specified in Section 91-1.04, "Materials," of the Standard Specifications to the specified minimum dry film thickness.
- B. Areas of inorganic zinc coating where finish coats are to be applied shall be tested by the Contractor for soluble salts using a Class A or B retrieval method as described in Technology Guide 15, "Field Methods for Retrieval and Analysis of Soluble Salts on Steel and Other Nonporous Substrates," of the "SSPC: The Society for Protective Coatings," and cleaned so the maximum level of soluble salts does not exceed the lesser of the manufacturer's written recommendations or 10 micrograms per square centimeter. Areas of inorganic zinc coating shall be tested at the rate of 3 tests for the first 1000 square feet to be painted per day and one test for each additional 1000 square feet or portion thereof at locations selected by the Engineer. When less than 1000 square feet of surface area is painted in a shift, at least 2 tests shall be performed. If levels of soluble salts exceed the maximum allowed by these special provisions, the entire area represented by the testing will be rejected. The Contractor shall perform additional cleaning and testing of rejected areas until soluble salt levels conform to these requirements.

Additional Requirements for Water Borne Inorganic Zinc Primers

- A. The surface pH of the inorganic zinc primer shall be tested by wetting the surface with deionized water for a minimum of 15 minutes but no longer than 30 minutes and applying pH paper with a capability of measuring in increments of 0.5 pH units. At least 2 surface pH readings shall be taken for every 500 square feet or portion thereof. If less than 500 square feet of steel is coated in a single shift or day, at least 2 surface pH readings shall be taken for primer applied during that period. Application of finish coats will not be permitted until the surface pH is less than or equal to 7.
- B. Dry to solvent insolubility for water borne inorganic zinc primers shall be determined in conformance with the requirements in ASTM Designation: D 4752, except that water shall be the solvent. The resistance rating shall be not less than 4. Areas of inorganic zinc coating shall be tested for solvent insolubility at the rate of one test per 500 square feet or portion thereof. Inorganic zinc coating represented by the tested area that does not meet the solvent insolubility requirements will be rejected. The Contractor, at the Contractor's expense, shall repair rejected areas by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

Additional Requirements for Solvent Borne Inorganic Zinc Primers

- A. Dry to solvent insolubility for solvent borne inorganic zinc primers shall be determined in conformance with the requirements in ASTM Designation: D 4752. The resistance rating shall be not less than 4. Areas of inorganic zinc coating shall be tested for solvent insolubility at the rate of one test per 500 square feet or portion thereof. Inorganic zinc coating represented by the tested area that does not meet the solvent insolubility requirements will be rejected. The Contractor, at the Contractor's expense, shall repair rejected areas by blast cleaning and repainting with inorganic zinc coating to the specified thickness.
- B. Surface hardness of solvent borne inorganic zinc shall be a minimum 2H when measured in conformance with the requirements in ASTM Designation: D 3363. Areas of inorganic zinc coating shall be tested at the rate of one test per 500 square feet or portion thereof. Inorganic zinc coating that fails to meet the surface hardness requirements shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

The Contractor, at the Contractor's expense, shall retest all rejected areas of inorganic zinc coating after repairs have been completed.

Except as approved by the Engineer, a minimum curing time of 72 hours shall be allowed between application of inorganic zinc coating and water rinsing.

Exposed areas of inorganic zinc coating where finish coats are specified shall be thoroughly water rinsed.

The final coat of inorganic zinc coating shall be applied after testing and completion of all operations that may damage or discolor the steel surface, including correction of runs, sags, thin and excessively thick areas in the paint film, skips and holidays, dry spray, or areas of nonuniform appearance.

The area to receive the final coat of inorganic zinc coating shall be lightly roughened by abrasive blasting using an abrasive no larger than No. 30 mesh. Abrasive blasting shall remove no more than 0.6-mil of inorganic zinc. The surface to be lightly roughened shall be free from moisture, dust, grease or any deleterious material. The undercoated areas of column casing surfaces not receiving a final coat shall be protected from abrasive blast cleaning operations.

The final coat of inorganic zinc coating shall be applied to the required dry film thickness in one uniform application within 24 hours after light roughening. The dry film thickness of the final coat of inorganic zinc coating shall be not less than one mil nor more than 3 mils.

The total dry film thickness of all applications of the single undercoat and final coat of inorganic zinc coating shall be not less than 5 mils nor more than 9 mils.

Finish coats will not be required.

GROUTING

Grouting shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications and these special provisions.

For non-circular columns where the minimum gap to be filled with grout is one inch and the maximum gap is greater than 4 inches, aggregate shall be used to extend the grout, but only to the extent that the cement content of the grout is not less than 845 pounds per cubic yard of grout. California Test 541 will not be required nor will the grout be required to pass through a sieve with a 0.07-inch maximum clear opening prior to being introduced into the grout pump. Aggregate shall consist of at least 70 percent fine aggregate and approximately 30 percent pea gravel, by weight. Fine aggregate shall conform to the provisions of Section 90-2, "Materials," of the Standard Specifications. The size of pea gravel shall be such that 100 percent passes the 1/2-inch sieve, a minimum 90 percent passes the 3/8-inch sieve, and not more than 5 percent passes the No. 8 sieve.

The Contractor shall limit the height of each lift of grout to minimize undulations and displacements of the surface of the shell during grouting. Undulations in the shell surface, including undulations from fabrication and erection, shall not exceed 1/4-inch in one foot nor shall the total displacement from plan location exceed 2 inches at any point. At the Contractor's option, a bracing system or other means may be employed to restrain the casing within the specified tolerances. Except where shown on the plans, restraints shall not pass through the columns. The grout shall harden prior to placing the next lift of grout, unless a bracing system is used.

Suitable external grout injection valves shall be installed for filling of the casings. The filling operation shall begin at the bottom of the casing. Spacing of the valves shall be such that the grout will fill the gap between the casing and the column.

Casings shall be sealed at the bottom. Grout shall be pumped into the casing such that the grout head is maintained uniformly around the column, and no visible evidence of water or air is ejected at the top of the grout. The grout at the casing top shall be covered with mortar and sloped to drain. Mortar shall conform to the provisions in Section 51-1.135, "Mortar," of the Standard Specifications.

Casings shall be positioned with spacers to center the casing around the existing column at the location shown on the plans. Spacers may be welded to the inside of the casing. Grout shall not be permitted to flow across shoulders or lanes occupied by public traffic, or to flow into gutters or other drainage facilities.

Clamps, valves, injection ports, lifting ears, and other accessories shall be completely removed not less than 24 hours after placing grout. Voids shall be filled with mortar and finished flush with the exterior surface of the casing.

MEASUREMENT AND PAYMENT

Column casings will be measured and paid for in conformance with the provisions in Section 55-4, "Measurement and Payment," of the Standard Specifications and these special provisions.

The contract price paid per pound for column casing shall include full compensation for furnishing all labor, materials (including polyethylene and adhesive), tools, equipment, and incidentals, and for doing all the work involved in column casings filled with grout, complete in place, including drainage piping, cleaning and painting of structural steel, and testing, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.73 SIGN STRUCTURES

Sign structures and foundations for overhead signs shall conform to the provisions in Section 56-1, "Overhead Sign Structures," of the Standard Specifications, "Steel Structures" of these special provisions, and the following requirements.

Before commencing fabrication of sign structures, the Contractor shall submit 2 sets of working drawings to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The working drawings shall include sign panel dimensions, span lengths, post heights, anchorage layouts, proposed splice locations, a snugging and tensioning pattern for anchor bolts and high-strength bolted connections, and details for permanent steel anchor bolt templates. The working drawings shall be supplemented with a written quality control program that includes methods, equipment, and personnel necessary to satisfy the requirements specified herein.

Working drawings shall be 22" x 34" or 11" x 17" in size and each drawing and calculation sheet shall include the State assigned designations for the sign structure type and reference as shown on the contract plans, District-County-Route-Post Mile, and contract number.

The Engineer shall have 30 days to review the sign structure working drawings after a complete submittal has been received. No fabrication or installation of sign structures shall be performed until the working drawings are approved in writing by the Engineer.

Should the Engineer fail to complete the review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the sign structure working drawings, the delay will be

considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Steel bolts not designated on the plans as high strength (HS) or stainless steel shall be for general applications and shall conform to the requirements in ASTM Designation: A 307.

A permanent steel template shall be used to maintain the proper anchor bolt spacing.

One top nut, one leveling nut, and 2 washers shall be provided for the upper threaded portion of each anchor bolt.

Flatness of surfaces for the following shall conform to the requirements in ASTM Designation: A 6/A 6M:

1. Base plates that are to come in contact with concrete, grout, or washers and leveling nuts
2. Plates in high-strength bolted connections

No holes shall be made in members unless the holes are shown on the plans or are approved in writing by the Engineer.

Longitudinal seam welds shall have 60 percent minimum penetration, except that within 6 inches of circumferential welds, longitudinal seam welds shall be complete joint penetration (CJP) groove welds. In addition, longitudinal seam welds on structures having telescopic pole segment splices shall be CJP groove welds on the female end for a length on each end equal to the designated slip fit splice length plus 6 inches.

Steel members used for overhead sign structures shall receive nondestructive testing (NDT) in conformance with AWS D1.1 and the following:

1.

Weld Location	Weld Type	Minimum Required NDT
Splice welds around the perimeter of tubular sections, poles, and arms.	CJP groove weld with backing ring	100% UT ^a or RT ^b
Longitudinal seam welds	CJP or PJP ^c groove weld	Random 25% MT ^d
Longitudinal seam welds within 6 inches of a circumferential splice.	CJP groove weld	100% UT or RT
Welds attaching base plates, flange plates, or pole or mast arm plates, to poles or arm tubes.	CJP groove weld with backing ring and reinforcing fillet	t > 3/16 inch: 100%UT and MT t < 3/16 inch: 100% MT after root weld pass and final weld pass t = pole or arm thickness
	External (top) fillet weld for socket-type connections	100% MT

- a ultrasonic testing
- b radiographic testing
- c partial joint penetration
- d magnetic particle testing

2. The acceptance and repair criteria for UT of welded joints where any of the members are less than 5/16 inch thick or where tubular sections are less than 13 inches in diameter shall conform to the requirements in AWS D1.1, Section 6.13.3.1. A written procedure

approved by the Engineer shall be used when performing this UT. These written procedures shall conform to the requirements in AWS D1.1, Annex K. The acceptance and repair criteria for other welded joints receiving UT shall conform to the requirements in AWS D1.1, Section 6, Table 6.3 for cyclically loaded nontubular connections.

3. The acceptance and repair criteria for radiographic or real time image testing shall conform to the requirements of AWS D1.1 for tensile stress welds.
4. For longitudinal seam welds, the random locations for NDT will be selected by the Engineer. The cover pass shall be ground smooth at the locations to be tested. If repairs are required in a portion of a tested weld, the repaired portion shall receive NDT, and additional NDT shall be performed on untested portions of the weld. The additional NDT shall be performed on 25 percent of that longitudinal seam weld. After this additional NDT is performed and if more repairs are required, then that entire longitudinal seam weld shall receive NDT.

Circumferential welds and base plate to post welds may be repaired only one time without written permission from the Engineer.

All ferrous metal parts of tubular sign structures shall be galvanized and shall not be painted.

Full compensation for furnishing anchor bolt templates and for testing of welds shall be considered as included in the contract price paid per pound for furnish sign structure, and no additional compensation will be allowed therefor.

10-1.74 ROADSIDE SIGNS

Roadside signs shall be furnished and installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

The Contractor shall furnish roadside sign panels in conformance with the provisions in "Furnish Sign" of these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications and AWP A Use Category System: UC4A, Commodity Specification A or B.

Marker panels mounted on a post with a roadside sign shall be considered to be sign panels and will not be paid for as markers.

10-1.75 FURNISH SIGN

Signs shall be fabricated and furnished in accordance with details shown on the plans, the Traffic Sign Specifications, and these special provisions.

Traffic Sign Specifications for California sign codes are available for review at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Traffic Sign Specifications for signs referenced with Federal MUTCD sign codes can be found in Standard Highway Signs Book, administered by the Federal Highway Administration, which is available for review at:

http://mutcd.fhwa.dot.gov/ser-shs_millennium.htm

Information on cross-referencing California sign codes with the Federal MUTCD sign codes is available at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Temporary or permanent signs shall be free from blemishes that may affect the serviceability and detract from the general sign color and appearance when viewing during daytime and nighttime from a distance of 25 feet. The face of each finished sign shall be uniform, flat, smooth, and free of defects, scratches, wrinkles, gel, hard spots, streaks, extrusion marks, and air bubbles. The front, back, and edges of the sign panels shall be free of router chatter marks, burns, sharp edges, loose rivets, delaminated skins, excessive adhesive over spray and aluminum marks.

QUALITY CONTROL FOR SIGNS

The requirements of "Quality Control for Signs" in this section shall not apply to construction area signs.

No later than 14 days before sign fabrication, the Contractor shall submit a written copy of the quality control plan for signs to the Engineer for review. The Engineer will have 10 days to review the quality control plan. Sign fabrication shall not begin until the Engineer approves the Contractor's quality control plan in writing. The Contractor shall submit to the Engineer at least 3 copies of the approved quality control plan. The quality control plan shall include, but not be limited to the following requirements:

- A. Identification of the party responsible for quality control of signs,
- B. Basis of acceptance for incoming raw materials at the fabrication facility,
- C. Type, method and frequency of quality control testing at the fabrication facility,
- D. List (by manufacturer and product name) of process colors, protective overlay film, retroreflective sheeting and black non-reflective film,
- E. Recommended cleaning procedure for each product, and
- F. Method of packaging, transport and storage for signs.

No legend shall be installed at the project site. Legend shall include letters, numerals, tildes, bars, arrows, route shields, symbols, logos, borders, artwork, and miscellaneous characters. The style, font, size, and spacing of the legend shall conform to the Standard Alphabets published in the FHWA Standard Highway Signs Book. The legend shall be oriented in the same direction in accordance with the manufacturer's orientation marks found on the retroreflective sheeting.

On multiple panel signs, legend shall be placed across joints without affecting the size, shape, spacing, and appearance of the legend. Background and legend shall be wrapped around interior edges of formed panel signs as shown on plans to prevent delamination.

The following notation shall be placed on the lower right side of the back of each sign where the notation will not be blocked by the sign post or frame:

- A. PROPERTY OF STATE OF CALIFORNIA,
- B. Name of the sign manufacturer,
- C. Month and year of fabrication,
- D. Type of retroreflective sheeting, and
- E. Manufacturer's identification and lot number of retroreflective sheeting.

The above notation shall be applied directly to the aluminum sign panels in 1/4-inch upper case letters and numerals by die-stamp and applied by similar method to the fiberglass reinforced plastic signs. Painting, screening, or engraving the notation will not be allowed. The notation shall be applied without damaging the finish of the sign.

Signs with a protective overlay film shall be marked with a dot of 3/8 inch in diameter. The dot placed on white border shall be black, while the dot placed on black border shall be white. The dot shall be placed on the lower border of the sign before application of the protective overlay film and shall not be placed over the legend and bolt holes. The application method and exact location of the dot shall be determined by the manufacturer of the signs.

For sign panels that have a minor dimension of 48 inches or less, no splice will be allowed in the retroreflective sheet except for the splice produced during the manufacturing of the retroreflective sheeting. For sign panels that have a minor dimension greater than 48 inches, only one horizontal splice will be allowed in the retroreflective sheeting.

Unless specified by the manufacturer of the retroreflective sheeting, splices in retroreflective sheeting shall overlap by a minimum of one inch. Splices shall not be placed within 2 inches from edges of the panels. Except at the horizontal borders, the splices shall overlap in the direction from top to bottom of the sign to prevent moisture penetration. The retroreflective sheeting at the overlap shall not exhibit a color difference under the incident and reflected light.

Signs exhibiting a significant color difference between daytime and nighttime shall be replaced immediately.

Repairing sign panels will not be allowed except when approved by the Engineer.

The Department will inspect signs at the Contractor's facility and delivery location, and in accordance with Section 6, "Control of Materials," of the Standard Specifications. The Engineer will inspect signs for damage and defects before and after installation.

Regardless of kind, size, type, or whether delivered by the Contractor or by a common carrier, signs shall be protected by thorough wrapping, tarping, or other methods to ensure that signs are not damaged by weather conditions and during transit. Signs shall be dry during transit and shipped on palettes, in crates, or tier racks. Padding and protective materials shall be placed between signs as appropriate. Finished sign panels shall be transported and stored by method that protects the face of signs from damage. The Contractor shall replace wet, damaged, and defective signs.

Signs shall be stored in dry environment at all times. Signs shall not rest directly on the ground or become wet during storage. Signs, whether stored indoor or outdoor, shall be free standing. In areas of high heat and humidity signs shall be stored in enclosed climate-controlled trailers or containers. Signs shall be stored indoor if duration of the storage will exceed 30 days.

Screen processed signs shall be protected, transported and stored as recommended by the manufacturer of the retroreflective sheeting.

When requested, the Contractor shall provide the Engineer test samples of signs and materials used at various stages of production. Sign samples shall be 12" x 12" in size with applied background, letter or numeral, and border strip.

The Contractor shall assume the costs and responsibilities resulting from the use of patented materials, equipment, devices, and processes for the Contractor's work.

SHEET ALUMINUM

Alloy and temper designations for sheet aluminum shall be in accordance with ASTM Designation: B 209.

The Contractor shall furnish the Engineer a Certificate of Compliance in conformance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the sheet aluminum.

Sheet aluminum shall be pretreated in accordance to ASTM Designation: B 449. Surface of the sheet aluminum shall be cleaned, deoxidized, and coated with a light and tightly adherent chromate conversion coating free of powdery residue. The conversion coating shall be Class 2 with a weight between 10 milligrams per square foot and 35 milligrams per square foot, and an average weight of 25 milligrams per square foot. Following the cleaning and coating process, the sheet aluminum shall be protected from exposure to grease, oils, dust, and contaminants.

Sheet aluminum shall be free of buckles, warps, dents, cockles, burrs, and defects resulting from fabrication.

Base plate for standard route marker shall be die cut.

RETROREFLECTIVE SHEETING

The Contractor shall furnish retroreflective sheeting for sign background and legend in conformance with ASTM Designation: D 4956 and "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Retroreflective sheeting shall be applied to sign panels as recommended by the retroreflective sheeting manufacturer without stretching, tearing, and damage.

Class 1, 3, or 4 adhesive backing shall be used for Type II, III, IV, VII, VIII, and IX retroreflective sheeting. Class 2 adhesive backing may also be used for Type II retroreflective sheeting. The adhesive backing shall be pressure sensitive and fungus resistant.

When the color of the retroreflective sheeting determined from instrumental testing is in dispute, the Engineer's visual test will govern.

PROCESS COLOR AND FILM

The Contractor shall furnish and apply screened process color, non-reflective opaque black film, and protective overlay film of the type, kind, and product that are approved by the manufacturer of the retroreflective sheeting.

The Contractor shall furnish the Engineer a Certificate of Compliance in accordance to Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the screened process color, non-reflective opaque black film, and protective overlay film.

The surface of the screened process color shall be flat and smooth. When the screened process colors determined from the instrumental testing in accordance to ASTM Designation: D 4956 are in dispute, the Engineer's visual test will govern.

The Contractor shall provide patterns, layouts, and set-ups necessary for the screened process.

The Contractor may use green, red, blue, and brown reverse-screened process colors for background and non-reflective opaque black film or black screened process color for legend. The coefficient of retroreflection for reverse-screened process colors on white retroreflective sheeting shall not be less than 70 percent of the coefficient of retroreflection specified in ASTM Designation: D 4956.

The screened process colors and non-reflective opaque black film shall have the same outdoor weatherability as that of the retroreflective sheeting.

After curing, screened process colors shall withstand removal when tested by applying 3M Company Scotch Brand Cellophane Tape No. 600 or equivalent tape over the color and removing with one quick motion at 90° angle.

SINGLE SHEET ALUMINUM SIGN

Single sheet aluminum signs shall be fabricated and furnished with or without frame. The Contractor shall furnish the sheet aluminum in accordance to "Sheet Aluminum" of these special provisions. Single sheet aluminum signs shall be fabricated from sheet aluminum alloy 6061-T6 or 5052-H38.

Single Sheet aluminum signs shall not have a vertical splice in the sheet aluminum. For signs with depth greater than 48 inches, one horizontal splice will be allowed in the sheet aluminum.

Framing for single sheet aluminum signs shall consist of aluminum channel or rectangular aluminum tubing. The framing shall have a length tolerance of $\pm 1/8$ inch. The face sheet shall be affixed to the frame with rivets of 3/16-inch diameter. Rivets shall be placed within the web of channels and shall not be placed less than 1/2 inch from edges of the sign panels. Rivets shall be made of aluminum alloy 5052 and shall be anodized or treated with conversion coating to

prevent corrosion. The exposed portion of rivets on the face of signs shall be the same color as the background or legend where the rivets are placed.

Finished signs shall be flat within a tolerance of $\pm 1/32$ inch per linear foot when measured across the plane of the sign in all directions. The finished signs shall have an overall tolerance within $\pm 1/8$ inch of the detailed dimensions.

Aluminum channels or rectangular aluminum tubings shall be welded together with the inert gas shielded-arc welding process using E4043 aluminum electrode filler wires as shown on the plans. Width of the filler shall be equal to wall thickness of smallest welded channel or tubing.

LAMINATED PANEL SIGN

Laminated panel signs shall consist of two sheet aluminum laminated to a honeycomb core and extruded aluminum frame to produce flat and rigid panels of one-inch or 2-1/2-inch nominal thickness.

The face of laminated panel signs shall be fabricated from sheet aluminum alloy 6061-T6 or 5052-H32 of 0.063-inch thickness. The back of laminated panel signs shall be fabricated from sheet aluminum alloy 3003-H14 of 0.040-inch thickness. The Contractor shall furnish sheet aluminum as provided in "Sheet Aluminum" of these special provisions.

The core material shall be phenolic impregnated kraft paper honeycomb and fungus resistant in accordance to Military Specification MIL-D-5272. The honeycomb cell size shall be 1/2 inch. Weight of the kraft paper shall be 80 pounds and impregnated minimum 18 percent by weight.

A laminating adhesive that can produce a resilient oil and water-resistant bond shall be used to adhere the extruded aluminum frame and the honeycomb core to the sheet aluminum. Edge and interior delamination occur when a 0.010-inch thick feeler gauge of 1/2 inch in length can be inserted into a depth of more than 1/2 inch between the extruded aluminum frame and the sheet aluminum. Laminated panel sign with delamination will be rejected.

Laminated panels shall be able to resist a wind load of 33 pounds per square foot for the following simple span lengths with a bending safety factor of 1.25:

Panel Type	Nominal Panel Thickness	Simple Span Length
A	one inch	9 feet 0 inch
B	one inch	9 feet 0 inch
	2-1/2 inch	14 feet 6 inches
H	2-1/2 inch	14 feet 6 inches

The tensile strength of laminated panels shall be at least 20 pounds per square inch when tested in accordance with the following modification and with ASTM Designations: C 297 and C 481, Cycle B after aging. Instead of spraying with hot water, the specimen shall be totally immersed in 158° F hot water. When requested by the Engineer or the Transportation Laboratory, at least one test sample of 12" x 12" in size shall be taken for every 2,000 square feet of the panel production cycle or of the total factory production order, whichever occurs first.

Rivets used to secure the sheet aluminum to the perimeter frame shall be fabricated from aluminum alloy 5052 and anodized or treated with a conversion coating to prevent corrosion.

Size of the aluminum rivets shall be 3/16 inch in diameter and placed at the corners of the laminated panels. Color of the exposed portion of the rivets shall be the same color as the sign background or legend on which the rivets are placed. Rivets or stainless steel screws shall be placed in holes drilled during fabrication in the perimeter frame.

On laminated multiple panel signs, a closure H-Section shall be placed in the top channel of the bottom panel. Perimeter frame of adjoining panel shall accommodate the closure H-Section in the closed position.

For signs with a depth of 5 feet 0 inch or less, the laminated panels shall be fabricated with no horizontal joints, splices or seams. For signs with a depth of greater than 5 feet 0 inch, the laminated panels may be fabricated in two panels.

The face of laminated panels shall be flat with a tolerance of $\pm 3/32$ inch per linear foot when measured across the plane of each panel in all directions. Where laminated panels adjoin, the gap between adjoining edges from one corner to the other corner shall not deviate by more than 1/32 inch. Non-adjoining edges from one corner to the other corner shall not deviate by more than 1/8 inch from a straight plane. The front and back sheet aluminum shall be flush with the perimeter frame. The panel edges shall be smooth.

Laminated panel signs shall be within +1/8 inch or -1/2 inch of the detailed dimensions. The difference in length between adjoining panels of multiple panel signs shall not be greater than 1/2 inch.

Overhead laminated panel signs shall be Type A and have a nominal thickness of one inch.

For overhead laminated signs with a length of 24 feet or less, the laminated panels shall be fabricated with no vertical joints, splices or seams.

The perimeter frame of Type A overhead laminated panels shall be connected by self-tapping hex head stainless steel screws. Sealant shall be placed at the corners of the perimeter frame to prevent moisture penetration. The perimeter frame of Type A panels shall consist of extruded channel edges on the vertical sides and consist of modified "H" section extrusion on the horizontal sides. The modified "H" section extrusion acts as an integral retainer track for affixing the bolts to provide blind fastening of panels to the structure support.

The Contractor shall furnish mounting hardware for overhead laminated panel signs, such as closure H-sections, clamps, bolts, nuts, and washers. The clamps shall be cast aluminum alloy with a minimum tensile strength of 25 kips per square inch. Bolt torque used for installing clamps shall not exceed 100 inch-pounds.

MEASUREMENT AND PAYMENT

Furnishing signs (except for construction area signs) will be measured by the square foot and the quantity to be paid for will be the total area, in square feet, of the sign panel types installed in place.

The contract price paid per square foot for furnish sign of the types specified in the Engineer's estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating and furnishing the

signs as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing and installing protective overlay on signs shall be considered as included in the contract price paid per square foot for furnish sign of the various types and no separate payment will be made therefor.

10-1.76 ALTERNATIVE PIPE

Alternative pipe culverts must comply with Section 62, "Alternative Culverts," of the Standard Specifications.

10-1.77 PLASTIC PIPE

Plastic pipe shall conform to the provisions in Section 64, "Plastic Pipe," of the Standard Specifications.

10-1.78 REINFORCED CONCRETE PIPE

Reinforced concrete pipe shall conform to the provisions in Section 65, "Reinforced Concrete Pipe," of the Standard Specifications and these special provisions.

GENERAL

Where embankment will not be placed over the top of the pipe, a relative compaction of not less than 85 percent shall be required below the pipe spring line for pipe installed using Method 1 backfill in trench, as shown on Standard Plan A62D. Where the pipe is to be placed under the traveled way, a relative compaction of not less than 90 percent shall be required unless the minimum distance between the top of the pipe and the pavement surface is the greater of 4 feet or one half of the outside diameter of the pipe.

Except as otherwise designated by classification on the plans or in the specifications, joints for culvert and drainage pipes shall conform to the plans or specifications for standard joints.

MATERIALS

The concrete for reinforced concrete pipe shall contain not less than 470 pounds of cementitious material per cubic yard and have a water-cementitious material ratio that does not exceed 0.40 by weight. Supplementary cementitious material is optional. Reinforcement shall have a minimum cover of 1 inch.

Special reinforced concrete pipe, having concrete cover over the steel reinforcement greater than the cover specified in AASHTO Designation: M 170, shall conform to the provisions in Section 65-1.02, "Materials," and Section 65-1.02A, "Circular Reinforced Concrete Pipe," of the Standard Specifications, except the width of crack produced by the D-load test specified in AASHTO Designation: M 170 shall be the width determined by the following formula:

$$b = \frac{t - 3/8d}{t - 3/8d - C} \times 0.01 \text{ inch}$$

Where:

- b = Width of crack to be produced in lieu of the 0.01-inch crack specified in AASHTO Designation: M 170
- t = Wall thickness of pipe, inches
- d = Effective depth of the section to be tested, feet
- C = Concrete cover over steel reinforcement in excess of cover specified in AASHTO Designation: M 170

Reinforced concrete pipe that is to be hydrostatically tested shall be strength tested by the 3-edge bearing method to a maximum D-load of 10 percent greater than the 0.01-inch cracking D-load specified in AASHTO Designation: M 170 or to the actual D-load required to produce a 0.01-inch crack, whichever is the lesser.

Special oval shaped reinforced concrete pipe, having concrete cover over the steel reinforcement greater than the cover specified in AASHTO Designation: M 207, shall conform to the provisions in Section 65-1.02, "Materials," and Section 65-1.02B, "Oval Shaped Reinforced Concrete Pipe," of the Standard Specifications, except the width of crack produced by the D-load test specified in AASHTO Designation: M 207 shall be the width determined by the following formula:

$$b = \frac{t - 3/8d}{t - 3/8d - C} \times 0.01 \text{ inch}$$

Where:

- b = Width of crack to be produced in lieu of the 0.01-inch crack specified in AASHTO Designation: M 207
- t = Wall thickness of pipe, inches
- d = Effective depth of the section to be tested, feet
- C = Concrete cover over steel reinforcement in excess of cover specified in AASHTO Designation: M 207

Oval shaped reinforced concrete pipe that is to be hydrostatically tested shall be strength tested by the 3-edge bearing method to a maximum D-load of 10 percent greater than the 0.01-inch cracking D-load specified in AASHTO Designation: M 207 or to the actual D-load required to produce a 0.01-inch crack, whichever is the lesser.

MEASUREMENT AND PAYMENT

The Department does not pay any additional cost for excess concrete cover over steel reinforcement.

10-1.79 CORRUGATED METAL PIPE

Corrugated steel pipes shall conform to the provisions in Section 66, "Corrugated Metal Pipe," of the Standard Specifications and these special provisions.

Asphaltic mastic coating or polymeric sheet coating substituted for bituminous coating shall be placed on the outside and inside surfaces of the pipe.

Corrugated steel pipe shall be fabricated from zinc-coated steel sheet.

Timber bulkheads shall be constructed and placed across the ends of unconnected corrugated metal pipe as shown on the plans. Wood for timber bulkheads shall be construction heart grade redwood at least one inch thick. Full compensation for constructing and placing timber bulkheads shall be considered as included in the contract price paid per linear foot for the size of corrugated metal pipe involved and no separate payment will be made therefor.

Pipe reducers will be measured and paid for by the linear foot as the corrugated metal pipe of the larger diameter connected to the reducer.

10-1.80 OVERTSIDE DRAIN

Hot mix asphalt overside drains shall conform to the provisions in Section 69, "Overside Drains," of the Standard Specifications.

10-1.81 MISCELLANEOUS FACILITIES

Flared end sections, steel pipe inlets and precast concrete pipe manholes shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

10-1.82 INLET DEPRESSION

This work consists of constructing inlet depressions around drainage inlets.

Hot mix asphalt used in the construction of inlet depressions in shoulder areas of roadways shall conform to the requirements in Section 39, "Hot Mix Asphalt," of the Standard Specifications.

Portland cement concrete used in the construction of inlet depressions placed in the shoulder areas of roadways shall conform to the requirements for portland concrete cement shoulders in Section 51, "Concrete Structures," of the Standard Specifications.

Where portland cement concrete pavement is to be placed around or next to inlet depressions, the inlet depressions shall not be constructed to final grade until after the pavement has been constructed adjacent to the inlet depression.

Portland cement concrete for inlet depression shall be placed on prepared base material compacted to not less than 95 percent relative compaction. After placement to the lines and grades shown on the plans, the surface shall be finished with a float and troweled smooth. Concrete adjacent to isolation joints shall be finished with an edger. The surface of the concrete

shall then be broom finished to create a surface having a coefficient of friction of not less than 0.30 as determined by California Test 342. If water is necessary, the water shall be applied to the surface immediately in advance of the brooming. The concrete shall be cured as provided in Section 90-7.02, "Curing Pavement," of the Standard Specifications.

Hot mix asphalt used in the construction of inlet depressions will be measured and paid for as hot mix asphalt (miscellaneous area).

Full compensation for handwork used in the construction of inlet depressions shall be considered as included in the contract price paid per square yard for place hot mix asphalt (miscellaneous area) and no additional compensation will be allowed therefor.

Concrete used in the construction of inlet depressions will be measured and paid for as minor concrete (minor structure).

Full compensation for forming and constructing inlet depression, including any necessary soil compaction or disposal of forming materials shall be considered as included in the contract price paid per cubic yard for minor concrete (minor structure) and no additional compensation will be allowed therefor.

10-1.83 SLOPE PROTECTION

Slope protection shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications and these special provisions.

Rock slope protection fabric must be Class 8.

10-1.84 SLOPE PAVING

Slopes under the ends of bridges, where shown on the plans, shall be paved in conformance with the provisions in Section 72-6, "Slope Paving," of the Standard Specifications and these special provisions.

The location of construction joints shall be subject to the approval of the Engineer. Placement of slope paving shall be scheduled so that the work, including placement, finishing, and application of curing, is completed in any section bounded by permissible construction joints on the same day that the work is started in that section.

Areas of slope paving shown on the plans to have a grooved finish shall be scored by dragging a finishing tool over the struck-off surface or by any other means which will result in a surface conforming to the details shown on the plans.

Prior to placing the permanent slope paving, the Contractor shall construct a test panel at least 4' x 6' at the site for approval by the Engineer. The test panel shall be constructed of the same materials as are proposed for the permanent work and shall be finished and cured as specified for the permanent work. Additional test panels shall be constructed as necessary until a

panel is produced which conforms to the requirements herein, before constructing other slope paving.

10-1.85 MISCELLANEOUS CONCRETE CONSTRUCTION

Concrete curb, gutter, sidewalk, curb ramp and gutter depression shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Curb ramp detectable warning surface shall consist of raised truncated domes constructed or installed on curb ramps in conformance with the details shown on the plans and these special provisions. At the option of the Contractor, the detectable warning surface shall be prefabricated, cast-in-place, or stamped into the surface of the curb ramp. The color of the detectable warning surface shall be yellow conforming to Federal Standard 595B, Color No. 33538.

Prefabricated detectable warning surface shall be in conformance with the requirements established by the Department of General Services, Division of State Architect and be attached in conformance with the manufacturer's recommendations.

Cast-in-place and stamped detectable warning surfaces shall be painted in conformance with the provisions in Section 59-6, "Painting Concrete," of the Standard Specifications.

The finished surfaces of the detectable warning surface shall be free from blemishes.

Prior to constructing the cast-in-place or stamping the detectable warning surface, the Contractor shall demonstrate the ability to produce a detectable warning surface conforming to the details shown on the plans and these special provisions by constructing a 24" x 24" test panel.

The manufacturer shall provide a written 5-year warranty for prefabricated detectable warning surfaces, guaranteeing replacement when there is defect in the dome shape, color fastness, sound-on-cane acoustic quality, resilience, or attachment. The warranty period shall begin upon acceptance of the contract.

Full compensation for constructing or furnishing and installing curb ramp detectable warning surfaces shall be considered as included in the contract price paid per cubic yard for minor concrete (curb ramp) and no separate payment will be made therefor.

10-1.86 MISCELLANEOUS IRON AND STEEL

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

10-1.87 MISCELLANEOUS METAL (BRIDGE)

Miscellaneous metal (bridge) shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Attention is directed to "Welding" of these special provisions.

Miscellaneous metal (bridge) shall consist of the miscellaneous bridge metal items listed in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

10-1.88 BRIDGE DECK DRAINAGE SYSTEM

Bridge deck drainage systems shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Self-tapping screws used for sleeve connections shall be hex-head stainless steel, installed in holes drilled to fit the self-tapping screws, conforming to the requirements of ASTM Designation: A 276, Type 304.

At the Contractor's option, fiberglass pipes and fittings with the same diameter and minimum bend radius as those shown on the plans may be substituted for welded steel pipe in deck drain systems.

Fiberglass pipe and fittings shall conform to the requirements in ASTM Designation: D 2996, and shall have a minimum short-term rupture strength of 30,000 psi. The adhesive type recommended by the manufacturer shall be used for joining pipe and fittings. Fiberglass pipe not enclosed in a box girder cell or encased in concrete shall be manufactured from ultraviolet-resistant resin pigmented with concrete-gray color, or be coated with a concrete-gray resin-rich exterior coating. Paint shall not be used. Fiberglass pipe treated with ultraviolet protection shall withstand a minimum of 2,500 hours of accelerated weathering when tested in conformance with the requirements in ASTM Designation: G 154. Lamps shall be UV-B (313 nm wavelength). The resting cycle shall be 4 hours of ultraviolet exposure at 140° F, and then 4 hours of condensate exposure at 120° F. After testing, the surface of the pipe shall exhibit no fiber exposure, crazing, or checking, and only a slight chalking or color change.

Support spacing for fiberglass pipe shall be the same as shown on the plans for welded steel pipe. Pipe supports shall have a width of not less than 1.5 inches.

A Certificate of Compliance for fiberglass pipe and fittings shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall include all laboratory test results conforming to the provisions specified herein.

For drainage piping NPS 8 or smaller, the Contractor shall have the option of substituting polyvinyl chloride (PVC) plastic pipe and fittings with the same diameter and minimum bend radius as shown on the plans for welded steel pipe, which is:

- A. Enclosed in a box girder cell and exposed for a length not greater than 20 feet within the cell, or
- B. encased in concrete.

The PVC plastic pipe and fittings shall be Schedule 40 conforming to the requirements of ASTM Designations: D 1785. The maximum support spacing for PVC plastic pipe shall be 6 feet.

Couplings used to connect PVC plastic pipe or fiberglass pipe to steel shall be threaded or flanged. The sleeve connections shown on the plans shall not be used for either PVC plastic pipe or fiberglass pipe.

If PVC plastic pipe or fiberglass pipe is substituted for welded steel pipe, the quantity of drainage piping will be computed on the basis of the dimensions and details shown on the plans, and no change in the quantities to be paid for will be made because of the use of PVC plastic pipe or fiberglass pipe.

Bridge deck drainage systems will be measured and paid for by the pound in the same manner specified for miscellaneous metal (bridge) in Section 75-1.06, "Measurement," and Section 75-1.07, "Payment," of the Standard Specifications.

10-1.89 CHAIN LINK FENCE

Chain link fence shall be Type CL-6 and shall conform to the provisions in Section 80, "Fences," of the Standard Specifications.

10-1.90 MARKERS AND DELINEATORS

Markers and delineators shall conform to the provisions in Section 82, "Markers and Delineators," of the Standard Specifications and these special provisions.

Markers and delineators on flexible posts shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Flexible posts shall be made from a flexible white plastic which shall be resistant to impact, ultraviolet light, ozone, and hydrocarbons. Flexible posts shall resist stiffening with age and shall be free of burns, discoloration, contamination, and other objectionable marks or defects which affect appearance or serviceability.

Retroreflective sheeting for metal and flexible target plates shall be the retroreflective sheeting designated for channelizers, markers, and delineators conforming to the requirements in ASTM Designation: D 4956-95 and in conformance with the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

10-1.91 METAL BEAM GUARD RAILING

Metal beam guard railing shall be constructed in conformance with the provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" of these special provisions.

Line posts shall be wood, steel, or plastic. Blocks shall be wood or plastic.

ALTERNATIVE FLARED TERMINAL SYSTEM

Alternative flared terminal system shall be furnished and installed as shown on the plans and in conformance with these special provisions.

The allowable alternatives for a flared terminal system shall consist of one of the following or a Department approved equal.

- A. **TERMINAL SYSTEM (TYPE FLEAT)** - Terminal system (Type FLEAT) shall be a Flared Energy Absorbing Terminal 350 manufactured by Road Systems, Inc., located in Big Spring, Texas, and shall include items detailed for terminal system (Type FLEAT) shown on the plans. The Flared Energy Absorbing Terminal 350 can be obtained from the distributor, Universal Industrial Sales, P.O. Box 699, Pleasant Grove, UT 84062, telephone (801) 785-0505 or from the distributor, Gregory Highway Products, 4100 13th Street, S.W., Canton, OH 44708, telephone (330) 477-4800.
- B. **TERMINAL SYSTEM (TYPE SRT)** - Terminal system (Type SRT) shall be an SRT-350 Slotted Rail Terminal (8-post system) as manufactured by Trinity Industries, Inc., and shall include items detailed for terminal system (Type SRT) shown on the plans. The SRT-350 Slotted Rail Terminal (8-post system) can be obtained from the manufacturer, Trinity Industries, Inc., P.O. Box 99, 950 West 400S, Centerville, UT 84014, telephone (800) 772-7976.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that the terminal systems furnished conform to the contract plans and specifications, conform to the prequalified design and material requirements, and were manufactured in conformance with the approved quality control program.

Terminal systems shall be installed in conformance with the manufacturer's installation instructions and these requirements. Each terminal system installed shall be identified by painting the type of terminal system in neat black letters and figures 2 inches high on the backside of the rail element between system posts numbers 4 and 5.

For terminal system (Type SRT), the steel foundation tubes with soil plates attached shall be, at the Contractor's option, either driven, with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes shall be backfilled with selected earth, free of rock, placed in layers approximately 4 inches thick and each layer shall be moistened and thoroughly compacted. The wood terminal posts shall be inserted into the steel foundation tubes by hand and shall not be driven. Before the wood terminal posts are inserted, the inside surfaces of the

steel foundation tubes to receive the wood posts shall be coated with a grease which will not melt or run at a temperature of 149° F or less. The edges of the wood terminal posts may be slightly rounded to facilitate insertion of the post into the steel foundation tubes.

For terminal system (Type FLEAT), the soil tubes shall be, at the Contractor's option, driven with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes shall be backfilled with selected earth, free of rock, placed in layers approximately 4 inches thick and each layer shall be moistened and thoroughly compacted. Wood posts shall be inserted into the steel foundation tubes by hand. Before the wood terminal posts are inserted, the inside surfaces of the steel foundation tubes to receive the wood posts shall be coated with a grease which will not melt or run at a temperature of 149° F or less. The edges of the wood posts may be slightly rounded to facilitate insertion of the post into the steel foundation tubes.

Surplus excavated material remaining after the terminal system has been installed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

The contract unit price paid for alternative flared terminal system shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing alternative flared terminal system, complete in place, including excavation, backfill and disposal of surplus material, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.92 VEGETATION CONTROL (MINOR CONCRETE)

This work shall consist of furnishing and constructing vegetation control as specified in these special provisions, as shown on the plans and as directed by the Engineer.

MATERIALS

Minor Concrete

Concrete for vegetation control shall consist of a mixture of portland cement concrete and concrete reinforcing fibers. Concrete shall conform to the provisions for minor concrete in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions. Components of the concrete for vegetation control shall be incorporated homogeneously at the concrete plant before delivery to the work site.

Reinforcing fibers for minor concrete shall consist of polypropylene fibers with an engineered sinusoidal contoured profile, manufactured specifically for use as concrete reinforcement. Reinforcing fiber shall consist of a blended ratio of 4 parts of coarse monofilament fibers with maximum individual fiber lengths of 2-inch \pm 1/2-inch and 1 part of fine fibrillated polypropylene fibers of various lengths and thickness. Reinforcing fibers shall be of a commercial source, combined with the concrete in proportions as recommended by the manufacturer.

Grout

Grout for vegetation control shall conform to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications and these special provisions.

Not more than 188 pounds of cement shall be used for each cubic yard of material produced.

Aggregate for grout shall be commercial quality concrete sand.

Color of grout shall match the color of the minor concrete used to construct the vegetation control.

Landscape Fabric

Landscape fabric shall be manufactured from thermally spun bonded polypropylene fabric and shall conform to the following:

Specification	Minimum Requirement
Grab Tensile Strength	135 lbs
Grab Elongation	70%
UV Resistance	70% @ 150 hours
Weight	3 ounces per square yard

Staples for landscape fabric shall be 2 inches in width, 6 inches in length and 11-gauge wire.

A copy of the manufacturer's product sheet, together with instructions for installation, shall be furnished to the Engineer 5 business days before installation.

A Certificate of Compliance for the landscape fabric shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SITE PREPARATION

Clearing

Areas to receive vegetation control shall be cleared of trash and debris in conformance with Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Vegetation shall be removed to the ground. Cleared trash, debris and removed vegetation shall be disposed of outside the highway right of way in conformance with Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Earthwork

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

After clearing, areas to receive vegetation control shall be excavated. Where vegetation control abuts the existing surfacing, the edge of the existing surfacing shall be on a neat line or shall be cut on a neat line to a minimum depth of 0.17-foot before removing the surfacing. The area to receive vegetation control shall be excavated to maintain planned flow lines, slope gradient and contours of the project site.

After excavation, areas to receive vegetation control shall be graded to a smooth, uniform surface and compacted to a relative compaction of not less than 90 percent.

PLACEMENT

Landscape fabric shall be stapled to prevent shifting during concrete placement. Fabric shall lie flat, smooth, without bulges or wrinkles, and maintain uniform contact with the soil surface.

Grout shall be spread to completely fill voids as shown on the plans.

Minor concrete shall be struck off and compacted until a layer of mortar has been brought to the surface. Minor concrete shall receive a broom finish.

Two weakened plane joints shall be constructed in the minor concrete at each post location, perpendicular to the rail and in line with the edge of the grout. The joints shall be constructed to a minimum depth of one inch by scoring with a tool that will leave the corners rounded and ensure free movement of concrete at the joint.

The finished grade of vegetation control shall be uniform; maintaining planned flow lines, slope gradient and contours of the project site.

MEASUREMENT AND PAYMENT

Quantities of vegetation control (minor concrete) will be measured by the square yard computed from measurements of actual areas placed. Vegetation control (minor concrete) placed outside the dimensions shown on the plans will not be paid for.

The contract price paid per square yard for vegetation control (minor concrete) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing vegetation control (minor concrete), including clearing trash, debris and vegetation and excavation, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.93 DECORATIVE FENCE

Decorative fence shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

Decorative fence fabric shall conform to the chain link fabric provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

The decorative fence fabric shall be 9-gage (0.148-inch diameter), Type IV, Class B, bonded black vinyl coated fabric, conforming to the requirements in AASHTO Designation: M 181.

The strength of the bond between the coating material and steel of the bonded black vinyl coated decorative fence fabric shall be equal to or greater than the cohesive strength of the polyvinyl chloride (PVC) coating material.

Decorative Fence will be measured by the linear foot from end to end along the face of the railing.

The contract price paid per linear foot for Decorative Fence shown in the Engineer's Estimate, shall include full compensation for furnishing all labor, materials, (including decorative fence fabric), tools, equipment, and incidentals, and for doing all the work involved in constructing and installing the Decorative Fence, complete in place, as shown on the plans, including furnishing working drawings and cleaning and painting, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.94 TUBULAR HANDRAILING

Tubular handrailing shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications.

10-1.95 CABLE RAILING

Cable railing shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications.

10-1.96 CONCRETE BARRIER

Concrete barriers shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

At those locations shown on the plans, concrete barrier markers shall be cemented to the barrier in conformance with the manufacturer's recommendations.

10-1.97 CONCRETE BARRIER (TYPE K)

Concrete barrier (Type K) shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

Concrete barrier (Type K) shall consist of precast units conforming to the provisions for temporary railing (Type K) in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications, except that removable panels shall not be used and the concrete barrier (Type K) shall remain in place at the completion of the contract.

Temporary railing (Type K) reflectors on concrete barrier (Type K) shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Full compensation for furnishing and installing temporary railing (Type K) reflectors on concrete barrier (Type K) shall be considered as included in the contract price paid per linear foot for concrete barrier (Type K) and no additional compensation will be allowed therefor.

10-1.98 TRANSITION RAILING (TYPE WB)

Transition railing (Type WB) shall be furnished and installed in conformance with details shown on the plans, the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

The 10-gage rail elements shall conform to the requirements of Class B, Type 1 three beam guard railing as shown in AASHTO Designation: M 180. End caps shall conform to the requirements of Class A, Type 1 three beam guard railing as shown in AASHTO Designation: M 180.

Surplus excavated material remaining after the transitional railing (Type WB) has been constructed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

The contract unit price paid for transition railing (Type WB) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing transition railing (Type WB), complete in place, including drilling holes for wood posts, driving posts, backfill, and disposal of surplus material, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.99 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING

Thermoplastic traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Thermoplastic material shall be free of lead and chromium, and shall conform to the requirements in State Specification PTH-02ALKYD.

Retroreflectivity of the thermoplastic traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of $250 \text{ mcd m}^{-2} \text{ lx}^{-1}$. Yellow thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of $150 \text{ mcd m}^{-2} \text{ lx}^{-1}$.

Where striping joins existing striping, as shown on the plans, the Contractor shall begin and end the transition from the existing striping pattern into or from the new striping pattern a sufficient distance to ensure continuity of the striping pattern.

Thermoplastic traffic stripes shall be applied at the minimum thickness and application rate as specified below. The minimum application rate is based on a solid stripe of 4 inches in width.

Minimum Stripe Thickness (inch)	Minimum Application Rate (lb/ft)
0.098	0.34

Thermoplastic traffic stripes and pavement markings shall be free of runs, bubbles, craters, drag marks, stretch marks, and debris.

10-1.100 PAINT TRAFFIC STRIPE AND PAVEMENT MARKING

Painted traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Traffic stripe and pavement marking paint shall conform to the requirements in State Specification No. PTWB-01.

The color of the painted traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6628-01.

Retroreflectivity of the paint traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White painted traffic stripes and pavement markings shall have a minimum initial retroreflectivity of $250 \text{ mcd m}^{-2} \text{ lx}^{-1}$. Yellow painted traffic stripes and pavement markings shall have a minimum initial retroreflectivity of $150 \text{ mcd m}^{-2} \text{ lx}^{-1}$.

10-1.101 PAVEMENT MARKERS

Pavement markers shall be placed in conformance with the provisions in Section 85, "Pavement Markers," of the Standard Specifications and these special provisions.

Attention is directed to "Traffic Control System For Lane Closure" of these special provisions regarding the use of moving lane closures during placement of pavement markers with bituminous adhesive.

The Contractor shall furnish the Engineer certificates of compliance for the pavement markers in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Retroreflective pavement markers shall be marked as abrasion resistant on the body of the markers.

SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS

10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

- A. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.
- B. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
- C. At intervals of one month during the plant establishment period.

COST BREAK-DOWN

The Contractor shall furnish the Engineer a cost break-down for the contract lump sum item of highway planting. The cost break-down table shall be submitted to the Engineer for approval within 15 working days after the contract has been approved. The cost break-down table will be approved, in writing, by the Engineer before any partial payment will be made for the item of highway planting.

The cost break-down shall be completed and furnished in the format shown in the sample of the cost break-down included in this section. Line item descriptions of work shown in the samples are the minimum to be submitted. Additional line item descriptions of work may be designated by the Contractor. If the Contractor elects to designate additional line item descriptions of work, the quantity, value and amount for those line items shall be completed in the same manner as for the line item descriptions shown in the samples. The line items and quantities given in the sample are to show the manner of preparing the cost break-down to be furnished by the Contractor.

The Contractor shall determine the quantities required to complete the work shown on the plans. The quantities and their values shall be included in the cost break-down submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-down submitted for approval.

The sum of the amounts for the line items of work listed in the cost break-down table for highway planting work shall be equal to the contract lump sum price bid for the work. Overhead and profit shall be included in each individual line item of work listed in the cost break-down table.

No adjustment in compensation will be made in the contract lump sum price paid for highway planting due to differences between the quantities shown in the cost break-down table furnished by the Contractor and the quantities required to complete the work as shown on the plans and as specified in these special provisions.

Individual line item values in the approved cost break-down table will be used to determine partial payments during the progress of the work and as the basis for calculating an adjustment in compensation for the contract lump sum item of highway planting due to changes in line items of work ordered by the Engineer. When the total value of ordered changes to line items of work increases or decreases the lump sum price bid for highway planting by more than 25 percent, the adjustment in compensation will be determined in the same manner specified for increases and decreases in the total pay quantity of an item of work in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

HIGHWAY PLANTING COST BREAK-DOWN

Contract No. 0F5804

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
COMMERCIAL FERTILIZER (PACKETS)	EA	96		
ROADSIDE CLEARING	LS	1		
IRON SULFATE	LB	4.5		
SOIL AMENDMENT	CY	0.9		
MULCH	CY	1.1		
PLANT (GROUP U)	EA	12		
TREE STAKING	EA	12		

TOTAL _____

10-2.02 EXISTING HIGHWAY PLANTING

In addition to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications, work performed in connection with existing highway planting shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

MAINTAIN EXISTING PLANTED AREAS

Existing planted areas shall be maintained as directed by the Engineer. Maintaining existing planted areas will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

10-2.03 (BLANK)

10-2.04 HIGHWAY PLANTING

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

HIGHWAY PLANTING MATERIALS

Mulch

Mulch must be green material and must comply with the following:

1. The mulch provider must be a compost producer and a participant in the United States Composting Council (USCC) Seal of Testing Assurance (STA) program.
2. The green material producer must be fully permitted as a compost producer in accordance with requirements of the California Integrated Waste Management Board (CIWMB), Local Enforcement Agencies (LEA) and any other State and Local Agencies that regulate solid waste facilities. If exempt from State permitting requirements, the composting facility must certify that it follows all guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.
3. Green material may be derived from any single or mixture of chipped, shredded, or ground vegetation; or clean processed recycled wood products.
4. Compost green materials such that weed seeds, pathogens and deleterious materials are reduced as specified under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3.
5. Green material must not contain paint, petroleum products, herbicides, fungicides or other chemical residues harmful to animal life or plant growth. Compost must possess no objectionable odors.
6. Metal concentrations in green material must not exceed the maximum metal concentrations listed in Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.
7. Green material must comply with the following table:

Physical and Chemical Requirements		
Property	Test Method	Requirement
pH	TMECC 04.11-A Elastometric pH 1:5 Slurry Method pH Units	6.0-8.5
Soluble Salts	TMECC 04.10-A Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm)	0-10.0
Moisture Content	TMECC 03.09-A Total Solids & Moisture at 70+/- 5 deg C % Wet Weight Basis	N/A
Organic Matter Content	TMECC 05.07-A Loss-On-Ignition Organic Matter Method (LOI) % Dry Weight Basis	30-100
Maturity	TMECC 05.05-A Germination and Vigor Seed Emergence Seedling Vigor % Relative to Positive Control	N/A N/A
Stability	TMECC 05.08-B Carbon Dioxide Evolution Rate mg CO ₂ -C/g OM per day	N/A
Particle Size	TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis	Inches % Passing 3 99% 3/8 < 25% Max. Length 4 inches
Pathogen	TMECC 07.01-B	

	Fecal Coliform Bacteria < 1000 MPN/gram dry wt.	Pass
Pathogen	TMECC 07.01-B Salmonella < 3 MPN/4 grams dry wt.	Pass
Physical Contaminants	TMECC 02.02-C Man Made Inert Removal and Classification: Plastic, Glass and Metal % > 4mm fraction	Combined Total: < 1.0
Physical Contaminants	TMECC 02.02-C Man Made Inert Removal and Classification: Sharps (Sewing needles, straight pins and hypodermic needles) % > 4mm fraction	None Detected

NOTE: TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

8. Before mulch application, submit a copy of the green material producer's Compost Technical Data Sheet and a copy of the compost producers STA certification. The Compost Technical Data Sheet must include laboratory analytical test results, directions for product use, and a list of product ingredients.
9. Before mulch application, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Commercial Fertilizer (Packets)

Commercial fertilizer (packet) shall be slow or controlled release and shall be in a biodegradable packet form. The packet shall gradually release nutrients over a 12-month period. Each packet shall have a weight of 10 g ± 1 g and shall have the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	10
Water Soluble Potash	5

ROADSIDE CLEARING

Before preparing planting areas, trash and debris shall be removed from these areas as required under Construction Site Management of these special provisions.

The project area shall be cleared as specified herein:

- A. Weeds shall be killed and removed within the entire highway right of way, within the project limits, except for existing planting areas to be maintained, and excluding median areas, new and existing pavement, curb, sidewalk and other surfaced areas.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

- A. Trash and debris shall be removed.
- B. Rodents shall be controlled.
- C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 6 inches in length, whichever occurs first.
- D. Existing ground cover shall be killed and removed from within the 6-foot diameter areas specified for each proposed plant location within the existing ground cover areas.
- E. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.

Weed Control

Weed control shall also conform to the following:

- A. Stolon type weeds shall be killed with glyphosate.
- B. Removed weeds and ground cover shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Roadside clearing work shall not include work required to be performed as clearing and grubbing as specified in Section 16, "Clearing and Grubbing," of the Standard Specifications.

PLANTING

Backfill material for plant holes must be a mixture of soil and soil amendment. The quantity of soil amendment shall be as shown on the Plant List. Thoroughly mix backfill material and uniformly distribute throughout the entire depth of the plant hole without clods and lumps.

Apply or place commercial fertilizer (packets) and iron sulfate at the time of planting and at the rates shown on the Plant List.

Place commercial fertilizer packets in the backfill of each plant at the time of planting and at the rate shown on the Plant List to within 6 inches to 8 inches of the soil surface and approximately one inch from the roots. When more than one fertilizer packet is required per plant, the packets must be distributed evenly around the root ball.

PLANT ESTABLISHMENT WORK

The plant establishment period shall be Type 2 and shall not be less than 250 working days.

Attention is directed to "Relief From Maintenance and Responsibility" in these special provisions regarding relief from maintenance and protection.

Weeds within plant basins, including basin walls, shall be controlled by hand pulling.

Weeds within ground cover areas and outside of plant basins shall be controlled by killing.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period.

After 125 working days of the plant establishment period have been completed, replacement of plants, except for ground cover plants, shall be one-gallon size for seedlings, pot and liner size

plants; 5-gallon size for one-gallon size plants; 15-gallon size for 5-gallon size plants; and other plant replacement plants shall be the same size as originally specified.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

The Contractor shall remove all tree staking at least 15 days prior to the completion of the plant establishment period.

Full compensation for the quantity of water used in the performance of the work, will be considered as included on the lump sum price paid for Highway Planting and Plant Establishment Work and no separate payment will be made therefor.

Full compensation for providing truck watering of the trees during the plant establishment period shall be considered as included in the lump sum price paid for Highway Planting and Plant Establishment Work and no separate payment will be made therefor.

SECTION 10-3. ELECTRICAL SYSTEMS

10-3.01 DESCRIPTION

Traffic signals, lighting (city street), modify lighting and sign illumination, ramp metering systems, modify traffic monitoring stations, interconnection conduit and conductors, and maintaining existing traffic management system elements during construction shall conform to the provisions in Section 86, "Electrical Systems," of the Standard Specifications and these special provisions.

Communication conduit is included in the following structures:

- A. Clinton Keith Road OC (Bridge No. 56-0721)

Traffic signal work shall be performed at the following locations:

- A. Location 1, Clinton Keith Road/Hidden Springs Road
- B. Location 2, Clinton Keith Road/I-15 Southbound Ramps
- C. Location 3, Clinton Keith Road/I-15 Northbound Ramps
- D. Location 4, Clinton Keith Road/Arya Drive

Ramp meter work shall be performed at the following locations:

- A. Clinton Keith Road/I-15 Southbound On-Ramp
- B. Clinton Keith Road/I-15 Northbound On-Ramp

Modify traffic monitoring station work shall be performed at the following location:

- A. Clinton Keith Road/I-15 Southbound On-Ramp

10-3.02 COST BREAK-DOWN

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

The cost break-down shall include the following items in addition to those listed in the Standard Specifications:

- CDMA Wireless Cellular Data Communications Assembly
- Battery Backup System
- Emergency Vehicle Preemption Sensor
- Video Detection System (VIDS)

Communication System – GPRS Modem Assembly, Network to Serial Adapter Card, CAT 5E Cable, LAN Extender, and Ethernet Switch

10-3.03 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS

Traffic signal system shutdowns shall be limited to periods between the hours of 9:00 a.m. and 3:00 p.m.

Traffic signal system shutdowns shall be limited to periods allowed for lane closures listed or specified in "Maintaining Traffic" of these special provisions.

10-3.04 MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION

Traffic Management System (TMS) elements include, but are not limited to ramp metering (RM) system, communication system, traffic monitoring stations, video image vehicle detection system (VIVDS), microwave vehicle detection system (MVDS), loop detection system, changeable message sign (CMS) system, extinguishable message sign (EMS) system, highway advisory radio (HAR) system, closed circuit television (CCTV) camera system, roadway weather information system (RWIS), visibility sensor, and fiber optic system.

Existing TMS elements, including detection systems, identified on the plans and located within the project limits shall remain in place and be protected from damage. If the construction activities require existing TMS elements to be nonoperational or off line, and if temporary or portable TMS elements are not shown on the plans, the Contractor shall provide for temporary or portable TMS elements. The Contractor shall receive the Engineer's approval on the type of temporary or portable TMS elements and installation method.

Before work is performed, the Engineer, the Contractor, and the Department's Traffic Operations Electrical representatives shall jointly conduct a pre-construction operational status check of all existing TMS elements and each element's communication status with the Traffic Management Center (TMC), including existing TMS elements that are not shown on the plans and elements that may not be impacted by the Contractor's activities. The Department's Traffic Operations Electrical representatives will certify the TMS elements' location and status, and provide a copy of the certified list of the existing TMS elements within the project limits to the Contractor. The status list will include the operational, defined as having full functionality, and the nonoperational components.

The Contractor shall obtain written approval from the Engineer at least 72 hours before interrupting existing TMS elements' communication with the TMC that will result in the elements being nonoperational or off line. The Contractor shall notify the Engineer at least 72 hours before starting excavation activities.

Traffic monitoring stations and their associated communication systems, which were verified to be operational during the pre-construction operational status check, shall remain operational on freeway/highway mainline at all times, except:

1. For a duration of up to 15 days on any continuous segment of the freeway/highway longer than 3 miles
2. For a duration of up to 60 days on any continuous segment of the freeway/highway shorter than 3 miles

If the construction activities require existing detection systems to be nonoperational or off line for a longer time period or the spacing between traffic monitoring stations is more than the specified criteria above, and temporary or portable detection operations are not shown on the plans, the Contractor shall provide provisions for temporary or portable detection operations. The Contractor shall receive the Engineer's approval on the type of detection and installation before installing the temporary or portable detection.

If existing TMS elements shown on the plans or identified during the pre-construction operational status check, except traffic monitoring stations, are damaged or fail due to the Contractor's activity, where the elements are not fully functional, the Engineer shall be notified immediately. If the Contractor is notified by the Engineer that existing TMS elements have been damaged, have failed or are not fully functional due to the Contractor's activity, the damaged or failed TMS elements, excluding structure-related elements, shall be repaired or replaced, at the Contractor's expense, within 24 hours. For a structure-related elements, the Contractor shall install temporary or portable TMS elements within 24 hours. For nonstructure-related TMS elements, the Engineer may approve temporary or portable TMS elements for use during the construction activities.

The Contractor shall demonstrate that repaired or replaced elements operate in a manner equal to or better than the replaced equipment or as directed by the Engineer. If the Contractor fails to perform required repairs or replacement work, as determined by the Engineer, the State may perform the repair or replacement work and the cost will be deducted from monies due to the Contractor.

A TMS element shall be considered nonoperational or off line for the duration of time that active communications with the TMC is disrupted, resulting in messages and commands not transmitted from or to the TMS element.

The Contractor shall provide provisions for replacing existing TMS elements within the project limits, including detection systems, that were not identified on the plans or during the pre-construction operational status check that became damaged due to the Contractor's activities.

If the pre-construction operational status check identified existing TMS elements, then the Contractor, the Engineer, and the Department's Traffic Operations Electrical representatives shall jointly conduct a post construction operational status check of all existing TMS elements and each element's communication status with the TMC. The Department's Traffic Operations Electrical representatives will certify the TMS elements' status and provide a copy of the certified list of the existing TMS elements within the project limits to the Contractor. The status list will include the operational, defined as having full functionality, and the nonoperational components. TMS elements that cease to be functional between pre and post construction status checks shall be repaired at the Contractor's expense and as directed by the Engineer.

The Engineer will approve, in writing, the schedule for final replacement, the replacement methods and the replacement elements, including element types and installation methods before

repair or replacement work is performed. The final TMS elements shall be new and of equal or better quality than the existing TMS elements.

PAYMENT

The contract lump sum price paid for maintaining existing traffic management system elements during construction shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in maintaining existing traffic management system elements as shown on the plans, specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

If no electrical work exists on the project and no TMS elements are identified within the project limits, the pre-construction operational status check will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Furnishing and installing temporary or portable TMS elements that are not shown on the plans, but are required when an existing TMS element becomes nonoperational or off line due to construction activities, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Furnishing and installing temporary or portable TMS elements and replacing TMS elements that are not shown on the plans nor identified during the pre-construction operational status check and were damaged by construction activities will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

If the Contractor is required to submit provisions for the replacement of TMS elements that were not identified, the provisions will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

10-3.05 CAST-IN-DRILLED-HOLE CONCRETE PILE FOUNDATIONS

GENERAL

Summary

This work includes constructing cast-in-drilled-hole concrete pile foundations for traffic signal and lighting standards.

Comply with Section 86-2.03, "Foundations," of the Standard Specifications and "Piling" of these special provisions.

MATERIALS

Concrete must contain not less than 590 pounds of cementitious material per cubic yard.

CONSTRUCTION

For standards located in sidewalk areas, the pile foundation must be:

1. Placed to final sidewalk grade before the sidewalk is placed
2. Square for the top 4 inches

Use sleeve nuts on Type 1-A and 1-B standards. The bottom of the base plate must be flush with finished grade.

PAYMENT

Payment for cast-in-drilled-hole concrete pile foundations shall conform to the provisions in Section 86-8, "Payment," of the Standard Specifications.

10-3.06 STANDARDS, STEEL PEDESTALS, AND POSTS

Standards, steel pedestals, and posts for traffic signal and lighting standards shall conform to the provisions in Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications and the following requirements.

Steel bolts not designated on the plans as high-strength (HS) or stainless steel shall be for general applications and shall conform to the requirements in ASTM Designation: A 307.

Anchor bolts shall conform to the requirements in ASTM Designation: F 1554, Grade 36. High-strength (HS) anchor bolts shall conform to the requirements in ASTM Designation: F 1554, Grade 105.

The sign mounting hardware shall be installed at the locations shown on the plans.

Non-illuminated street name signs shall be installed on signal mast arms using a minimum 3/4" x 0.020" round edge stainless steel strap and saddle bracket. The strap shall be wrapped at least twice around the mast arm, tightened, and secured with a 3/4" stainless strap seal. The sign panel shall be leveled and hardware securely tightened.

Handhole reinforcement rings for standards, steel pedestals, and posts shall be continuous around the handholes.

Type 1 standards shall be assembled and set with the handhole on the downstream side of the pole in relation to traffic or as shown on the plans.

At Locations 1 and 4, Type 1 standards shall be spun aluminum unless otherwise specified.

10-3.07 CONDUIT

Conduit to be installed underground shall be Type 3, Schedule 80 unless otherwise specified. At Locations 1 and 4, conduit to be installed underground shall be Type 1 unless otherwise specified.

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 3, Schedule 80.

Conduit runs shown on the plans to be located behind curbs may be installed in the street, within 3 feet of, and parallel with the face of the curb, by the trenching in pavement method in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard

Specifications. Pull boxes shall be located behind the curb or at the locations shown on the plans.

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, and controller cabinets shall be sealed with an approved type of sealing compound.

At the option of the Contractor, the final 2 feet of conduit entering a pull box in a reinforced concrete structure may be Type 4.

10-3.08 CONDUCTORS, CABLES, AND WIRING

Splices shall be insulated by "Method B".

Conductors shall be wrapped around projecting end of conduit in pull boxes, as shown on the plans. Cables shall be secured to the projecting end of conduit in pull boxes to prevent pulling of cables without removing the securing device.

Signal Interconnect Cable (SIC) shall be the 6-pair type.

10-3.09 SERVICE

Continuous welding of exterior seams in service equipment enclosures is not required.

Service equipment enclosures shall be the aluminum type.

Circuit breakers shall be the cable-in/cable-out type, mounted on non-energized clips. All circuit breakers shall be mounted vertically with the up position of the handle being the "ON" position.

Each service shall be provided with up to 2 main circuit breakers which shall disconnect ungrounded service entrance conductors. Where the "Main" circuit breaker consists of 2 circuit breakers as shown on the plans or required in the special provisions, each of the circuit breakers shall have a minimum interrupting capacity of 10,000 A, rms.

An engraved phenolic nameplate shall be installed with stainless steel rivets on the exterior of the front panel indicating the identification number and the service address of the service cabinet enclosure. Character size shall be a minimum of 5 mm in height.

Service conduits between the utility owned power poles and the service equipment enclosures shall not be installed until service locations have been verified by the serving utility.

Where a new service is to be installed, the Contractor shall notify the Engineer in writing at least 5 working days prior to the date service is required.

The Contractor shall be responsible for contacting the power company, arranging and providing for the electrical service connections and ensuring that adequate notice is provided to the serving utility in advance of need.

10-3.10 STATE-FURNISHED CONTROLLER ASSEMBLIES

The Model 170 and 2070 controller assemblies, excluding anchor bolts, will be State-furnished as provided under "Materials" of these special provisions.

The Contractor shall construct each controller cabinet foundation as shown on the plans for Model 332A and 334 cabinets (including furnishing and installing anchor bolts), shall install the controller cabinet on the foundation, and shall make field wiring connections to the terminal blocks in the controller cabinet.

A listing of field conductor terminations, in each State-furnished controller cabinet, will be furnished free of charge to the Contractor at the site of the work.

State forces will maintain controller assemblies. The Contractor's responsibility for controller assemblies shall be limited to conforming to the provisions in Section 6-1.02, "State-Furnished Materials," of the Standard Specifications.

The Contractor shall acquire the traffic signal controller assembly from the State of California, Department of Transportation (Caltrans) and shall compensate the State of California for costs incurred in obtaining, testing and supplying a traffic signal controller assembly. This fee does not supersede any other fee charged by Caltrans for review, inspection or fieldwork performed by State staff as a result of the Contractor's work. If the fee has not been paid prior to permit issuance, full payment shall be made to the Caltrans cashier prior to starting any traffic signal work authorized by this permit and at least thirty days before the controller is needed for installation. The Contractor shall give the State's representative not less than 10 working days written advance notice prior to picking up the controller assembly; however, when the controller assembly arrives at the Caltrans warehouse located in the City of San Bernardino, the Contractor shall have three working days to pick up equipment upon notification. If the Contractor fails to pick up equipment upon notification of its arrival at the warehouse, the Contractor will be charged \$50.00 a day for storing equipment. When the equipment is requested by the Contractor or upon its arrival, Caltrans will provide a time and location for picking up the controller assemblies. The controller assemblies shall be furnished by the Contractor.

The Contractor shall install the controller assembly, its cabinet as specified on the plans, and all ancillary equipment.

The cost of picking up and delivering each controller assembly shall be included in the lump sum price paid for the system being installed, and no additional compensation shall be allowed therefor.

The Contractor shall arrange to have a signal technician qualified to work on the controller and employed by the controller manufacturer or his representative, present at the time the equipment is turned on.

Full compensation for installing the controller assembly and foundation, including the programming and functional testing of the equipment, is included in the contract lump sum price paid for the system being installed, and no additional compensation will be allowed therefor.

10-3.11 LIGHT EMITTING DIODE SIGNAL MODULE

GENERAL

Summary

This work includes installing LED signal module. Comply with Section 86, "Electrical Systems," of the Standard Specifications.

Use LED signal module as the light source for the following traffic signal faces:

1. 12-inch section
2. 8-inch section
3. 12-inch arrow section
4. 12-inch programmed visibility (PV) section

Submittals

Before shipping LED signal modules to job site, submit the following to the Transportation Laboratory:

1. Delivery form including district number, EA, and contact information
2. List containing all LED signal module serial numbers anticipated for use
3. LED signal modules

Quality Control and Assurance

Module must be one listed on the Pre-Qualified Products List for LED traffic signals at:

http://www.dot.ca.gov/hq/esc/approved_products_list

The State will test LED signal module shipments as specified in ANSI/ASQ Z1.4.. Testing will be completed within 30 days of delivery to the Transportation Laboratory. LED signal modules tested or submitted for testing must be representative of typical production units. LED and circular LED signal modules will be tested as specified in California Test 604. Arrow, U-turn, and bicycle LED signal modules will be tested as specified in California Test 3001. All parameters of the specification may be tested on the modules. LEDs must be spread evenly across the module. LED arrow indication must provide the minimum initial luminous intensity listed. Measurements will be performed at the rated operating voltage of 120 V(ac).

Delays resulting from submittal of non-compliant materials do not relieve you from executing the contract within the allotted time. Non-compliant materials will be rejected. You must resubmit new LED for retesting and pick up the failed units within 7 days of notification. You must provide new LED signal modules and allow a minimum of 30 days for the retest. You must pay for all shipping and handling costs related to testing and retesting. Delays resulting from resubmittal and retesting are your responsibility and no extra time will be allowed.

After testing, you must pick up the tested LED signal modules from the Transportation Laboratory and deliver to the job site.

Warranty

The manufacturer must provide a written warranty against defects in materials and workmanship for LED signal modules for a minimum period of 48 months after installation of LED signal modules. Replacement LED signal modules must be provided within 15 days after receipt of failed LED modules at your expense. The State pays for shipping the failed modules to you. All warranty documentation must be submitted to the Engineer before installation. Replacement LED signal modules must be delivered to State Maintenance Electrical Shop at 175 Cluster Street, San Bernardino.

MATERIALS

Minimum power consumption for LED signal module must be 5 W.

LED signal module must have an operational lifecycle rating of 48 months. During the operational lifecycle, LED signal module must meet all parameters of this specification.

LED signal module must be designed for installation in the door frame of standard traffic signal housing.

LED signal module must:

1. Be 4 pounds maximum weight
2. Be manufactured for 12-inch circular and arrow , and 8-inch circular section
3. Be from the same manufacturer
4. Be the same model for each size
5. Be sealed units with:
 - 5.1. 2 color-coded conductors for power connection, except for lane control LED signal modules use 3 color-coded conductors.
 - 5.2. Printed circuit board and power supply contained inside and complying with Chapter 1, Section 6 of TEES published by the Department.
 - 5.3. Lens that is:
 - 5.3.1. Integral to the units
 - 5.3.2. Convex or flat with a smooth outer surface
 - 5.3.3. Made of UV stabilized plastic or glass, and withstands UV exposure from direct sunlight for 48 months without exhibiting evidence of deterioration
 - 5.4. 1-piece EPDM gasket
6. Include 3-foot long conductors with quick disconnect terminals attached
7. Be sealed in door frames
8. Fit into existing traffic signal section housing and comply with ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads"

Individual LEDs must be wired so catastrophic loss or failure of 1 LED will not result in loss of more than 5 percent of the signal module light output. Failure of an individual LED in a string must not result in loss of entire string or other indication.

No special tools for installation are allowed.

12-inch Arrow

Comply with Section 9.01 of ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads" for arrow indications.

LED signal module must:

1. Be weather tight and connect directly to electrical wiring.
2. Be capable of optical unit replacement.
3. Be a single, self-contained device, ready for installation into traffic signal housing.
4. Have manufacturer's name, trademark, model number, serial number, lot number, month and year of manufacture, and required operating characteristics, including rated voltage, power consumption, and volt-ampere, permanently marked on the back of the module.
5. Have a symbol of module type and color. Symbol must be an inch in diameter. Color must be written out in 0.50 inch high letters next to the symbol.
6. Be AllnGaP technology for red and yellow indications and gallium nitride technology for green indications.
7. Be ultra bright type rated for 100,000 hours of continuous operation from -40 °C to +74 °C.
8. Have a maximum power consumption as follows:

Power Consumption Requirements

LED Signal Module Type	Power Consumption (Watts)					
	Red		Yellow		Green	
	25 °C	74 °C	25 °C	74 °C	25 °C	74 °C
12-inch circular	11	17	22	25	15	15
8-inch circular	8	13	13	16	12	12
12-inch arrow	9	12	10	12	11	11
12-inch U-turn	9	12	10	12	11	11
Bicycle	11	17	22	25	15	15
Programmed Visibility	11	17	22	25	15	15
Lane Control (X)	9	12	--	--	--	--
Lane Control (Arrow)	--	--	--	--	11	11

Lens may be tinted, or may use transparent film or materials with similar characteristics to enhance "ON/OFF" contrasts. Tinting or other materials to enhance "ON/OFF" contrast must not affect chromaticity and must be uniform across the face of the lens.

If polymeric lens is used, surface coating or chemical surface treatment must be applied for front surface abrasion resistance.

Power supply must be integral to the module.

Internal components must be adequately supported to withstand mechanical shock and vibration from high winds and other sources.

Lens and LED signal module material must comply with the ASTM specifications for that material.

Enclosures containing either the power supply or electronic components of LED signal module, except lenses, must be made of UL94VO flame-retardant material.

If a specific mounting orientation is required, the LED signal module must have prominent and permanent vertical markings for accurate indexing and orientation within the signal housing. Markings must include an up arrow, or the word "UP" or "TOP."

LED signal module must meet or exceed the following values when operating at 25 °C:

Minimum Initial Intensities for Circular Indications (cd)

Angle (v,h)	8-inch			12-inch		
	Red	Yellow	Green	Red	Yellow	Green
2.5, ±2.5	157	314	314	399	798	798
2.5, ±7.5	114	228	228	295	589	589
2.5, ±12.5	67	133	133	166	333	333
2.5, ±17.5	29	57	57	90	181	181
7.5, ±2.5	119	238	238	266	532	532
7.5, ±7.5	105	209	209	238	475	475
7.5, ±12.5	76	152	152	171	342	342
7.5, ±17.5	48	95	95	105	209	209
7.5, ±22.5	21	43	43	45	90	90
7.5, ±27.5	12	24	24	19	38	38
12.5, ±2.5	43	86	86	59	119	119
12.5, ±7.5	38	76	76	57	114	114
12.5, ±12.5	33	67	67	52	105	105
12.5, ±17.5	24	48	48	40	81	81
12.5, ±22.5	14	29	29	26	52	52
12.5, ±27.5	10	19	19	19	38	38
17.5, ±2.5	19	38	38	26	52	52
17.5, ±7.5	17	33	33	26	52	52
17.5, ±12.5	12	24	24	26	52	52
17.5, ±17.5	10	19	19	26	52	52
17.5, ±22.5	7	14	14	24	48	48
17.5, ±27.5	5	10	10	19	38	38

Minimum Luminance for Arrows, U-turn, Bicycle, Lane Control, and PV Indications (FL)

	Red	Yellow	Green
Arrow Indication	1,605	3,210	3,210

LED signal module must meet or exceed the following illumination values for 48 months when operating over a temperature range of -40 °C to + 74 °C. Yellow LED signal module must meet or exceed the following illumination values for 48 months, when operating at 25 °C:

Minimum Maintained Intensities for Circular Indications (cd)

Angle (v,h)	8-inch			12-inch		
	Red	Yellow	Green	Red	Yellow	Green
2.5, ±2.5	133	267	267	339	678	678
2.5, ±7.5	97	194	194	251	501	501
2.5, ±12.5	57	113	113	141	283	283
2.5, ±17.5	25	48	48	77	154	154
7.5, ±2.5	101	202	202	226	452	452
7.5, ±7.5	89	178	178	202	404	404
7.5, ±12.5	65	129	129	145	291	291
7.5, ±17.5	41	81	81	89	178	178
7.5, ±22.5	18	37	37	38	77	77
7.5, ±27.5	10	20	20	16	32	32
12.5, ±2.5	37	73	73	50	101	101
12.5, ±7.5	32	65	65	48	97	97
12.5, ±12.5	28	57	57	44	89	89
12.5, ±17.5	20	41	41	34	69	69
12.5, ±22.5	12	25	25	22	44	44
12.5, ±27.5	9	16	16	16	32	32
17.5, ±2.5	16	32	32	22	44	44
17.5, ±7.5	14	28	28	22	44	44
17.5, ±12.5	10	20	20	22	44	44
17.5, ±17.5	9	16	16	22	44	44
17.5, ±22.5	6	12	12	20	41	41
17.5, ±27.5	4	9	9	16	32	32

Minimum Maintained Luminance for Arrow, U-turn, Bicycle, Lane Control, and PV Indications (FL)

	Red	Yellow	Green
Arrow Indication	1,610	3,210	3,210

LED signal module must comply with the following chromaticity requirements for 48 months when operating over a temperature range of -40 °C to +74 °C.

Chromaticity Standards (CIE Chart)

Red	Y: not greater than 0.308, or less than 0.998 - x
Yellow	Y: not less than 0.411, nor less than 0.995 - x, nor greater than 0.452
Green	Y: not less than 0.506 - 0.519x, nor less than 0.150 + 1.068x, nor more than 0.730 - x

LED signal module must operate:

1. At a frequency of 60 Hz ± 3 Hz, over a voltage range from 95 V(ac) to 135 V(ac), without perceptible flicker to the unaided eye. Fluctuations of line voltage must have no visible effect on luminous intensity of the indications. Rated voltage for measurements must be 120 V(ac).
2. Compatible with currently used controller assemblies, including solid state load switches, flashers, and conflict monitors. Comply with TEES Chapters 3 and 6. If a 20 mA alternating current or less is applied to the unit, the voltage read across the 2 leads must be 15 V(ac) or less.

Wiring and terminal block must comply with Section 13.02 of ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads." Electrical connection for each Type 1 LED signal module must be 2 secured, color-coded, 3-foot long, 600 V(ac), 20 AWG minimum stranded jacketed copper wires. Wires must comply with NEC, rated for service at +105 °C.

LED signal module on-board circuitry must:

1. Include voltage surge protection to withstand high-repetition noise transients. The voltage surge protection must comply with NEMA Standard TS2, Section 2.1.6.
2. Comply with FCC, Title 47, SubPart B, Section 15 regulations for Class A emission limits for electronic noise.

LED signal module must provide a power factor of 0.90 or greater.

Total harmonic distortion from current and voltage induced into an alternating current power line by LED signal module must not exceed 20 percent at an operating temperature of 25 °C.

When power is applied to LED signal module, light emission must occur within 90 ms.

10-3.12 BATTERY BACKUP SYSTEM

GENERAL

Summary

This work includes installing battery backup system (BBS). Comply with Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and TEES.

The State will furnish BBS components as listed in "Materials" of these special provisions.

You must furnish the external cabinet and batteries.

Submittals

Before shipping external cabinets to the jobsite, submit material list including contract number, cabinet serial numbers, and contact information to the Transportation Laboratory.

Submit a Certificate of Compliance for each external cabinet and batteries to the Engineer under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Quality Control and Assurance

The State may test the cabinets.

Functional Testing

After complete installation, BBS functional test must be performed. Test for 30 minutes of continuous, satisfactory operation with utility power turned off. Perform test in the presence of the Engineer.

Warranty

Batteries must be warranted by the manufacturer to operate within a temperature range of -25 °C to +60 °C for 2 years.

Batteries must have a written warranty against defects in materials and workmanship from the manufacturer prorated for a period of 60 months after installation. You must provide the Engineer with all warranty documentation before installation. Replacement batteries must be available within 5 business days after receipt of failed batteries at no cost to the State except the cost of shipping the failed batteries. Replacement batteries must be delivered to Caltrans Maintenance Electrical Shop at 175 Cluster Street, San Bernardino.

MATERIALS

Batteries must:

1. Be deep cycle, sealed prismatic, lead-calcium-based, absorbed-glass mat and valve-regulated lead acid (AGM/VRLA) type
2. Have voltage rating of 12 V
3. Be group size 24
4. Be commercially available and stocked locally
5. Have a carrying handle
6. Be marked with date code, maximum recharge data, and recharge cycles
7. Have 2 top-mounted, threaded, stud posts that include all washers and nuts required for attaching 3/8-inch ring lugs of a State-furnished BBS battery harness
8. Include rubber insulating protective covers for protecting the lugs, posts, and wiring - red for positive terminal and black for negative terminal
9. Be new and fully-charged when furnished
10. Be free from damage or deformities

External cabinet must be one listed on the Pre-Qualified Products List at:

http://www.dot.ca.gov/hq/esc/approved_products_list/

External cabinet must be capable of housing:

1. 8 batteries
2. Inverter/charger unit
3. Power transfer relay
4. Manually-operated bypass switch
5. Required control panels
6. Wiring and harnesses

Dimensions and details for the external cabinet, for attaching the external cabinet to the Model 332A cabinet, and for wiring the State-furnished equipment will be available in an information handout as described in "Project Information" of these special provisions.

The following details must comply with Section 86-3.04, "Controller Cabinets," of the Standard Specifications and TEES:

1. Door construction, including material, thickness, coating, and welds

2. Frame
3. Door seals
4. Continuous stainless steel piano hinge or 4 leaves with 2 bolts on each side of each leaf, used to connect the door to external cabinet
5. Padlock clasp or latch and lock mechanism

The external cabinet must be ventilated by using louvered vents, filter, and a thermostatically controlled fan. Fan must be AC-operated from the same line output as the Model 332A cabinet. A 2-position terminal block must be provided on the fan panel, along with 10 feet of connected hookup wire.

The external cabinet surface must be anodized aluminum. Anti-graffiti paint must not be used.

The external cabinet must include all bolts, washers, nuts, and cabinet-to-cabinet coupler fittings necessary for mounting it to the Model 332A cabinet.

Fasteners for the external cabinet must include:

1. 8 cabinet mounting bolts that are 18-8 stainless steel hex head, fully-threaded, and 3/8" – 16 x 1"
2. 2 washers per bolt designed for 3/8-inch bolt and are 18-8 stainless steel 1-inch OD round flat type
3. K-lock nut per bolt: K-lock washer that is 18-8 stainless steel and hex-nut

External cabinet to Model 332A or 334 cabinet couplings must include a conduit for power connections between the 2 cabinets. Couplings must include:

1. 2-inch nylon-insulated steel chase nipple, T & B 1947 or equivalent
2. 2-inch sealing, steel locknut, T & B 146SL or equivalent
3. 2-inch nylon-insulated steel bushing, T & B 1227 or equivalent

CONSTRUCTION

Mount external cabinet to either the left or right side of Model 332A or 334 cabinet. The typical side-mounting location of external cabinet is flush with the bottom of the Model 332A or 334 cabinet and approximately equidistant from the front and rear door edges.

MEASUREMENT AND PAYMENT

Full compensation for assembling and installing battery backup system is included in the contract lump sum price paid for Signal and Lighting, and no separate payment will be made therefor.

10-3.13 LIGHT EMITTING DIODE PEDESTRIAN SIGNAL FACE MODULES

GENERAL

Summary

This work includes installing LED pedestrian signal face (PSF) module into standard Type A pedestrian signal housing. Comply with Section 86, "Electrical Systems," of the Standard Specifications.

Submittals

Before shipping LED PSF modules to job site, submit the following to the Transportation Laboratory:

1. Delivery form including district number, EA, and contact information
2. List containing all LED PSF module serial numbers anticipated for use
3. LED PSF modules

Quality Control and Assurance

Module must be one listed on the Pre-Qualified Products List for LED traffic signals at:

http://www.dot.ca.gov/hq/esc/approved_products_list

The State will test LED PSF module shipments as specified in ANSI/ASQ Z1.4.. Testing will be completed within 30 days of delivery to the Transportation Laboratory. LED PSF modules tested or submitted for testing must be representative of typical production units. LED PSF modules will be tested as specified in California Test 606. All parameters of the specification may be tested on the modules.

Delays resulting from submittal of non-compliant materials do not relieve you from executing the contract within the allotted time. Non-compliant materials will be rejected. You must resubmit new LED for retesting and pick up the failed units within 7 days of notification. You must provide new LED PSF modules and allow a minimum of 30 days for the retest. You must pay for all shipping and handling costs related to testing and retesting. Delays resulting from resubmittal and retesting are your responsibility and no extra time will be allowed.

After successful testing, you must pick up the tested LED PSF modules from the Transportation Laboratory and deliver to the job site.

Warranty

The manufacturer must provide a written warranty against defects in materials and workmanship for LED PSF modules for a minimum period of 48 months after installation of LED PSF modules. Replacement LED PSF modules must be provided within 15 days after receipt of failed LED PSF modules at your expense. The State pays for shipping the failed modules to you. All warranty documentation must be submitted to the Engineer before installation. Replacement LED PSF modules must be delivered to State Maintenance Electrical Shop at 175 Cluster Street, San Bernardino.

MATERIALS

LED PSF module must:

1. Be from the same manufacturer.
2. Be installed in standard Type A pedestrian signal housing, "UPRAISED HAND" and "WALKING PERSON." Do not include reflectors.
3. Use LED as the light source.
4. Be designed to mount behind or replace face plates of standard Type A housing as specified in ITE publication, Equipment and Material Standards, Chapter 3, "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."
5. Have a minimum power consumption of 10 W.
6. Use required color and be ultra bright type rated for 100,000 hours of continuous operation from -40 °C to +74 °C.
7. Be able to replace signal lamp optical units and pedestrian signal faces with both LED and incandescent light sources.
8. Fit into pedestrian signal section housings without modifications to the housing. The housing must comply with ITE publication, Equipment and Materials Standards, Chapter 3, "Pedestrian Traffic Control Signal Heads."
9. Be a single, self-contained device, not requiring on-site assembly for installation into standard Type A housing.
10. Have the following information permanently marked on the back of module:
 - 10.1. Manufacturer's name
 - 10.2. Trademark
 - 10.3. Model number
 - 10.4. Serial number
 - 10.5. Lot number
 - 10.6. Month and year of manufacture
 - 10.7. Required operating characteristics, as follows:
 - 10.7.1. Rated voltage
 - 10.7.2. Power consumption
 - 10.7.3. Volt-ampere (VA)
 - 10.7.4. Power factor
11. Have prominent and permanent vertical markings for accurate indexing and orientation within the signal housing if a specific mounting orientation is required. Markings must include an up arrow, or the word "UP" or "TOP." Marking must be a minimum of 1-inch diameter.

Circuit board and power supply must be contained inside the LED PSF modules. Circuit board must comply with Chapter 1, Section 6 of TEES published by the Department.

Individual LEDs must be wired so catastrophic loss or failure of 1 LED will not result in loss of more than 5 percent of the PSF module light output. Failure of an individual LED in a string must not result in the loss of entire string or other indication.

LEDs must be evenly distributed in each indication. Do not use outline forms.

No special tools for installation are allowed.

Installation of the LED PSF module into pedestrian signal face must require only removal of lenses, reflectors, lamps, and existing LED modules.

Power supply for LED PSF module must be integral to the module. Power supply for each symbol must be isolated to avoid turn-on conflict.

Assembly and manufacturing processes for LED PSF module must assure that all internal components are adequately supported to withstand mechanical shock and vibration from high winds and other sources.

Material used for LED PSF module must comply with ASTM D 3935.

Enclosures containing either the power supply or electronic components of LED PSF module, except lenses, must be made of UL94VO flame-retardant material.

Color of "UPRAISED HAND" symbol must be portland orange.

Color of "WALKING PERSON" symbol must be lunar white.

Each symbol must not be less than 10 inches high and 6.5 inches wide. Uniformity ratio of illuminated symbols must not exceed 4 to 1 between highest and lowest luminance areas. Symbols must comply with ITE publication, Equipment and Material Standards, Chapter 3, "Pedestrian Traffic Control Signal Indications," and the "California MUTCD."

LED PSF module must maintain an average luminance value over 48 months of continuous use in signal operation for a temperature range of -40 °C to +74 °C. In addition, LED PSF modules must meet or exceed the following luminance values upon initial testing at 25 °C.

Luminance Values

PSF module	Luminance
UPRAISED HAND	1,094 FL
WALKING PERSON	1,547 FL

Color output of LED PSF module must comply with chromaticity requirements in Section 5.3 of ITE publication, Equipment and Material Standards, Chapter 3, "Pedestrian Traffic Control Signal Indications."

Measured chromaticity coordinates of LED PSF module must comply with the following chromaticity requirements for 48 months when operating over a temperature range of -40 °C to +74 °C.

Chromaticity Standards (CIE Chart)

UPRAISED HAND (portland orange)	Not greater than 0.390, nor less than 0.331, nor less than 0.997-X
WALKING PERSON (lunar white)	X: not less than 0.280, nor greater than 0.320 Y: not less than 1.055*X - 0.0128, nor greater than 1.055*X + 0.0072

LED PSF module maximum power consumption must not exceed the following values:

Power Consumption Requirements

PSF module	Power Consumption @ 24°C	Power Consumption @ 74°C
UPRAISED HAND	10.0 W	12.0 W
WALKING PERSON	9.0 W	12.0 W

Wiring and terminal block must comply with Section 13.02 of ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads." The LED PSF module must be supplied with spade lugs and 3 secured, color-coded, 3-foot long, 600 V(ac), 20 AWG minimum stranded jacketed copper wires. Wires must comply with NEC, rated for service at +105 °C.

LED PSF module must operate:

1. At a frequency of 60 Hz \pm 3 Hz over a voltage range from 95 V(ac) to 135 V(ac) without perceptible flicker to the unaided eye. Fluctuations of line voltage must have no visible effect on luminous intensity of the indications. Rated voltage for measurements must be 120 V(ac).
2. Compatible with currently used State controller assemblies including solid state lead switches, flashers, and conflict monitors. Comply with TEES Chapters 3 and 6. If a 20 ma alternating current or less is applied to the unit, the voltage read across the 2 leads must be 15 V(ac) or less.

LED PSF module on-board circuitry must:

1. Include voltage surge protection to withstand high-repetition noise transients. The voltage surge protection must comply with NEMA Standard TS2, Section 2.1.6.
2. Comply with FCC, Title 47, SubPart B, Section 15 regulations for Class A emission limits for electronic noise.

LED PSF module must provide a power factor of 0.90 or greater.

Total harmonic distortion from current and voltage induced into an alternating current power line by LED PSF module must not exceed 20 percent at an operating temperature of 25 °C.

The LED PSF module circuitry must prevent perceptible light emission to the unaided eye when a voltage, 50 V(ac) or less is applied to the unit.

When power is applied to LED PSF module, light emission must occur within 90 ms.

The "UPRAISED HAND" and "WALKING PERSON" symbol indications must be electrically isolated from each other. Sharing a power supply or interconnect circuitry between the 2 indications is not allowed.

10-3.14 DETECTORS

Loop detector sensor units will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

Loop wire shall be Type 2.

Loop detector lead-in cable shall be Type C.

For Type E detector loops, sides of the slot shall be vertical and the minimum radius of the slot entering and leaving the circular part of the loop shall be 1-1/2 inches. Slot width shall be a maximum of 5/8 inch. Loop wire for circular loops shall be Type 2. Slots of circular loops shall be filled with hot melt rubberized asphalt sealant.

The depth of loop sealant above the top of the uppermost loop wire in the sawed slots shall be 2 inches, minimum.

10-3.15 EMERGENCY VEHICLE DETECTOR SYSTEM

Each traffic signal shall have an emergency vehicle detector system which shall conform to the details shown on the plans and these special provisions.

GENERAL

Each emergency vehicle detector system shall consist of an optical emitter assembly or assemblies located on the appropriate vehicle and an optical detector/discriminator assembly or assemblies located at the traffic signal.

Emitter assemblies are not required for this project except units for testing purposes to demonstrate that the systems perform as specified. Tests shall be conducted in the presence of the Engineer as described below under "System Operation" during the signal test period. The Engineer shall be given a minimum of 2 working days notice prior to performing the tests.

Each system shall permit detection of 2 classes of authorized vehicles. Class I (mass transit) vehicles shall be detected at ranges of up to 1,000 feet from the optical detector. Class II (emergency) vehicles shall be detected at ranges up to 1,800 feet from the optical detector.

Class I signals (those emitted by Class I vehicles) shall be distinguished from Class II signals (those emitted by Class II vehicles) on the basis of the modulation frequency of the light from the respective emitter. The modulation frequency for Class I signal emitters shall be 9.639 Hz \pm 0.110 Hz. The modulation frequency for Class II signal emitters shall be 14.035 Hz \pm 0.250 Hz.

A system shall establish a priority of Class II vehicle signals over Class I vehicle signals and shall conform to the requirements in Section 25352 of the California Vehicle Code.

EMITTER ASSEMBLY

Each emitter assembly, provided for testing purposes, shall consist of an emitter unit, an emitter control unit, and connecting cables.

General

Each emitter assembly, including lamp, shall operate over an ambient temperature range of -34°C to $+60^{\circ}\text{C}$ at both modulation frequencies and operate continuously at the higher frequency for a minimum of 3,000 hours at 25°C ambient before failure of the lamp or other components.

Each emitter unit shall be controlled by a single, maintained-contact switch on the respective emitter control unit. The switch shall be located to be readily accessible to the vehicle driver. The control unit shall contain a pilot light to indicate that the emitter power circuit is energized and shall generate only one modulating code, either that for Class I vehicles or that for Class II vehicles.

Functional

Each emitter unit shall transmit optical energy in one direction only.

The signal from each Class I signal emitter unit shall be detectable at a distance of 1,000 feet when used with a standard optical detection/discriminator assembly and filter to eliminate visible light. Visible light shall be considered eliminated when the output of the emitter unit with the filter is less than an average of 0.0003-candela per energy pulse in the wavelength range of 380 nm to 750 nm when measured at a distance of 10 feet. A Certificate of Compliance, conforming to the requirements in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be submitted to the Engineer with each Class I emitter unit.

The signal from each Class II signal emitter unit shall be detectable at a distance of 1,800 feet when used with a standard optical detection/discriminator assembly.

The standard optical detection/discriminator assembly to be used in making the range tests shall be available from the manufacturer of the system. A certified performance report shall be furnished with each assembly.

Electrical

Each emitter assembly shall provide full light output with input voltages of between 12.5 V (dc) and 17.5 V (dc). An emitter assembly shall not be damaged by input voltages up to 7.5 V (dc) above supply voltage. The emitter assembly shall not generate voltage transients, on the input supply, which exceed the supply voltage by more than 4 volts.

Each emitter assembly shall consume not more than 100 W at 17.5 V (dc) and shall have a power input circuit breaker rated at 10 A to 12 A, 12 V (dc).

The design and circuitry of each emitter shall permit its use on vehicles with either negative or positive ground without disassembling or rewiring of the unit.

Mechanical

Each emitter unit shall be housed in a weatherproof corrosion-resistant housing. The housing shall be provided with facilities to permit mounting on various types of vehicles and shall have provision for aligning the emitter unit properly and for locking the emitter unit into this alignment.

Each emitter control unit shall be provided with hardware to permit the unit to be mounted in or on an emergency vehicle or mass transit vehicle. Where required for certain emergency vehicles, the emitter control unit and exposed controls shall be weatherproof.

OPTICAL DETECTION/DISCRIMINATOR ASSEMBLY

General

Each optical detection/discriminator assembly shall consist of one or more optical detectors, connecting cable and a discriminator module.

Each assembly, when used with standard emitters, shall have a range of at least 1,000 feet for Class I signals and 1,800 feet for Class II signals. Standard emitters for both classes of signals shall be available from the manufacturer of the system. Range measurements shall be taken with all range adjustments on the discriminator module set to "maximum".

Optical Detector

Each optical detector shall be a waterproof unit capable of receiving optical energy from two separately aimable directions. The horizontal angle between the 2 directions shall be variable from 180 degrees to 5 degrees.

The reception angle for each photocell assembly shall be a maximum of 8 degrees in all directions about the aiming axis of the assembly. Measurements of reception angle will be taken at a range of 1,000 feet for a Type I emitter and at a range of 1,800 feet for a Type II emitter.

Internal circuitry shall be solid state and electrical power shall be provided by the associated discriminator module.

Each optical detector shall be contained in a housing, which shall include 2 rotatable photocell assemblies, an electronic assembly and a base. The base shall have an opening to permit mounting on a mast arm or a vertical pipe nipple, or suspension from a span wire. The mounting opening shall have female threads for 3/4 inch conduit. A cable entrance shall be provided which shall have male threads and gasketing to permit a waterproof cable connection. Each detector shall have weight of less than 2.5 pounds and shall present a maximum wind load area of 36 square inches. The housing shall be provided with weep holes to permit drainage of condensed moisture.

Each optical detector shall be installed, wired and aimed as specified by the manufacturer.

Cable

Optical detector cable (EV-C) shall meet the requirements of IPCEA-S-61-402/NEMA WC 5, Section 7.4, 600-V (ac) control cable, 75°C, Type B, and the following:

- A. The cable shall contain 3 conductors, each of which shall be No. 20 (7 x 28) stranded, tinned copper with low-density polyethylene insulation. Minimum average insulation thickness shall be 25 mils. Insulation of individual conductors shall be color coded: 1-yellow, 1-blue, 1-orange.
- B. The shield shall be either tinned copper braid or aluminized polyester film with a nominal 20 percent overlap. Where film is used, a No. 20 (7 x 28) stranded, tinned, bare drain

wire shall be placed between the insulated conductors and the shield and in contact with the conductive surface of the shield.

- C. The jacket shall be black polyvinyl chloride with minimum ratings of 600 V (ac) and 80°C and a minimum average thickness of 43 mils. The jacket shall be marked as required by IPCEA/NEMA.
- D. The finished outside diameter of the cable shall not exceed 0.35-inch.
- E. The capacitance, as measured between any conductor and the other conductors and the shield, shall not exceed 48 pf per foot at 1000 Hz.
- F. The cable run between each detector and the controller cabinet shall be continuous without splices or shall be spliced only as directed by the detector manufacturer.

Discriminator Module

Each discriminator module shall be designed to be compatible and usable with a Model 170 controller unit and to be mounted in the input file of a Model 332 or Model 336 controller cabinet, and shall conform to the requirements of Chapter I of the State of California, Department of Transportation, "Traffic Signal Control Equipment Specifications."

Each discriminator module shall be capable of operating 2 channels, each of which shall provide an independent output for each separate input.

Each discriminator module, when used with its associated detectors, shall perform the following:

- A. Receive Class I signals at a range of up to 1,000 feet and Class II signals at a range of up to 1,800 feet.
- B. Decode the signals, on the basis of frequency, at $9.639 \text{ Hz} \pm 0.119 \text{ Hz}$ for Class I signals and $14.035 \text{ Hz} \pm 0.255 \text{ Hz}$ for Class II signals.
- C. Establish the validity of received signals on the basis of frequency and length of time received. A signal shall be considered valid only when received for more than 0.50-second. No combination of Class I signals shall be recognized as a Class II signal regardless of the number of signals being received, up to a maximum of 10 signals. Once a valid signal has been recognized, the effect shall be held by the module in the event of temporary loss of the signal for a period adjustable from 4.5 seconds to 11 seconds in at least 2 steps at $5 \text{ seconds} \pm 0.5 \text{ second}$ and $10 \text{ seconds} \pm 0.5 \text{ second}$.
- D. Provide an output for each channel that will result in a "low" or grounded condition of the appropriate input of a Model 170 controller unit. For Class I signals the output shall be a $6.25 \text{ Hz} \pm 0.1 \text{ percent}$, rectangular waveform with a 50 percent duty cycle. For Class II signals the output shall be steady.

Each discriminator module shall receive electric power from the controller cabinet at either 24 V (dc) or 120 V (ac).

Each channel together with the channel's associated detectors shall draw not more than 100 mA at 24 V (dc) or more than 100 mA at 120 V (ac). Electric power, one detector input for each channel and one output for each channel shall terminate at the printed circuit board edge connector pins listed below:

BOARD EDGE CONNECTOR PIN ASSIGNMENT

A	DC ground		
B	+24 V (dc)	P	(NC)
C	(NC)		
D	Detector input, Channel A	R	(NC)
E	+24V (dc) to detectors	S	(NC)
F	Channel A output (C)	T	(NC)
		U	(NC)
H	Channel A output (E)	V	(NC)
J	Detector input, Channel B	W	Channel B Output (C)
K	DC Ground to detectors	X	Channel B Output (E)
L	Chassis ground	Y	(NC)
M	AC-	Z	(NC)
N	AC+		

(C) Collector, Slotted for Keying

(E) Emitter, Slotted for Keying

(NC) Not connected, cannot be used by manufacturer for any purpose.

Two auxiliary inputs for each channel shall enter each module through the front panel connector. Pin assignment for the connector shall be as follows:

- A. Auxiliary detector 1 input, Channel A
- B. Auxiliary detector 2 input, Channel A
- C. Auxiliary detector 1 input, Channel B
- D. Auxiliary detector 2 input, Channel B

Each channel output shall be an optically isolated NPN open collector transistor capable of sinking 50 mA at 30 V (ac) and shall be compatible with the Model 170 controller unit inputs.

Each discriminator module shall be provided with means of preventing transients received by the detector from affecting the Model 170 controller assembly.

Each discriminator module shall have a single connector board and shall occupy one slot width of the input file. The front panel of each module shall have a handle to facilitate withdrawal and the following controls and indicators for each channel:

- A. Three separate range adjustments each for both Class I and Class II signals.
- B. A 3-position, center-off, momentary contact switch, one position (down) labeled for test operation of Class I signals, and one position (up) labeled for test operation of Class II signals.
- C. A "signal" indication and a "call" indication each for Class I and for Class II signals. The "signal" indication denotes that a signal above the threshold level has been received. A "call" indication denotes that a steady, validly coded signal has been received. These 2 indications may be accomplished with a single indication lamp; "signal" being denoted by a flashing indication and "call" with a steady indication.

In addition, the front panel shall be provided with a single circular, bayonet-captured, multi-pin connector for 2 auxiliary detector inputs for each channel. Connector shall be a mechanical configuration conforming to the requirements in Military Specification MIL-C-26482 with 10-4 insert arrangement, such as Burndy Trim Trio Bantamate Series, consisting of the following:

- A. Wall mounting receptacle, G0B10-4PNE with SM20M-1S6 gold plated pins.
- B. Plug, G6L10-4SNE with SC20M-1S6 gold plated sockets, cable clamp and strain relief that shall provide for a right angle turn within 2-1/2 inches maximum from the front panel surface of the discriminator module.

Cabinet Wiring

The Model 332 cabinet has provisions for connections between the optical detectors, the discriminator module and the Model 170 controller unit.

Wiring for a Model 332 cabinet shall conform to the following:

- A. Slots 12 and 13 of input file "J" have each been wired to accept a 2-channel module.
- B. Field wiring for the primary detectors, except 24-V (dc) power, shall terminate on either terminal board TB-9 in the controller cabinet or on the rear of input file "J," depending on cabinet configuration. Where TB-9 is used, position assignments shall be as follows:

Position	Assignment
4	Channel A detector input, 1st module (Slot J-12)
5	Channel B detector input, 1st module (Slot J-12)
7	Channel A detector input, 2nd module (Slot J-13)
8	Channel B detector input, 2nd module (Slot J-13)

The 24-V (dc) cabinet power will be available at Position 1 of terminal board TB-1 in the controller cabinet.

Field wiring for the auxiliary detectors shall terminate on terminal board TB-O in the controller cabinet. Position assignments are as follows:

FOR MODULE 1 (J-12)		FOR MODULE 2 (J-13)	
Position	Assignment	Position	Assignment
1	+24V (dc) from (J-12E)	7	+24V (dc) from (J-13E)
2	Detector ground From (J-12K)	8	Detector ground from (J-13K)
3	Channel A auxiliary detector input 1	9	Channel A auxiliary detector input 1
4	Channel A auxiliary detector input 2	10	Channel A auxiliary detector input 2
5	Channel B auxiliary detector input 1	11	Channel B auxiliary detector input 1
6	Channel B auxiliary detector input 2	12	Channel B auxiliary detector input 2

SYSTEM OPERATION

The Contractor shall demonstrate that the components of each system are compatible and will perform satisfactorily as a system. Satisfactory performance shall be determined using the following test procedure during the functional test period:

- A. Each system to be used for testing shall consist of an optical emitter assembly, an optical detector, an optical detector cable and a discriminator module.
- B. The discriminator modules shall be installed in the proper input file slot of the Model 170 controller assembly.
- C. Two tests shall be conducted; one using a Class I signal emitter and a distance of 1,000 feet between the emitter and the detector, the other using a Class II signal emitter

and a distance of 1,800 feet between the emitter and the detector. Range adjustments on the module shall be set to "Maximum" for each test.

- D. Each test shall be conducted for a period of one hour, during which the emitter shall be operated for 30 cycles, each consisting of a one minute "on" interval and a one minute "off" interval. During the total test period the emitter signal shall cause the proper response from the Model 170 controller unit during each "on" interval and there shall be no improper operation of either the Model 170 controller unit or the monitor during each "off" interval.

10-3.16 LUMINAIRES

Ballasts shall be the lag regulator type.

10-3.17 INTERNALLY ILLUMINATED SIGNS

The "METER ON" sign shall be a Type A pedestrian signal modified so that the reflector shall be a single chamber with 2 incandescent lamps.

The message shall be white "METER ON" as shown on the plans. White color shall be in conformance with the provisions in Section 86-4.06, "Pedestrian Signal Faces," of the Standard Specifications.

Lenses shall be 3/16 inch, minimum thickness, clear acrylic or polycarbonate plastic or 1/8 inch nominal thickness glass fiber reinforced plastic, with molded, one-piece, neoprene gasket. Message lettering for "METER" shall be "Series C," 4-1/2 inches high, with uniform 1/2 inch stroke, and for "ON" shall be "Series C," 6 inches high, with uniform one inch stroke. Letters shall be clear, transparent or translucent, with black opaque background silk screened on to the second surface of the lens.

10-3.18 PHOTOELECTRIC CONTROLS

Contactors shall be the mechanical armature type.

Photoelectric units for illuminated signs shall have a "turn-on" level of between 20 foot-candles and 30 foot-candles (corresponds to a switching level of approximately 40 foot-candles to 60 foot-candles measured in the horizontal plane). "Turn-off" level shall not exceed 3 times the "turn-on" level.

Luminaires shall have Type V photoelectric control.

10-3.19 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT

Salvaged electrical materials shall be hauled to the State of California, Department of Transportation maintenance yard located at 175 Cluster Street, San Bernardino and stockpiled.

The Contractor shall provide the equipment, as necessary, to safely unload and stockpile the material. A minimum notice of 2 business days shall be given prior to delivery.

10-3.20 DISPOSING OF ELECTRICAL EQUIPMENT

Fluorescent light ballasts which contain polychlorinated biphenyls (PCBs) shall be disposed of in conformance with the California Department of Toxic Substances Control (DTSC) Regulations set forth in Title 22, Division 4.5, Chapter 42, of the California Code of Regulations.

Ballasts and transformers that contain polychlorinated biphenyl (PCB) are designated as extremely hazardous wastes and fluorescent tubing and mercury lamps are designated as hazardous wastes under Title 22, Division 4.5, Chapter 11, Article 4.1 and Article 5, of the California Code of Regulations.

The State assumes generator responsibility for these wastes. The Engineer will prepare the Hazardous Waste Manifest for Shipment. Ballasts shall be packaged and transported to a hazardous waste disposal facility. The Contractor shall package and transport fluorescent lights to an appropriately permitted facility.

PAYMENT

Full compensation for hauling, stockpiling, and disposing of transformers, fluorescent tubing and mercury lamps and non-leaking fluorescent light ballasts shall be considered as included in the contract price paid for the various items of work and no additional compensation will be allowed therefor.

10-3.21 WIRELESS CELLULAR DATA COMMUNICATIONS ASSEMBLY

GENERAL

The wireless cellular data communications assembly shall consist of the Code Division Multiple Access (CDMA) modem, an external antenna, antenna cable, power supply/adaptor for modem, interface cable between modem and 170 Controller, and modem mounting bracket. The wireless cellular data communications assembly shall provide wireless data transmission between the signal controller in the field and the Transportation Management Center (TMC).

CDMA Modem

The modem shall be product certified by the cellular provider.

RF Specifications:

224 mW RF output (+23.5dBm)

Full duplex transceiver

Dual band support for both 800 MHz and 1.9 GHz bands

Adheres to CDMA authentication as specified in CDMA2000

Antenna

The antenna shall be a dipole EVDO type, which will screw into the CDMA modem with an SMA type connector.

Packet Mode Features:

The modem shall support data rates up to 150 kbs and 75 kbps.

DC Power Specifications:

Advanced Power Management features

Low power consumption

Input Voltage: 10 VDC to 28 VDC

Input Current: 40 mA to 200 mA

Typical Receive: 200 mA at 12 VDC

Typical Transmit: Approximately 200 mA at 12 VDC

Dormant connection (idle for 10-20 seconds): 40 mA at 12 VDC

The above power requirements shall be provided by an AC adapter or other approved devices.

Environmental:

Operating ranges: -30°C to +70°C (10% duty cycle limit above 60°C)

Humidity: 5%-95% Non-condensing

Physical Characteristics:

Weight: Shall be less than 0.17 ounces

Size: Not greater than 3 inches wide x-1 inch high x-5 inches long

Status LEDs: Shall provide as a minimum indications for power, Received

Signal Strength Indication (RSSI), and data transmission error

RF Antenna Connector: 50 Ohm Terminal Node Controller (TNC)

Serial Interface: RS232 DB-9F

Modem Mounting Bracket: Shall attach and secure the modem in the proximity of the 170/2070 Controller C2 port within the 332 Controller Cabinet

Interface Connection with 170 Controller:

Interface cable shall conform with C2P modem interconnect harness, "Model 170 Connectors", TSCES-2, of Traffic Control Equipment Specifications, January 1999, except that cable ends shall be C2P connector to the Model 170/2070 Controller and DB9 male connector to the external modem, with the following pin configurations as follow:

DB9M (to external modem)**C2P (to Model 170/2070 controller)**

Function	Pin	Pin	Function
Transmit Data	3	K	Data In
Receive Data	2	L	Data Out
Signal Ground	5	N	Ground
Request to Send	7	J	Request to Send
Clear to Send	8	M	Clear to Send
Data Terminal Ready	1	H	Clear Detect

Application Interfaces:

TCP/IP, UDP/IP, DHCP, HTTP, SNMP, SMTP, SMS, MSCI and Modbus

The contractor shall perform a loop test at the installation site by transmitting via a cellular device requesting data from the 170 Controller and monitoring the resulting return data under supervision of the District Electrical Operations Engineer.

Acceptance Testing

At the time of the signal turn on, the wireless cellular data communication system will be tested by State forces to perform a loop test at the installation site by transmitting via a cellular device requesting data from the 170 Controller and monitoring the resulting return data. The test will be for a period of not less than 5 days of continuous, satisfactory operation.

WARRANTY

The Contractor shall provide a written warranty from the manufacturer against defects in materials and workmanship for wireless cellular data communication assembly for a period of 12 months after the acceptance test has been completed. Replacement of the wireless cellular data communication assembly shall be provided within 5 days after receipt of failed wireless cellular data communication assembly at no cost to the State, except the cost of shipping the failed parts. All warranty documentation shall be given to the Engineer at the time of delivering. Replacement parts of the wireless cellular data communication assembly shall be delivered to Caltrans Maintenance Electrical Shop at 175 Cluster Street, San Bernardino.

PAYMENT

Full compensation for wireless cellular data communication assembly shall be considered as included in the contract lump sum price for the system being installed and no separate payment will be made therefore.

10-3.22 COMMUNICATION SYSTEM

GENERAL

Communication system includes furnishing and installing the following equipment and performing testing as per the plans, these Special Provisions and Section 86 "Signals, Lighting and Electrical Systems" of the Standard Specifications:

DESCRIPTION
GPRS Modem Assembly
Network to Serial Adapter Card
Cat 5E Cable
LAN Extender
Ethernet Switch

10-3.23 GENERAL PACKET RADIO SYSTEM MODEM

SUMMARY

The General Packet Radio Service (GPRS) assembly shall consist of a GPRS modem, GPRS antenna and antenna cable. The equipment shall be furnished and installed as shown in the plans. The Contractor shall secure all components and cables to the rack or cabinet as necessary. The installed wireless cellular data communication assembly shall be compatible with the

existing AT&T GPRS/EDGE (Enhanced Data rates for Global system for mobile communications Evolution) system currently being used. The Contractor shall provide software, cabling and GPRS modem for connection to the existing wireless telecommunications provider's GPRS system. The Contractor shall be responsible for compatibility and demonstrating compatibility.

FUNCTIONAL REQUIREMENTS

The GPRS modem shall be capable of connecting to a general packet radio system wireless data network. The modem shall be capable of providing high-speed connectivity, as well as backup network connectivity, including physical Serial and Ethernet connectivity for transmitting and receiving data from field controllers to the District 8 Transportation Management Center.

The Contractor shall provide SMA-M / TNC-F adaptor for SMA-F modem and TNC-M antenna connection.

The Contractor shall provide necessary power supplies, mounting hardware and wiring. The GPRS modem shall meet or exceed the following requirements:

Description	Specifications
Network	Quad band 1900/850 MHz and 1800/900 MHz GSM HSDPA/UMTS
Transmit Frequency	From 1850 to 1910 MHz and from 824 to 849 MHz
Transmit Power Range At Antenna Port	1.0 W for 1900 MHz and 0.8 W for 850 MHz
Throughput	Up to 240 kbps, from 100 to 130 kbps typical
Receiver Frequency	From 1930 to 1990 MHz and from 869 to 894 MHz
Receiver Sensitivity	Typical -107 dBm
Network Protocols	UDP/TCP, DHCP,
Features	NAT, Port forwarding (minimum of 15 ports), VPN pass-through, DES, 3DES and up to 256-bit AES Encryption, IPsec with IKE/ISAKMP, Multiple tunnel support, SCEP for X.509 certificates, IP filtering, HTTP, Web management
Security	SSL, SSH v2, FIPS 197
Ethernet Interface	IEEE 802.3, 10/100Base-T, RJ-45 switch port, 10/100 Mbps (auto-sensing), Full or half duplex (auto-sensing)
Serial Interface	1 EIA-232 DB-9 F port, Up to 230 kbps, hardware and software flow control, full signal support for TX, RX, RTS, CTS, DTR, DSR and DCD, hardware and software flow control
RF Antenna Connector	50 Ω TNC Male
Regulatory Approvals / Certifications	UL 60950, CE, CSA 22.2 No. 60950, EN60950, FCC Part 15, Class A, AS/NZS CISPR 22, EN55024, EN55022, Class A, PTCRB, NAPRD.03, GCF-CC, R&TTE, EN 301 511, GSM GPRS/EDGE, HSDPA/UMTS
LED Indicators	Ethernet, power on, RSSI, link/activity
Input Voltage	From 9 V(dc) to 30 V(dc)
Input Current	From 40 mA to 200 mA
Operating Temperature	From -22°F to +140°F
Max Weight	2.0 lbs
Max Size	5.0" (W) x 1.50"(H) x 8.0"(L)

ACTIVATION

The Contractor shall send all necessary activation information from the manufacturer to the Engineer in an electronic text format. With the information provided, the State will activate the modems after installation.

GPRS ANTENNA AND ANTENNA CABLE

The antenna shall be a fixed mount design and use a waterproof acrylic foam adhesive to attach to the outside surface of the controller cabinet. The adhesive should be resistant to Jet Propellant Grade 4 (JP-4), acetone, methyl ethyl ketone, motor oil and gasoline. The antenna shall be equipped with a separate coaxial cable with appropriate connectors at each end. The antenna and the GPRS modem shall be connected using the cable.

The antenna shall be compatible with the modem and the existing AT & T GPRS/EDGE system. The antenna shall not be more than 1 1/8-inches high and 4 3/8-inches in diameter and it shall operate in dual bands with frequency ranges from 824 MHz to 896 MHz and from 1850 MHz to 1915 MHz.

Voltage Standing Wave Ratio (VSWR) at resonant point	1.5:1 or less
Nominal Impedance	50 Ω
Gain	3 dB
Horizontal Radiation Pattern	Omni Directional
Polarization	Vertical
Maximum Power Input	125 W

WARRANTY

The GPRS modem assembly shall have a 2-year warranty by the manufacturer. The warranty shall include hardware parts needed for repair. The Contractor shall provide the Engineer with warranty documentation and the appropriate manufacturer contact information. The warranty period shall begin upon Contract Acceptance.

DELIVERY

The Contractor shall deliver the GPRS modem to the Engineer 10-days before the Contractor is scheduled to pick up the State-Furnished Model 334 cabinet.

TESTING

Proper operation of the GPRS modem shall be demonstrated by successfully performing a loop back test at the installation site by the Contractor. The loop back test shall involve transmitting data from the Model 170 controller to the TMC computer and monitoring the resulting return data. For success, the test shall transmit 5 minutes continuously, every hour, for one full day. The Contractor shall be responsible for developing the test procedures with documentation that include required equipment, prior to testing. The Engineer will approve the test procedures and documentation before the Contractor performs the testing. The testing shall be observed by the Engineer and the final recorded results approved by the Engineer.

10-3.24 NETWORK TO SERIAL ADAPTER CARD

The Contractor shall configure and test all cards prior to acceptance. The Engineer will provide the IP addresses to the Contractor.

Minimum Specifications

Hardware

1. Designed for Model 170 controller equipment
2. Model 400 modem card compatible form factor

Software

1. Universal IP address assignment (Static IP, DHCP, Auto-IP)
2. Secure web user interface (HTTP/HTTPS) with context sensitive
3. Telnet command line interface
4. Modem emulation and port logging
5. TCP/UDP forwarding characteristics: bytes, idle time, data pattern
6. User-configurable TCP/UDP Socket ID

Ethernet Interface

1. Connector: RJ-45
2. Physical layer: 10/100Base-T
3. Data rate: 10/100 Mbps (auto-sensing)
4. Mode: Full or half duplex (auto-sensing)
5. Status LED's (Ethernet):
 - 5.1. Network Link Status
 - 5.2. Network Activity
 - 5.3. Serial
 - 5.4. Data Out (TXD)
 - 5.5. Data In (RXD)
 - 5.6. Data Carrier Detect (DCD)
 - 5.7. Ready to Send (RTS)

Power Requirements

1. 3.3 V(dc) at 250 mA typical

Environmental

1. Storage temperature: From -50 to 125 °C
2. Operating temperature: From -40 to 85 °C
3. Relative humidity: From 5 to 90 percent (non-condensing)
4. Altitude: Up to 12,000 feet

Regulatory Approvals

1. UL (Underwriter's Laboratory)
2. UR (Underwriter's Registered)

Certificate of Compliance

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in accordance with NEMA TS1/2 Environmental Requirements for Traffic Control Equipment.

Warranty

Provide a written warranty against defects in materials and workmanship for a minimum period of 36 months after installation of network to serial adapter card. All warranty documentation must be submitted to the Engineer before installation.

10-3.25 CATEGORY 5E CABLE

Category 5E cable shall be the unshielded, non-gel filled type, and shall meet the requirements of TIA/EIA 568B.2, Category 5E Cable, and the following:

The cable shall contain 8 conductors, each of which shall be No. 24, minimum, solid bare copper conductors. Each conductor shall be insulated with polyolefin, polyethylene, polyvinyl chloride or fluorinated ethylene propylene material. Conductors shall be in twisted pairs. Color coding shall distinguish each pair: blue, blue/white; brown, brown/white; green, green/white; orange, orange/white.

The cable jacket shall be rated for a minimum of 300 V and 60°C and shall be polyvinyl chloride, polyethylene, polyolefin or fluorinated ethylene propylene. The jacket shall be black, gray, or blue. The jacket shall be marked as required by NEMA. The jacket shall be marked at not more than every three foot interval with the cable identification: manufacturer's name, product identification, number of conductors and conductor size, and voltage and temperature ratings. Cable length markings may be sequentially alternated with the cable identification markings at not more than every three foot interval.

The finished outside diameter of the cable shall not exceed 1/2".

Installation

The cable run between components shall be continuous without splices. A minimum of three feet of slack shall be provided at each pull box, junction box or vault, and a minimum of 10 feet at each cabinet. The ends of the category 5E cable shall be terminated with appropriate RJ-type connectors as necessary to connect the equipment shown on the plans, or shall be terminated with crimped and soldered spade type terminals at terminal blocks.

10-3.26 LAN EXTENDER

The Contractor shall configure and test the LAN extender prior to acceptance. The Engineer will provide the IP addresses to the Contractor. All LAN extenders shall be the rack mounted type, complete with all cables, conductors, hardware, and other equipment as required making the system completely operational. Location and mounting of the equipment shall be as shown on the plans or as directed by the Engineer and in compliance with the manufacturer's installation requirements.

Interface

1. Ethernet Port:

- 1.1. Port: One RJ-45 port, 10/100BASE-TX Full/Half-duplex.
- 1.2. Auto-Negotiation, Auto-MDI/MDIX.
- 1.3. Speed: 10/100Mbps.
- 1.4. Distance: Not less than 328ft.
- 1.5. Cable: 10BASE-T: UTP CAT. 3, 4, 5 (2-pair wire).
- 1.6. 100BASE-TX: UTP CAT. 5 (2-pair wire).

2. Ethernet Extender Port:

- 2.1. Port: One RJ-11 and Terminal Block port.
- 2.2. Speed: 1/3/5/10/15/20/25/30/40/50 Mbps.
- 2.3. Distance: Not less than 6,232 ft.
- 2.4. Cable: Telephone line 24 AWG (0.5 mm diameter, 1-pair wire) or larger.

Protocols Supported

Shall support higher layer protocols.

Operating Power

The LAN extender shall have redundant power supply connections and shall be designed to the following power requirements:

1. Input voltage: 120 V(ac)
2. Low power consumption.
3. With overload current and reverse polarity protection.

Status Indicators

The LAN extender shall provide the listed status indicating LED's for monitoring proper system operation as followed:

1. Power (on).
2. Link/Speed.

Environmental Requirements

The LAN extender shall be environmentally hardened and shall be designed to operate in the following environmental conditions:

1. From -40 to +85 °C (-40 to +167 °F) operating temperature range.
2. From -40 to +85 °C (-40 to +185 °F) storing temperature range.
3. From 5 to 95 percent relative humidity, non-condensing.

Compatibility Requirements

The LAN extender and associated firmware, software, hardware, protocol, and other features shall be fully and completely compatible with the existing Ethernet switch currently in use.

The Contractor shall demonstrate the compatibility to the Engineer by actual installation demonstration or by other means approved by the Engineer.

Installation

The installation of the LAN extender shall be according to the plans, the manufacturer's instructions, and adjusted per field conditions with the Engineers approval.

The LAN extender shall be installed in the Model 334 controller cabinet. The placement of the LAN extender shall allow provision for cable installation and maintenance.

Certificate of Compliance

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in accordance with NEMA TS-1/TS-2 Environmental Requirements for Traffic Control Equipment.

Warranty

Provide a written warranty against defects in materials and workmanship for a minimum period of 36 months after installation of LAN extender. All warranty documentation must be submitted to the Engineer before installation.

10-3.27 ETHERNET SWITCH

The Ethernet Switch (ES) shall provide a minimum of four ports, 10/100BaseTX, for connection of the various equipment as shown on the plans.

Each Ethernet switch shall be functionally tested for fifteen minutes and shall be error free without any loss of data.

Prototype equipment will not be acceptable. Only equipment previously marketed and sold for at least six months prior to the advertising date will be acceptable.

All manuals, software and warranty forms shall be submitted with the ES for acceptance.

All ES equipment shall be warranted against defects and any failure that may occur through normal use for a minimum of five years from the date of contract acceptance.

The Contractor shall furnish, install, configure and test the ES as shown on the project plans.

The ES shall meet or exceed the following requirements:

Parameter	Specification
Standards Compliance	IEEE 802.3, IEEE 802.3u, IEEE 802.3x
Protocol	CSMA/CD
Switch Architecture	Store and Forward
Transfer Rate	14,880 pps for Ethernet Port 148,800 pps for Fast Ethernet Port
Port Attributes	Auto-MDI/MDI-X Crossover Detection Up to 200 Mbps full duplex bandwidth at each port Address Learning and Aging, and Data Flow Control for enhanced transmission reliability
Memory Buffer	512 kb
LED	Unit: Master, Power, Power 1, Power 2 Port: Link/Activity, Full-Duplex/Collision
Network Cable	100BaseTX:2-pair UTP/STP Cat. 5 cable EIA/TIA-568 100 ohm(100 m)
Back Plane	1.0 Gbps
Packet Throughput Ability	0.74 Mpps at 64 bytes (5TX)
Power Supply	Input Voltage: 120 V(ac)
Power Consumption	3 W Max
Mechanical	Casting: IP30 Metal Case Nominal Dimensions: 2.3" (W) x 5.5" (H) x 4.5" (D) Installation: DIN-Rail/Wall Mountable
Operation Temperature	From -40 to 85 °C Min range
Operation Humidity	From 5 to 95 percent, non-condensing
Storage Temperature	From -40 to 85 °C
EMI	FCC Class A CE EN6100-4-2/EN6100-4-3/EN6100-4-4/EN6100-4-5/EN6100-4-6
Stability Testing	Shock: IEC60068-2-27 Free Fall: IEC60068-2-32 Vibration: IEC60068-2-6

Warranty

Provide a written warranty against defects in materials and workmanship for a minimum period of 36 months after installation of Ethernet switch. All warranty documentation must be submitted to the Engineer before installation.

10-3.28 SYSTEM TESTING AND DOCUMENTATION

GENERAL

This work includes performing system testing and furnishing documentation as per the plans, the Standard Specifications, these special provisions and as directed by the Engineer. The system testing shall consist of performing the following tests, validate the operational performance of systems and furnish documentation:

1. Description of Work
2. Physical Inspection
3. Acceptance Testing
4. Field Element Connectivity Testing
5. Final Acceptance

The system testing and documentation shall cover connectivity testing for field elements, pre-installation testing, physical inspection, system testing, final acceptance testing and system

documentation that is required to validate the operational performance of the ramp metering systems, as shown on the plans and described elsewhere in these special provisions.

The Contractor shall submit a copy of each document to the Engineer for approval. The Engineer shall review and either approve, or reject the document within 10 working days. If the Engineer rejects the document, the Contractor shall submit a revised document within 10 working days for review and approval by the Engineer.

Unless specified elsewhere, the Contractor shall provide to the Engineer two printed copies of each document approved by the Engineer and as specified in these special provisions. For testing purposes, a "ping" is used as: a computer network administration utility used to test whether a particular host is reachable across an internet protocol (IP) network. The IP addressable equipment shall be "pinged" a minimum of 5 consecutive instances for each test.

Prototype equipment is not acceptable. All equipment shall be current standard production units and shall have been in use for a minimum of 6 months. Rebuilt or reconditioned equipment will not be allowed.

PRE-INSTALLATION TESTING

Laboratory testing shall include testing of all new material and cables in a laboratory environment prior to delivery to the site. The tests shall either be conducted at the equipment manufacturer's premises or at a laboratory arranged by the Contractor, unless otherwise specified elsewhere in these special provisions.

The Contractor shall provide documentation for demonstrating specification compliance on each Contractor-furnished item. Documentation shall include certification from manufacturer indicating that each piece of Contractor-furnished equipment meet its requirements described in these special provisions.

PHYSICAL INSPECTION

The Contractor shall provide documentation to prove delivery of all material, equipment, cable and documentation. If any material or documentation is outstanding or have been replaced under pre-acceptance warranty a physical inspection and documentation shall be provided for this material. The physical inspection shall consist of inspecting all installed material to ensure workmanship satisfies the specified requirements.

ACCEPTANCE TESTING

The acceptance testing includes the preparation of an acceptance test plan, , and documentation of the results.

Final acceptance tests shall be conducted after the site test results have been reviewed and accepted by the Engineer. These tests include the complete system in normal operations.

Installation documentation and test results shall be provided for all material, equipment and cable prior to submission of the acceptance test plan and commencement of acceptance tests. This documentation shall be in accordance with the Contract and shall include the following as appropriate:

1. Model and part number for all material.

2. Identification of interconnections.

The Contractor shall submit a copy of the acceptance test plan to the Engineer for approval prior to commencement of acceptance testing. The acceptance test plan shall address the full testing requirements of the specifications. The acceptance test plan shall detail all tests to be performed, the test results which are expected and the test schedule. The acceptance test plan will include the following major test and acceptance categories:

1. Physical inspection
2. Functional tests
3. Performance tests

On approval by the Engineer, the Contractor shall submit two copies of the acceptance test plan to the Engineer.

The Contractor shall test the communication system according to the approved acceptance test plan and shall provide all test equipment, labor and ancillary items required to perform the testing. The test equipment shall be certified to be calibrated to the manufacturers' specifications. The model and part numbers and date of last calibration of all test equipment shall be included with the test results.

Acceptance testing shall not commence until all material required by these special provisions and plans are delivered, installed, aligned, all production test and site test documentation and results have been approved by the Engineer.

All acceptance test results shall be fully documented and such documentation provided as a condition of acceptance.

FUNCTIONAL TESTS

Functional testing shall be performed on material after delivery to the site. Functional tests shall be performed in accordance with an approved test plan. Material or equipment which fails to meet requirements shall be repaired or replaced and tests shall be repeated until satisfactory. Functional test results, including results of failed tests or re-tests, shall be submitted and delivered with material and equipment delivered to the site.

Full performance tests shall be performed on not less than 5 percent or at least one unit of material selected at random from the delivered material and equipment. Full performance tests shall be performed in accordance with a test plan developed by the Contractor and approved by the Engineer.

FIELD ELEMENT CONNECTIVITY TESTING

The Contractor shall verify the performance of the communication equipment (Network to Serial Adapter). All applicable network addresses and settings will be supplied to the Contractor. The acceptance testing for each Element cabinet shall consist of the following steps:

1. The Network to Serial Adapter shall be "pinged" from the TMC. To constitute a successful "ping", there must be a response from the target IP Address.

2. The Network to Serial Adapter shall be turned OFF. A "ping" from the TMC shall then be sent and the Element Fiber Optic Switch and Network to Serial Adapter shall not be responsive.
3. The Network to Serial Adapter shall then be turned ON. A "ping" from the TMC shall be sent and the Element Fiber Optic Switch and Network to Serial Adapter shall be successful.

FINAL ACCEPTANCE

The system will not be accepted until all of the following conditions have been met as follows:

1. Physical, functional and full performance acceptance tests have been completed and the results are approved by the Engineer.
2. All documentation has been completed and submitted to the Engineer.
3. All connections that were changed to perform acceptance tests are restored and tested.

Upon completion of acceptance tests the Contractor shall connect all equipment to form a fully operational system.

10-3.29 PAYMENT

The contract lump sum price or prices paid for signal and lighting shall include highway lighting at intersections in connection with signals only.

Other roadway lighting on the project shall be considered as included in the contract lump sum price paid for lighting and sign illumination.

Full compensation for hauling and stockpiling electrical materials shall be considered as included in the contract price paid for the item requiring the material to be salvaged and no additional compensation will be allowed therefor.

If any of the fabrication sites for the materials listed are located more than 300 air line miles from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impractical and difficult to determine the actual increase in these expenses, it is agreed that payment to the Contractor for furnishing these listed materials from each fabrication site located more than 300 air line miles from both Sacramento and Los Angeles will be reduced \$2,000:

1. Service equipment enclosures

Full compensation for Type III-BF and Type III-CF service equipment enclosures shall be considered as included in the contract prices paid for the various items requiring service equipment enclosures and no additional compensation will be allowed therefor.

Full compensation for the removal of lighting and sign illumination is included in the contract lump sum price paid for lighting and sign illumination and no additional compensation will be made therefor.

Full compensation for the removal of signal and lighting equipment is included in the contract lump sum price paid for the appropriate signal and lighting and no additional compensation will be made therefor.

The contract lump sum price paid for modify traffic monitoring station shall include full compensation for furnishing all labor, materials, tools, wiring, jumpers, equipment, and incidentals, and for doing all the work involved in traffic monitoring station, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract lump sum price paid for ramp metering system shall include full compensation for furnishing all labor, materials, tools, wiring, jumpers, equipment, and incidentals, and for doing all the work involved in ramp metering system, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for communication system shall be considered as included in the contract lump sum price for ramp metering system and no separate payment will be made therefore.

Standard Plans List

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. Applicable Revised Standard Plans (RSP) and New Standard Plans (NSP) indicated below are included in the project plans as Standard Plan sheets.

ACRONYMS, ABBREVIATIONS AND SYMBOLS

A10A	Acronyms and Abbreviations (Sheet 1 of 2)
A10B	Acronyms and Abbreviations (Sheet 2 of 2)
A10C	Symbols (Sheet 1 of 2)
A10D	Symbols (Sheet 2 of 2)

PAVEMENT MARKERS, TRAFFIC LINES, AND PAVEMENT MARKINGS

A20A	Pavement Markers and Traffic Lines, Typical Details
A20B	Pavement Markers and Traffic Lines, Typical Details
A20C	Pavement Markers and Traffic Lines, Typical Details
A20D	Pavement Markers and Traffic Lines, Typical Details
A24A	Pavement Markings – Arrows
A24B	Pavement Markings – Arrows
RSP A24C	Pavement Markings – Symbols and Numerals
A24D	Pavement Markings – Words
A24E	Pavement Markings – Words and Crosswalks

EXCAVATION AND BACKFILL

A62A	Excavation and Backfill – Miscellaneous Details
A62B	Limits of Payment for Excavation and Backfill – Bridge Surcharge and Wall
A62C	Limits of Payment for Excavation and Backfill – Bridge
A62D	Excavation and Backfill – Concrete Pipe Culverts
RSP A62DA	Excavation and Backfill – Concrete Pipe Culverts
A62E	Excavation and Backfill – Cast-In-Place Reinforced Concrete Box and Arch Culverts
A62F	Excavation and Backfill – Metal and Plastic Culverts

OBJECT MARKERS, DELINEATORS, CHANNELIZERS AND BARRICADES

A73A	Object Markers
A73B	Markers
A73C	Delineators, Channelizers and Barricades

SURVEY MONUMENTS

RSP A74	Survey Monuments
---------	------------------

METAL BEAM GUARD RAILING – STANDARD RAILING SECTIONS

RSP A77A1	Metal Beam Guard Railing – Standard Railing Section (Wood Post with Wood Block)
A77B1	Metal Beam Guard Railing – Standard Hardware
A77C1	Metal Beam Guard Railing – Wood Post and Wood Block Details
RSP A77C3	Metal Beam Guard Railing – Typical Line Post Embedment and Hinge Point Offset Details
RSP A77C4	Metal Beam Guard Railing – Typical Railing Delineation and Dike

	Positioning Details
NSP A77C5	Metal Beam Guard Railing – Typical Vegetation Control Standard Railing Section
NSP A77C6	Metal Beam Guard Railing – Typical Vegetation Control for Terminal System End Treatments
NSP A77C7	Metal Beam Guard Railing – Typical Vegetation Control at Structure Approach and Departure
NSP A77C8	Metal Beam Guard Railing – Typical Vegetation Control at Fixed Object
NSP A77C9	Metal Beam Guard Railing – Typical Vegetation Control at Fixed Object
NSP A77C10	Metal Beam Guard Railing – Typical Vegetation Control at Fixed Object
	METAL BEAM GUARD RAILING – TYPICAL LAYOUTS FOR EMBANKMENTS
RSP A77E1	Metal Beam Guard Railing – Typical Layouts for Embankments
RSP A77E2	Metal Beam Guard Railing – Typical Layouts for Embankments
RSP A77E3	Metal Beam Guard Railing – Typical Layouts for Embankments
RSP A77E4	Metal Beam Guard Railing – Typical Layouts for Embankments
RSP A77E5	Metal Beam Guard Railing – Typical Layouts for Embankments
RSP A77E6	Metal Beam Guard Railing – Typical Layouts for Embankments
	METAL BEAM GUARD RAILING – TYPICAL LAYOUTS FOR STRUCTURES
RSP A77F1	Metal Beam Guard Railing – Typical Layouts for Structure Approach
A77F2	Metal Beam Guard Railing – Typical Layouts for Structure Approach and Between Structures
RSP A77F3	Metal Beam Guard Railing – Typical Layouts for Structure Approach
	METAL BEAM GUARD RAILING – TYPICAL LAYOUTS FOR FIXED OBJECTS
RSP A77G3	Metal Beam Guard Railing – Typical Layouts for Roadside Fixed Objects
RSP A77G4	Metal Beam Guard Railing – Typical Layouts for Roadside Fixed Objects
RSP A77G5	Metal Beam Guard Railing – Typical Layouts for Roadside Fixed Objects
RSP A77G6	Metal Beam Guard Railing – Typical Layouts for Roadside Fixed Objects
RSP A77G7	Metal Beam Guard Railing – Typical Layouts for Roadside Fixed Objects
RSP A77G8	Metal Beam Guard Railing – Typical Layouts for Roadside Fixed Objects
	METAL BEAM GUARD RAILING – END ANCHORAGE AND RAIL TENSIONING ASSEMBLY
RSP A77H1	Metal Railing – End Anchor Assembly (Type SFT)
RSP A77H2	Metal Railing – Rail Tensioning Assembly
A77H3	Metal Railing – Anchor Cable and Anchor Plate Details
A77I1	Metal Railing – End Anchor Assembly (Type CA)
A77I2	Metal Beam Guard Railing – Buried Post End Anchor
	METAL BEAM GUARD RAILING – CONNECTIONS DETAILS AND TRANSITION RAILING TO BRIDGE RAILINGS, ABUTMENTS AND WALLS
RSP A77J3	Metal Beam Guard Railing – Connections to Abutments and Walls
RSP A77J4	Metal Beam Guard Railing – Transition Railing (Type WB)
RSP A77K1	Metal Beam Guard Railing – Connections to Bridge Railings with Sidewalks Details No. 1
A77K2	Metal Beam Guard Railing – Connections to Bridge Railings with Sidewalks Details No. 2

**METAL BEAM GUARD RAILING – TERMINAL SYSTEM END
TREATMENT**

A77L1 Metal Beam Railing – Terminal System (Type SRT)
A77L5 Metal Beam Railing – Terminal System (Type FLEAT)

FENCES

RSP A85 Chain Link Fence
NSP A85A Chain Link Fence Details
NSP A85B Chain Link Fence Details

**CURBS, DRIVEWAYS, DIKES, CURB RAMPS AND ACCESSIBLE
PARKING**

RSP A87A Curbs and Driveways
A87B Asphalt Concrete Dikes
RSP A88A Curb Ramp Details
A88B Curb Ramp and Island Passageway Details

PAVEMENTS

RSP P1 Jointed Plain Concrete Pavement
RSP P2 Jointed Plain Concrete Pavement – Widened Slab Details
RSP P8 Jointed Plain Concrete Pavement – Individual Slab Replacement
RSP P10 Concrete Pavement – Dowel Bar Details
RSP P12 Concrete Pavement – Dowel Bar Basket Details
NSP P13 Continuously Reinforced Concrete Pavement – Single Piece Transverse
Bar Assembly
RSP P17 Concrete Pavement – Tie Bar Basket Details
RSP P18 Concrete Pavement – Lane Schematics and Isolation Joint Detail
RSP P20 Concrete Pavement – Joint Details
RSP P30 Jointed Plain Concrete Pavement – End Panel Pavement Transitions
P33 Concrete Pavement – Lane Drop Paving Details
NSP P34 Concrete Pavement – Lane Drop Paving Details No. 2
RSP P35 Concrete Pavement – Ramp Transition Paving Details
RSP P45 Concrete Pavement – Drainage Inlet Details No. 1
RSP P46 Concrete Pavement – Drainage Inlet Details No. 2
P70 Asphalt Concrete Paving (Longitudinal Tapered Notched Wedge Joint)

DRAINAGE INLETS, PIPE INLETS AND GRATES

NSP D71 Drainage Inlet Markers
D72 Drainage Inlets
D73 Drainage Inlets
NSP D73A Drainage Inlets (Precast)
D74A Drainage Inlets
RSP D74B Drainage Inlets
D74C Drainage Inlets Details
D75A Steel Pipe Inlets
RSP D75B Concrete Pipe Inlets
D75C Pipe Inlets – Ladder and Trash Rack Details
RSP D77A Grate Details
D77B Bicycle Proof Grate Details

GUTTER AND INLET DEPRESSIONS

D78A Gutter Depressions
D78B Inlet Depressions – Concrete Shoulders
D78C Inlet Depressions – Asphalt Concrete Shoulders

	BOX CULVERTS
D81	Cast-In-Place Reinforced Concrete – Double Box Culvert
D82	Cast-In-Place Reinforced Concrete Box Culvert – Miscellaneous Details
D84	Box Culvert Wingwalls – Types A, B and C
	PIPE DOWNDRAINS, ANCHORAGE SYSTEMS AND OVERSIDE DRAINS
D87A	Corrugated Metal Pipe Downdrain Details
D87C	Cable Anchorage System
D87D	Overside Drains
	PIPE HEADWALLS, ENDWALLS AND WINGWALLS
D89	Pipe Culver Headwalls – Straight and "L"
D90	Pipe Culvert Headwalls, Endwalls and Wingwalls – Types A, B and C
	PIPE RISER AND DRAINAGE INLET RISER CONNECTIONS
D93A	Pipe Riser Connections
D93B	Drainage Inlet Riser Connections
D93C	Pipe Riser with Debris Rack Cage
	FLARED END SECTIONS
D94A	Metal and Plastic Flared End Sections
D94B	Concrete Flared End Sections
	PIPE COUPLING AND JOINT DETAILS
D97A	Corrugated Metal Pipe Coupling Details No. 1 – Annular Coupling Band Bar and Strap and Angle Connections
D97C	Corrugated Metal Pipe Coupling Details No. 2 – Helical and Universal Couplers
RSP D97D	Corrugated Metal Pipe Coupling Details No. 4 – Hugger Coupling Bands
RSP D97E	Corrugated Metal Pipe Coupling Details No. 5 – Standard Joint
RSP D97F	Corrugated Metal Pipe Coupling Details No. 6 – Positive Joint
RSP D97G	Corrugated Metal Pipe Coupling Details No. 7 – Downdrain
D97H	Reinforced Concrete Pipe or Non-Reinforced Concrete Pipe – Standard and Positive Joints
	PLANTING AND IRRIGATION
RSP H1	Planting and Irrigation – Abbreviations
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
	EROSION CONTROL
RNSP H51	Erosion Control Details (Fiber Roll)
	TEMPORARY CRASH CUSHIONS, RAILING AND TRAFFIC SCREEN
RSP T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
RSP T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
RSP T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
NSP T3A	Temporary Railing (Type K)
T4	Temporary Traffic Screen
T5	Temporary Terminal Section (Type K)
	PROJECT FUNDING SIGNS
RSP T7	Construction Project Funding Identification Signs
	TEMPORARY TRAFFIC CONTROL SYSTEMS
T10	Traffic Control System for Lane Closure On Freeways and Expressways

T10A Traffic Control System for Lane and Complete Closures on Freeways and Expressways

T14 Traffic Control System for Ramp Closure

T15 Traffic Control System for Moving Lane Closure on Multilane Highways

T16 Traffic Control System for Moving Lane Closure on Multilane Highways

TEMPORARY WATER POLLUTION CONTROL

T51 Temporary Water Pollution Control Details (Temporary Silt Fence)

T53 Temporary Water Pollution Control Details (Temporary Cover)

RSP T56 Temporary Water Pollution Control Details (Temporary Fiber Roll)

T57 Temporary Water Pollution Control Details (Temporary Check Dam)

T58 Temporary Water Pollution Control Details (Temporary Construction Entrance)

NSP T62 Temporary Water Pollution Control Details (Temporary Drainage Inlet Protection)

NSP T65 Temporary Water Pollution Control Details [Temporary Fence (Type ESA)]

BRIDGE DETAILS

B0-1 Bridge Details

B0-3 Bridge Details

B0-5 Bridge Details

B0-13 Bridge Details

PILES

B2-3 16" and 24" Cast-In-Drilled-Hole Concrete Pile

RETAINING WALLS

B3-1 Retaining Wall Type 1 - H = 4' through 30'

B3-7 Retaining Wall Type 5

B3-8 Retaining Wall Details No. 1

B3-9 Retaining Wall Details No. 2

JOINT SEALS

RSP B6-21 Joint Seals (Maximum Movement Rating = 2")

BOX GIRDER DETAILS

B7-1 Box Girder Details

DECK DRAINS

B7-6 Deck Drains - Types D-1 and D-2

B7-8 Deck Drainage Details

UTILITY OPENING

B7-10 Utility Opening - Box Girder

B7-11 Utility Details

CAST-IN-PLACE PRESTRESSED GIRDER

B8-5 Cast-In-Place Prestressed Girder Details

CHAIN LINK RAILING, CABLE RAILING AND TUBULAR HAND RAILING

B11-47 Cable Railing

B11-51 Tubular Hand Railing

B11-52 Chain Link Railing Type 7

BRIDGE CONCRETE BARRIERS

B11-54 Concrete Barrier Type 26

B11-56 Concrete Barrier Type 736

WATER SUPPLY LINE (BRIDGE)

- B14-5 Water Supply Line (Details) (Pipe Sizes Less Than 4")**
- ROADSIDE SIGNS**
- RS1 Roadside Signs, Typical Installation Details No. 1**
- RS2 Roadside Signs – Wood Post, Typical Installation Details No. 2**
- RS3 Roadside Signs – Laminated Wood Box Post Typical Installation Details No. 3**
- RS4 Roadside Signs, Typical Installation Details No. 4**
- OVERHEAD SIGNS (TRUSS)**
- S1 Overhead Signs – Truss, Instructions and Examples**
- S2 Overhead Signs – Truss, Single Post Type – Post Type II thru IX**
- S3 Overhead Signs – Truss, Single Post Type – Base Plate and Anchorage Details**
- S4 Overhead Signs – Truss, Single Post Type – Structural Frame Members Details No. 1**
- S5 Overhead Signs – Truss, Single Post Type – Structural Frame Members Details No. 2**
- S6 Overhead Signs – Truss, Gusset Plate Details**
- S7 Overhead Signs – Truss, Single Post Type – Square Pedestal Pile Foundation**
- S8 Overhead Signs – Truss, Single Post Type – Round Pedestal Pile Foundation**
- S12 Overhead Signs – Truss, Structural Frame Details**
- S13 Overhead Signs – Truss, Frame Juncture Details**
- S16 Overhead Signs – Walkway Details No. 1**
- S17 Overhead Signs – Walkway Details No. 2**
- S17A Overhead Signs – Walkway Details No. 3**
- S18 Overhead Signs – Walkway Safety Railing Details**
- S19 Overhead Signs – Truss, Sign Mounting Details – Laminated Panel – Type A**
- OVERHEAD AND ROADSIDE SIGNS PANELS**
- S81 Overhead Laminated Sign – Single or Multiple Panel, Type A (1" Thick)**
- S85 Seam Closure, "H" Section Extrusion and Post Spacing Tables, Multi-Horizontal Laminated Panel Aluminum Signs**
- S86 Laminated Panel Details – Extrusions for Type A, B and H Panels**
- S87 Type A-1 Mounting Hardware – Overhead Laminated Type A Panel, Truss and Lightweight Sign Structures**
- S88 Type A-2 Mounting Hardware – Overhead Laminated Type A Panel, Bridge Mounted and Tubular Sign Structures**
- S93 Framing Details for Framed Single Sheet Aluminum Signs, Rectangular Shape**
- S94 Roadside Framed Single Sheet Aluminum Signs, Rectangular Shape**
- S95 Roadside Single Sheet Aluminum Signs, Diamond Shape**
- ELECTRICAL SYSTEMS – SYMBOLS AND ABBREVIATIONS**
- RSP ES-1A Electrical Systems (Symbols and Abbreviations)**
- RSP ES-1B Electrical Systems (Symbols and Abbreviations)**
- RSP ES-1C Electrical Systems (Symbols and Abbreviations)**

**ELECTRICAL SYSTEMS – SERVICE EQUIPMENT AND WIRING
DIAGRAMS**

ES-2A	Electrical Systems (Service Equipment)
RSP ES-2C	Electrical Systems (Service Equipment Notes, Type III Series)
RSP ES-2E	Electrical Systems (Service Equipment and Typical Wiring Diagram, Type III – B Series)
RSP ES-2F	Electrical Systems (Service Equipment and Typical Wiring Diagram Type III – C Series)
ES-3B	Electrical Systems (Controller Cabinet Details)
ES-3C	Electrical Systems (Controller Cabinet Details)

**ELECTRICAL SYSTEMS – TELEPHONE DEMARCATION
CABINETS**

RSP ES-3F	Electrical Systems (Telephone Demarcation Cabinet, Type C)
ES-3G	Electrical Systems (Telephone Demarcation Cabinet, Type C Details)

**ELECTRICAL SYSTEMS – IRRIGATION CONTROLLER
ENCLOSURE CABINET**

ES-4A	Electrical Systems (Signal Heads and Mountings)
ES-4B	Electrical Systems (Signal Heads and Mountings)
RSP ES-4C	Electrical Systems (Signal Heads and Mountings)
RSP ES-4D	Electrical Systems (Signal Heads and Mountings)
ES-4E	Electrical Systems (Signal Faces and Mountings)

ELECTRICAL SYSTEMS – DETECTORS

RSP ES-5A	Electrical Systems (Detectors)
ES-5B	Electrical Systems (Detectors)
ES-5C	Electrical Systems (Detectors)
ES-5D	Electrical Systems (Detectors)

ELECTRICAL SYSTEMS – LIGHTING STANDARDS

RSP ES-6A	Electrical Systems (Lighting Standard, Types 15 and 21)
ES-6B	Electrical Systems (Lighting Standard, Types 15 and 21, Barrier Rail Mounted Details)
RSP ES-6E	Electrical Systems (Lighting Standard, Types 30 and 31)
ES-6F	Electrical Systems (Lighting Standard, Types 30 and 31, Slip Base Plate Details)

**ELECTRICAL SYSTEMS – SIGNAL AND LIGHTING STANDARD,
PUSH BUTTON POSTS AND TYPE 15TS STANDARD**

ES-7A	Electrical Systems (Signal and Lighting Standards, Push Button Posts and Type 15TS Standard)
RSP ES-7B	Electrical Systems (Signal and Lighting Standard – Type 1 Standards and Equipment Numbering)
RSP ES-7E	Electrical Systems (Signal and Lighting Standard – Case 3 Arm Loading, Wind Velocity = 100 mph, Arm Lengths 15' to 45')
RSP ES-7F	Electrical Systems (Signal and Lighting Standard – Case 4 Arm Loading, Wind Velocity = 100 mph, Arm Lengths 25' to 45')
RSP ES-7G	Electrical Systems (Signal And Lighting Standard – Case 5 Arm Loading, Wind Velocity = 100 mph, Arm Lengths 50' to 55')
ES-7H	Electrical Systems (Signal and Lighting Standard – Case 5 Arm Loading, Wind Velocity = 100 mph, Arm Lengths 60' to 65')

**ELECTRICAL SYSTEMS – SIGNAL AND LIGHTING STANDARD
DETAILS**

- ES-7M Electrical Systems (Signal and Lighting Standards – Details No. 1)
ES-7N Electrical Systems (Signal and Lighting Standards – Details No. 2)
- ELECTRICAL SYSTEMS – INTERNALLY ILLUMINATION STREET
NAME SIGN**
- ES-70 Electrical Systems (Sign Illumination – Internally Illumination Street
Name Sign)
- ELECTRICAL SYSTEMS – PEDESTRIAN BARRICADES**
- ES-7P Electrical Systems (Pedestrian Barricades)
- ELECTRICAL SYSTEMS – PULL BOX DETAILS**
- ES-8 Electrical Systems (Pull Box Details)
- ELECTRICAL SYSTEMS – ELECTRICAL DETAILS, STRUCTURE
INSTALLATIONS**
- RSP ES-9A Electrical Systems (Electrical Details, Structure Installations)
ES-9B Electrical Systems (Electrical Details, Structure Installations)
RSP ES-9C Electrical Systems (Electrical Details, Structure Installations)
ES-9D Electrical Systems (Electrical Details, Structure Installations)
ES-9E Electrical Systems (Electrical Details, Structure Installations)
- ELECTRICAL SYSTEMS – ISOFOOTCANDLE DIAGRAMS AND
FOUNDATION DETAILS**
- ES-10 Electrical Systems (Isofootcandle Diagrams)
ES-11 Electrical Systems (Foundation Installations)
- ELECTRICAL SYSTEMS – SPLICING, WIRING DETAILS AND
FUSE RATINGS**
- ES-13A Electrical Systems (Splicing Details)
ES-13B Electrical Systems (Wiring Details and Fuse Ratings)
- ELECTRICAL SYSTEMS – SIGN ILLUMINATION EQUIPMENT
AND CONTROLS**
- ES-15A Electrical Systems (Sign Illumination Equipment)
ES-15B Electrical Systems (36" Fluorescent Sign Illumination Equipment)
ES-15C Electrical Systems (Sign Illumination Equipment)
RSP ES-15D Electrical Systems (Lighting and Sign Illumination Control)



OFFICE OF
CLERK OF THE BOARD OF SUPERVISORS
1st FLOOR, COUNTY ADMINISTRATIVE CENTER
P.O. BOX 1147, 4080 LEMON STREET
RIVERSIDE, CA 92502-1147
PHONE: (951) 955-1060
FAX: (951) 955-1071

KECIA HARPER-IHEM
Clerk of the Board of Supervisors

KIMBERLY A. RECTOR
Assistant Clerk of the Board

September 20, 2011

THE PRESS ENTERPRISE
ATTN: LEGALS
PO BOX 792
RIVERSIDE, CA 92501

FAX (951) 368-9018
E-MAIL: legals@pe.com

RE: NOTICE INVITING BIDS: INTERSTATE 15 AT CLINTON KEITH ROAD A2-0264

To Whom It May Concern:

Attached is a copy for publication in your newspaper for **TEN (10) TIMES:**

Thursday	- September 22, 2011	Tuesday	- September 27, 2011
Friday	- September 23, 2011	Wednesday	- September 28, 2011
Saturday	- September 24, 2011	Thursday	- September 29, 2011
Sunday	- September 25, 2011	Friday	- September 30, 2011
Monday	- September 26, 2011	Saturday	- October 1, 2011

We require your affidavit of publication immediately upon completion of the last publication.

Your invoice must be submitted to this office in duplicate, WITH TWO CLIPPINGS OF THE PUBLICATION.

NOTE: PLEASE COMPOSE THIS PUBLICATION INTO A SINGLE COLUMN FORMAT.

Thank you in advance for your assistance and expertise.

Sincerely,

McGil

Cecilia Gil, Board Assistant to
KECIA HARPER-IHEM, CLERK OF THE BOARD

Gil, Cecilia

From: PE Legals <legals@pe.com>
Sent: Tuesday, September 20, 2011 9:35 AM
To: Gil, Cecilia
Subject: RE: FOR PUBLICATION: BIDS for I15 at Clinton Keith Road A2-0264

Received for publication on Sept. 22 & Oct. 1

Thank You!

enterprisemedia

Publisher of the Press-Enterprise

Maria G. Tinajero • Legal Advertising Department

1-800-880-0345 • Fax: 951-368-9018 • email: legals@pe.com

Please Note: Deadline is 10:30 AM two (2) business days prior to the date you would like to publish.

Additional days required for larger ad sizes

From: Gil, Cecilia [<mailto:CCGIL@rcbos.org>]
Sent: Tuesday, September 20, 2011 9:26 AM
To: PE Legals
Subject: FOR PUBLICATION: BIDS for I15 at Clinton Keith Road A2-0264

Good Morning! Attached is a Notice Inviting Bids, for publication from Sept. 22 to Oct. 1, 2011. Please confirm. THANK YOU!

Cecilia Gil

Board Assistant to the
Clerk of the Board of Supervisors
951-955-8464

**THE COUNTY ADMINISTRATIVE CENTER IS CLOSED EVERY FRIDAY UNTIL FURTHER NOTICE.
PLEASE CONSIDER THE ENVIRONMENT BEFORE PRINTING.**

NOTICE INVITING BIDS

County of Riverside, herein called Owner, invites sealed proposals for:

**INTERSTATE 15 AT CLINTON KEITH ROAD
INTERCHANGE IMPROVEMENTS**

PROJECT No. A2-0264

Proposal shall be delivered to the Riverside County Transportation department, 14th Street Annex, 3525 14th Street, Riverside, California 92501, telephone (951) 955-6780 not later than 2:00 p.m., on Wednesday, October 19, 2011, to be promptly opened in public at said address. Each proposal shall be in accordance with plans, specifications, and other contract documents, dated August 2011, and prepared by County of Riverside, whose address is same as the above, from whom they may be obtained upon deposit of \$125 per full size plan set (or \$65 per half size plan [11"x17"]), plus mailing. No refund. Prospective bidders may preview the plans, specifications and other contract documents, at no charge prior to purchase, at the above noted location.

The Contractor is required to have a Class "A" license at the time of bid submission.

Engineering Estimate	\$14,850,000.00 - \$17,325,000.00
Bid Bond	10%
Performance Bond	100%
Payment Bond	100%
Working Days	300 Working Days

www.tlma.co.riverside.ca.us/trans

Dated: September 20, 2011

Kecia Harper-Ihem, Clerk of the Board
By: Cecilia Gil, Board Assistant



THE PRESS-ENTERPRISE **TV.com**



WEEKLY



HS

e-MEDIA waves

LANDSOCAL

10	11	12	13	14	15	16	17	18	19	20
DATE	REFERENCE NUMBER	DESCRIPTION - OTHER COMMENTS/CHARGES	PRODUCT/ZONE	SIZE	BILLED UNITS	TIMES RUN	RATE	GROSS AMOUNT	NET AMOUNT	
09/22/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.30	122.20	122.20	
09/23/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
09/24/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
09/25/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
09/26/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
09/27/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
09/28/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
09/29/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
09/30/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	
10/01/2011	I00624260-09222011	NOTICE INVITING BIDS County of River	Press-Enterprise	2 x 47 LI	94	1	1.20	112.80	112.80	

Order Placed by: Cecilia Gil

RECEIVED RIVERSIDE COUNTY
 CLERK / BOARD OF SUPERVISORS
 2011 OCT 11 PM 1:36

*Transp.
3.96 of 09/13/11*

Legal Advertising Invoice

BALANCE
\$1,137.40

SALES CONTACT INFORMATION		ADVERTISER INFORMATION			
1	25	6	7	2	
Maria Tinajero 951-368-9225	BILLING PERIOD 10/01/2011 - 10/01/2011	BILLED ACCOUNT NUMBER 100141323	ADVERTISER/CLIENT NUMBER 100141323	ADVERTISER/CLIENT NAME BOARD OF SUPERVISORS	

PLEASE DETACH AND RETURN THIS PORTION WITH YOUR REMITTANCE

ADVERTISER/CLIENT NAME			
BOARD OF SUPERVISORS			
1	6	7	
BILLING PERIOD 10/01/2011 - 10/01/2011	BILLED ACCOUNT NUMBER 100141323	ADVERTISER/CLIENT NUMBER 100141323	
23	24	3	
BALANCE \$1,137.40	INVOICE NUMBER I00624260-09222011	TERMS OF PAYMENT DUE UPON RECEIPT	



Legal Advertising Invoice

8 BILLING ACCOUNT NAME AND ADDRESS

9 REMITTANCE ADDRESS

BOARD OF SUPERVISORS
P.O. BOX 1147
COUNTY OF RIVERSIDE
RIVERSIDE, CA 92502

Enterprise Media
POST OFFICE BOX 12009
RIVERSIDE, CA 92502-2209

THE PRESS-ENTERPRISE

3450 Fourteenth Street
Riverside, CA 92501-3878
951-684-1200
951-368-9018 FAX

PROOF OF PUBLICATION (2010, 2015.5 C.C.P)

Publication(s): Press-Enterprise

PROOF OF PUBLICATION OF


Ad Desc.: /

I am a citizen of the United States. I am over the age of eighteen years and not a party to or interested in the above entitled matter. I am an authorized representative of THE PRESS-ENTERPRISE, a newspaper in general circulation, printed and published daily in the County of Riverside, and which newspaper has been adjudicated a newspaper of general circulation by the Superior Court of the County of Riverside, State of California, under date of April 25, 1952, Case Number 54446, under date of March 29, 1957, Case Number 65673, and under date of August 25, 1995, Case Number 267864; that the notice, of which the annexed is a printed copy, has been published in said newspaper in accordance with the instructions of the person(s) requesting publication, and not in any supplement thereof on the following dates, to wit:

09/22, 09/23, 09/24, 09/25, 09/26, 09/27, 09/28, 09/29, 09/30, 10/01/2011

I certify (or declare) under penalty of perjury that the foregoing is true and correct.

Date: October 01, 2011
At: Riverside, California



BOARD OF SUPERVISORS
P.O. BOX 1147
COUNTY OF RIVERSIDE
RIVERSIDE, CA 92502

Ad Number: 0000624260-01

P.O. Number:

Ad Copy:

NOTICE INVITING BIDS

County of Riverside, herein called Owner, invites sealed proposals for:

INTERSTATE 15 AT CLINTON KEITH ROAD INTERCHANGE IMPROVEMENTS

PROJECT No. A2-0264

Proposal shall be delivered to the Riverside County Transportation department, 14th Street Annex, 3525 14th Street, Riverside, California 92501, telephone (951) 955-6780 not later than 2:00 p.m., on Wednesday, October 19, 2011, to be promptly opened in public at said address. Each proposal shall be in accordance with plans, specifications, and other contract documents, dated August 2011, and prepared by County of Riverside, whose address is same as the above, from whom they may be obtained upon deposit of \$125 per full size plan set (or \$65 per half size plan (11"x17")), plus mailing. No refund. Prospective bidders may preview the plans, specifications and other contract documents, at no charge prior to purchase, at the above noted location.

The Contractor is required to have a Class 'A' license at the time of bid submission.

Engineering Estimate	\$14,850,000.00 - \$17,325,000.00
Bid Bond	10%
Performance Bond	100%
Payment Bond	100%
Working Days	300 Working Days

www.ftma.co.riverside.ca.us/trans

Dated: September 20, 2011

Kecia Harper-Ihem, Clerk of the Board
By: Cecilia Gil, Board Assistant 9/22-10/1