

**SUBMITTAL TO THE FLOOD CONTROL AND
WATER CONSERVATION DISTRICT
BOARD OF SUPERVISORS
COUNTY OF RIVERSIDE, STATE OF CALIFORNIA**



ITEM: 11.3
(ID # 11881)

MEETING DATE:
Tuesday, February 25, 2020

FROM: FLOOD CONTROL DISTRICT:

SUBJECT: FLOOD CONTROL DISTRICT: Accept Low Bid and Award the Contract for the Jurupa-Pyrite MDP Line A-2, Stage 1, Project No. 1-0-00234-01, District 2. [\$361,156 - District Funds 100%]

RECOMMENDED MOTION: That the Board of Supervisors:

1. Accept the low bid submitted by the firm of Southwest General Engineering for \$350,637 for the construction of the above-referenced project;
2. Award the contract to Southwest General Engineering and authorize the Chairwoman of the Board of Supervisors of the Riverside County Flood Control and Water Conservation District (District) to execute the Construction Agreement on behalf of the District; and
3. Direct the Clerk of the Board to return three (3) copies of the executed Jurupa-Pyrite MDP Line A-2, Stage 1 contract documents to the District.


ACTION:Policy

Jason Uhley, GENERAL MGR-CHF FLD CNTRL ENG 1/30/2020

MINUTES OF THE BOARD OF SUPERVISORS

On motion of Supervisor Spiegel, seconded by Supervisor Jeffries and duly carried by unanimous vote, IT WAS ORDERED that the above matter is approved as recommended.

Ayes: Jeffries, Spiegel, Washington, Perez and Hewitt
Nays: None
Absent: None
Date: February 25, 2020
xc: Flood

Kecia R. Harper
Clerk of the Board
By: 
Deputy

**SUBMITTAL TO THE FLOOD CONTROL AND WATER CONSERVATION DISTRICT BOARD
OF SUPERVISORS
COUNTY OF RIVERSIDE, STATE OF CALIFORNIA**

FINANCIAL DATA	Current Fiscal Year:	Next Fiscal Year:	Total Cost:	Ongoing Cost
COST	\$ 361,156	\$ 0	\$ 361,156	\$ 0
NET COUNTY COST	\$ 0	\$ 0	\$ 0	\$ 0
SOURCE OF FUNDS:			Budget Adjustment: No	
25110 947400 548200 Zone 1 Infrastructure (97%)				
25110 947400 523220 Zone 1 License & Permits (3%)				
			For Fiscal Year: 19/20	

C.E.O. RECOMMENDATION: Approve

BACKGROUND:

Summary

On October 22, 2019 (Agenda Item 11.1, MT# 10580), the Board of Supervisors for the District authorized the Clerk of the Board to advertise for construction contract bids for the Jurupa-Pyrite MDP Line A-2, Stage 1 project.

The District opened bids for Jurupa-Pyrite MDP Line A-2, Stage 1 on November 21, 2019. The lowest responsible bid was received from Southwest General Engineering for the sum of \$350,637. Two contractors submitted a bid in response to this call for bids.

On January 2, 2020, a Notice of Intent to Award the contract to Contractor was emailed to both bidders. Pursuant to Article 3, Section 3.3 of the Instructions to Bidders, bidders are provided five (5) days to submit any protest of the intent to award. No protests were received by the deadline.

The Contractor has executed the construction contract and provided the bonds and insurance documents which meet the requirements of the contract.

The Fiscal Data listed includes this bid amount plus the required Western Riverside County Multiple Species Habitat Conservation Plan mitigation payment (see Additional Fiscal Information section below).

The Jurupa-Pyrite MDP Line A-2, Stage 1 project is located in the city of Jurupa Valley, in the County of Riverside. The project starts from the southern terminus of Bellmore Street and outlets on the western side of Agate Street. The project will remove an existing crushed corrugated metal pipe and replace it with approximately 498 feet of concrete swale between Bellmore and Agate Streets, and will construct 66 feet of grated trench drain to convey flows across Agate Street. The project is designed to provide improved drainage to residents and reduce localized ponding. This system is considered interim until a much larger '100-year' underground storm drain can be budgeted and constructed in the future.

**SUBMITTAL TO THE FLOOD CONTROL AND WATER CONSERVATION DISTRICT BOARD
OF SUPERVISORS
COUNTY OF RIVERSIDE, STATE OF CALIFORNIA**

County Counsel has reviewed the construction contract with exhibits and approved as to form.

CEQA Compliance

On April 10, 2018 (Agenda Item 11.2, MT# 6440), the Board of Supervisors for the District found that the construction of the Jurupa-Pyrite MDP Line A-2, Stage 1 project will not have a significant adverse effect on the environment and is exempt from the California Environmental Quality Act (CEQA) pursuant to Sections 15303(d) and 15061(b)(3) of the State CEQA Guidelines. In accordance with CEQA, a Notice of Exemption was prepared by the District and filed by the Clerk of the Board upon approval of the project.

Prev. Agn. Ref.: MT#10580, 11.1 of 10/22/19 Advertise
MT#6440, 11.2 of 04/10/18 CEQA Exempt

Impact on Residents and Businesses

This project will retrofit an older, built-out neighborhood with drainage infrastructure to reduce street and property flooding and will increase the public safety and quality of life for the local residents.

Additional Fiscal Information

Pursuant to the Implementing Agreement for the Western Riverside County Multiple Species Habitat Conservation Plan (MSHCP) executed on June 22, 2004, the Financial Data listed is comprised of the bid amount of \$350,637 for Contractor, plus up to \$10,519 (3% of bid) for MSHCP mitigation, for a total of \$361,156 (bid plus 3% amount). The MSHCP Implementing Agreement requires the District to make a payment to the Western Riverside County Regional Conservation Authority for up to 3% of the total capital costs (bid amount described above) as required mitigation for the construction of flood control facilities. The actual mitigation payment that will be made by the District may be reduced based on acquisition of replacement habitat for the benefit of Covered Species, as defined in the Implementing Agreement and the MSHCP.

Contract History and Price Reasonableness

Pursuant to Public Contract Code 21091, invitation of sealed bids was solicited by advertising in print and digital media. The Contractor's bid was reasonable and is approximately 29% above the project engineer's estimate.

ATTACHMENTS):

1. Bid Summary/Abstract
2. Project Location Map
3. Contract Documents (Sheets XXIII through XXXIV) and Certificate of Liability Insurance - 4 copies

**SUBMITTAL TO THE FLOOD CONTROL AND WATER CONSERVATION DISTRICT BOARD
OF SUPERVISORS
COUNTY OF RIVERSIDE, STATE OF CALIFORNIA**



Jason Farin, Senior Management Analyst

2/19/2020



Gregory F. Priamos, Director County Counsel

2/13/2020

**JURUPA-PYRITE MDP LINE A-2, STAGE 1
PROJECT NO. 1-0-00234**



THE JURUPA-PYRITE MDP LINE A-2 PROJECT IS LOCATED IN THE CITY OF JURUPA VALLEY AND WILL SERVE TO ALLEVIATE RECURRING FLOODING ISSUES EXPERIENCED BY ADJACENT RESIDENTS. THE PROJECT WILL CONSTRUCT A 9'H X 6'W CONCRETE TRAPEZOIDAL SWALE WITH 2H:1V SIDESLOPES THAT WILL CONVEY FLOWS WEST FROM THE TERMINUS OF BELLMORE STREET AND OUTLETS THROUGH A GRATED TRENCH DRAIN SYSTEM ACROSS AGATE STREET.



Riverside County Flood Control & Water Conservation District
1995 Market St. Riverside, CA 92501 Phone: 951.955.1200 Fax: 951.788.9965

Bid Summary

Project Name: JURUPA-PYRITE MDP LINE A-2, STAGE 1


Project Number: 1-0-0234-01

Bid Open Date: 11/21/2019

<i>Total</i>	<i>Contractor Name</i>	<i>Phone</i>
\$350,637.40	SOUTHWEST GENERAL ENGINEERING 3625 PLACENTIA LANE RIVERSIDE CA 9501	951-781-4303
\$583,976.00	SIDRA GROUP, INC. DBA TRINITY FENCE 6510 Box Springs Boulevard, Suite G Riverside CA 92507	951.653.6987
\$271,097.00	RCFC Engineer's Estimate	

Riverside County Flood Control & Water Conservation District

1995 Market St. Riverside, CA 92501 Phone: 951.955.1200 Fax 951.788.9965



Project Name: JURUPA-PYRITE MDP LINE A-2, STAGE 1

Project Number: 1-0-0234-01

Bid Open Date: 11/21/2019

Page 1 of 2

Item No. & Description	Unit	Quantity	ENGINEER'S ESTIMATE			SOUTHWEST GENERAL ENGINEERING			SIDRA GROUP, INC. DBA TRINITY FENCE		
			Unit Bid	Total Bid	Unit Bid	Total Bid	Unit Bid	Total Bid	Unit Bid	Total Bid	
1 MOBILIZATION	L.S.	1	\$10,000.00	\$10,000.00	\$6,670.00	\$6,670.00	\$45,983.00	\$45,983.00			
2 WATER CONTROL	L.S.	1	\$5,000.00	\$5,000.00	\$8,310.00	\$8,310.00	\$9,308.00	\$9,308.00			
3 TRAFFIC CONTROL	L.S.	1	\$8,000.00	\$8,000.00	\$11,200.00	\$11,200.00	\$46,887.00	\$46,887.00			
4 CLEARING AND MISCELLANEOUS WORK	L.S.	1	\$20,000.00	\$20,000.00	\$39,000.00	\$39,000.00	\$34,857.00	\$34,857.00			
5 EXCAVATION	C.Y.	507	\$15.00	\$7,605.00	\$44.60	\$22,612.20	\$65.00	\$32,955.00			
6 STREET RECONSTRUCTION	C.Y.	167	\$16.00	\$2,672.00	\$57.70	\$9,635.90	\$44.00	\$7,348.00			
7 BACKFILL	C.Y.	15	\$20.00	\$300.00	\$168.00	\$2,520.00	\$229.00	\$3,435.00			
8 CLASS "A" CONCRETE, RETAINING WALL	C.Y.	7	\$550.00	\$3,850.00	\$1,345.00	\$9,415.00	\$3,108.00	\$21,756.00			
9 CLASS "A" CONCRETE, CONCRETE SWALE	C.Y.	91	\$450.00	\$40,950.00	\$405.00	\$36,855.00	\$521.00	\$47,411.00			
10 CLASS "B" CONCRETE, 2' CUTOFF WALL	L.F.	983	\$15.00	\$14,745.00	\$15.70	\$15,433.10	\$38.00	\$37,354.00			
11 CLASS "B" CONCRETE, MISCELLANEOUS	C.Y.	3	\$130.00	\$390.00	\$2,270.00	\$6,810.00	\$925.00	\$2,775.00			
12 AGGREGATE BASE, CLASS 2	C.Y.	73	\$25.00	\$1,825.00	\$154.00	\$11,242.00	\$116.00	\$8,468.00			
13 HOT MIX ASPHALT (HMA)	TONS	94	\$150.00	\$14,100.00	\$138.00	\$12,972.00	\$159.00	\$14,946.00			
14 MODIFIED 6-FOOT CHAIN LINK FENCE	L.F.	500	\$20.00	\$10,000.00	\$61.50	\$30,750.00	\$55.50	\$27,750.00			
15 TEMPORARY FENCING	L.F.	197	\$35.00	\$6,895.00	\$14.80	\$2,915.60	\$15.00	\$2,955.00			
16 MODIFIED 14-FOOT DOUBLE DRIVE GATES	PAIR	1	\$800.00	\$800.00	\$3,420.00	\$3,420.00	\$4,484.00	\$4,484.00			
17 4'W X 1.5'H GRATED TRENCH DRAIN	L.F.	56	\$1,600.00	\$89,600.00	\$1,485.00	\$83,160.00	\$3,371.00	\$188,776.00			
18 MIDWEST GUARDRAIL SYSTEM	L.F.	35	\$110.00	\$3,850.00	\$48.50	\$1,697.50	\$142.00	\$4,970.00			
19 ADJUST MANHOLE TO GRADE	EACH	1	\$2,000.00	\$2,000.00	\$1,455.00	\$1,455.00	\$1,247.00	\$1,247.00			
20 EXTRA DIRECTED WORK	L.S.	1	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00			
21 ROCK SLOPE PROTECTION, CLASS I (20-LB)	C.Y.	6	\$75.00	\$450.00	\$181.00	\$1,086.00	\$1,356.00	\$8,136.00			
22 CRUSHED ROCK	C.Y.	66	\$40.00	\$2,640.00	\$73.20	\$4,831.20	\$95.00	\$6,270.00			
23 ROCK SLOPE PROTECTION FABRIC	S.Y.	17	\$25.00	\$425.00	\$20.70	\$351.90	\$57.00	\$969.00			
24 DUST ABATEMENT	L.S.	1	\$5,000.00	\$5,000.00	\$2,445.00	\$2,445.00	\$10,216.00	\$10,216.00			

Riverside County Flood Control & Water Conservation District

1995 Market St. Riverside, CA 92501 Phone: 951.955.1200 Fax 951.788.9965




Project Name: JURUPA-PYRITE MDP LINE A-2, STAGE 1

Project Number: 1-0-0234-01

Bid Open Date: 11/21/2019

Page 2 of 2

Item No. & Description	Unit	Quantity	ENGINEER'S ESTIMATE		SOUTHWEST GENERAL ENGINEERING		SIDRA GROUP, INC. DBA TRINITY FENCE	
			Unit Bid	Total Bid	Unit Bid	Total Bid	Unit Bid	Total Bid
25 STORMWATER AND NON-STORMWATER POLLUTION CONTROL	L.S.	1	\$10,000.00	\$10,000.00	\$15,850.00	\$15,850.00	\$4,720.00	\$4,720.00
				\$271,097.00		\$350,637.40		\$583,976.00



SPECIFICATIONS and CONTRACT DOCUMENTS
for the CONSTRUCTION of
JURUPA-PYRITE MDP LINE A-2,
STAGE 1

PROJECT NO. 1-0-00234

These specifications and contract documents have been prepared under the direction of the following Registered Civil Engineers:

Recommended By:


Design Engineer 10/1/2019
Date




Approved By:

General Manager—Chief Engineer 10/1/2019
Date



TABLE OF CONTENTS

<u>Title</u>	<u>Page</u>
Notice Inviting Bids to Contractors	II-III
Instructions to Bidders	IV-XIII
Bid Proposal	
Contractor's Proposal	XIV-XV
List of Subcontractors	XVI
Experience Statement	XVII
Statement of Licensure	XVIII
Non-Collusion Declaration	XIX
Iran Contracting Act Certification	XX
Bid Bond	XXI-XXII
Construction Agreement, Bonds and Other Forms	
Construction Agreement	XXIII-XXIV
Exhibit A	XXV
Performance Bond	XXVI-XXVIII
Payment Bond	XXIX-XXX
Workers' Compensation Contractor Certificate	XXXI
Declaration of Sufficiency of Funds	XXXII-XXXIV

GENERAL PROVISIONS

Section I - Definition of Terms	1
1.01 Terms	
1.02 Similarity of Words	
Section II - Scope of Work	2
2.01 Work to be Done	
2.02 Construction Schedule	
2.03 Drawings and Specifications on the Work	
2.04 Estimate of Quantities	
2.05 Protests	
2.06 Alterations	
2.07 Extra Work	
2.08 Payment for Extra Work	
2.09 Rights of Way	
2.10 Cleaning Up	
Section III - Control of the Work	6
3.01 Authority of the Engineer	
3.02 Detail Drawings	
3.03 Conformity with Plans and Allowable Deviations	
3.04 Interpretation of Plans and Specifications	
3.05 Superintendence	
3.06 Lines and Grades	

TABLE OF CONTENTS - CONTD.

GENERAL PROVISIONS contd.

	<u>Page</u>
3.07 Inspection of Work	
3.08 Removal of Defective and Unauthorized Work	
3.09 Equipment and Plant	
3.10 Final Inspection	
Section IV - Control of Material	9
4.01 District Furnished Materials	
4.02 Source of Supply and Quality of Materials	
4.03 Samples and Tests	
4.04 Digging Trenches or Other Excavations	
4.05 Storage of Materials	
4.06 Defective Materials	
4.07 Assignment of Claims	
Section V - Legal Relations and Responsibility	11
5.01 Laws to be Observed	
5.02 Contractor's Responsibility	
5.03 Contractor's Responsibility for Work	
5.04 Property Rights in Materials	
5.05 Permits and Licenses	
5.06 Royalties and Patents	
5.07 Sanitary Provisions	
5.08 Public Safety	
5.09 Use of Explosives	
5.10 Provisions for Emergencies	
5.11 Unforeseen Difficulties	
5.12 Access to the Work	
5.13 Guarantee of Work	
5.14 Damages by Act of God	
Section VI - Prosecution and Progress	18
6.01 Progress of the Work	
6.02 Overtime Work and Work at Night	
6.03 Subcontracting	
6.04 Character of Workmen	
6.05 Temporary Suspension of the Work	
6.06 Time of Completion and Damages	
6.07 Delays and Extension of Time	
6.08 Assignment	
6.09 Termination of Contract	

TABLE OF CONTENTS - CONTD.

GENERAL PROVISIONS contd.

	<u>Page</u>
Section VII - Payment	22
7.01 Scope of Payments	
7.02 Payment and Compensation for Altered Quantities	
7.03 Force Account Payment	
7.04 Acceptance	
7.05 Deductions from Payments	
7.06 Partial Payments	
7.07 Delayed Payments	
7.08 Final Payment	
7.09 Claims Resolution - Claims up to \$375,000	
7.10 Claims Resolution - All Claims (Public Contract Code Section 9204)	
Section VIII - General	34
8.01 Cooperation between Contractors	
8.02 Insurance - Indemnification/Hold Harmless/Defend	
8.03 Public Utilities	
8.04 Protection of Existing Street Facilities	
8.05 Diversion and Control of Water	
8.06 Dust Abatement	
8.07 Project Signs	
8.08 Examination of Plans, Specifications, Contract, and Site of Work	
Section IX - Watering	41
9.01 Description	
Section X - Public Convenience, Traffic Control and Detours	41
10.01 General	
10.02 Signs	
10.03 Materials Storage	

SPECIAL PROVISIONS

Section 1 - General	43
1.1 Drawings and Specifications	
1.2 Submittals to District	
Section 2 - Time of Completion, Damages and Legal Holidays	43
2.1 General	
2.2 Damages	
2.3 Legal Holidays	

TABLE OF CONTENTS - CONTD.

SPECIAL PROVISIONS contd.

	<u>Page</u>
Section 3 - Force Account Payment	44
3.1 Labor Surcharge	
3.2 Equipment Rental	
Section 4 - Protection of Existing Utilities	44
4.1 General	
4.2 Cooperation with Utilities Relocated by Others	
Section 5 - Project Site Maintenance	45
Section 6 - Special Requirements	45
6.1 National Pollutant Discharge Elimination System (NPDES)	
6.2 Sanitation	
6.3 Heavy Equipment Working Hours	
6.4 Encroachment Permits	
6.5 Toxic Material Disposal	
6.6 Survey Crew	
6.7 Survey Monuments	
6.8 Job Trailer Site	
6.9 Construction Tolerances	
6.10 Surplus Excavated Material	
6.11 Sewer Line Inspection	
6.12 Project Signs	
6.13 Liability Insurance	
6.14 Accidental Discovery	
6.15 Nesting Bird Pre-Construction Survey	
Section 7 and Section 8 – Not Used	50
Section 9 - Payment	50

DETAILED SPECIFICATIONS

Section 10 - Mobilization	51
10.1 Description	
10.2 Payment	
Section 11 - Water Control	51
11.1 Description	
11.2 Water Control	
11.3 Measurement and Payment	

TABLE OF CONTENTS - CONTD.

DETAILED SPECIFICATIONS contd.

	<u>Page</u>
Section 12 - Traffic Control	52
12.1 Description	
12.2 Notification of Agencies	
12.3 Public Convenience and Access	
12.4 Construction Signs and Traffic Control Plans	
12.5 Flaggers	
12.6 Payment	
Section 13 - Clearing and Miscellaneous Work	54
13.1 Description	
13.2 Clearing and Miscellaneous Work	
13.3 Payment	
Section 14 - Earthwork	55
14.1 Description	
14.2 General Excavation Requirements	
14.3 Excavation	
14.4 Street Reconstruction	
14.5 General Backfill Requirements	
14.6 Testing	
14.7 Backfill	
14.8 Measurement	
14.9 Payment	
Section 15 - Not Used	58
Section 16 - Concrete Construction	58
16.1 Description	
16.2 General Requirements	
16.3 Material and Methods	
16.4 General Reinforcing Steel Requirements	
16.5 Consistency	
16.6 Placing	
16.7 Form Removal and Finish	
16.8 Curing	
16.9 Joints	
16.10 Use of the Concrete Swale Invert	
16.11 Class "A" Concrete, Retaining Wall	
16.12 Class "A" Concrete, Concrete Swale	

TABLE OF CONTENTS - CONTD.

DETAILED SPECIFICATIONS contd.

	<u>Page</u>
16.13 Class "B" Concrete, 2' Cutoff Wall	
16.14 Class "B" Concrete, Miscellaneous	
16.15 Measurement	
16.16 Payment	
Section 17 and Section 18 – Not Used	64
Section 19 - Flexible Pavement Construction	64
19.1 Description	
19.2 Aggregate Base, Class 2	
19.3 General Hot Mix Asphalt (HMA) Requirements	
19.4 Hot Mix Asphalt (HMA) Aggregate	
19.5 Asphalt Binder	
19.6 Hot Mix Asphalt (HMA) Prime Coat	
19.7 Hot Mix Asphalt (HMA) Paint Binder/Tack Coat	
19.8 Hot Mix Asphalt (HMA) Placement	
19.9 Hot Mix Asphalt (HMA)	
19.10 Measurement	
19.11 Payment	
Section 20 - Fences and Gates	69
20.1 Description	
20.2 Modified 6-Foot Chain Link Fence	
20.3 Temporary Fencing	
20.4 Modified 14-Foot Double Drive Gates	
20.5 Measurement	
20.6 Payment	
Section 21 - Miscellaneous	70
21.1 Description	
21.2 4'W x 1.5'H Grated Trench Drain	
21.3 Midwest Guardrail System	
21.4 Adjust Manhole to Grade	
21.5 Extra Directed Work	
21.6 Measurement	
21.7 Payment	
Section 22 through Section 25 – Not Used	72

TABLE OF CONTENTS - CONTD.

DETAILED SPECIFICATIONS contd.

	<u>Page</u>
Section 26 - Stonework	72
26.1 Description	
26.2 General	
26.3 Rock Slope Protection, Class I (20-lb)	
26.4 Crushed Rock	
26.5 Rock Slope Protection Fabric	
26.6 Measurement	
26.7 Payment	
Section 27 - Dust Abatement	73
27.1 Description	
27.2 Dust Abatement	
27.3 Payment	
Section 28 - Not Used	74
Section 29 - Stormwater and Non-Stormwater Pollution Control	74
29.1 Description	
29.2 General	
29.3 Pollution Prevention Plan Preparation (PPP) and Approval	
29.4 PPP Amendments	
29.5 PPP Implementation	
29.6 Non-Stormwater Discharge or Dewatering	
29.7 Payment	
Section 30 and Section 31 - Not Used	77
Appendix "A" - South Coast Air Quality Management District Rule 403	78
Appendix "B" - Project Signs	79
Drawing No. 1-0731	Sheets 1 through 9

NOTICE INVITING BIDS TO CONTRACTORS

Riverside County Flood Control and Water Conservation District hereinafter called "District", invites sealed proposals for construction of:

**Jurupa-Pyrite MDP Line A-2, Stage 1
Project No. 1-0-00234-01
located in the city of Jurupa Valley
Riverside County, California**

On or after **October 22, 2019**, Specifications and Contract Documents may be examined at the District's office at 1995 Market Street, Riverside, California, and may be obtained upon payment to District of **\$60.00** per set, received at the District's office and **\$65.00** per set if mailed. The Specifications and Contract Documents are also offered on CD-ROM for \$10.00 received at the District's office and \$15.00 if mailed. No refund.

Each proposal must be accompanied by a bid security in the form of a certified check, cashier's check or bid bond equal to ten percent (10%) of the amount bid, payable to the Riverside County Flood Control and Water Conservation District as a guarantee that the Contractor will, if awarded the contract, execute a satisfactory contract and furnish the required bonds and proof of insurance.

Bid Proposals must be placed in a sealed envelope clearly marked "Bid Proposal". Bid Proposals must be in accordance with the instructions and other Contract Documents and filed with the District by **2:00 p.m. on Thursday, November 21, 2019** at 1995 Market Street, Riverside, California, which time and place are fixed for the public opening of bids.

Any questions, requests for information and requests for clarification or interpretation of the Specifications must be submitted in writing to the District attention:

Christian Portillo
Email: cportill@rivco.org
OR
Hard Copy: Riverside County Flood Control and Water Conservation District
1995 Market Street, Riverside, CA 92501
Attn: Christian Portillo

Questions or requests must be received **no later than 5:00 p.m. on Tuesday, November 12, 2019.**

Pursuant to Labor Code Section 1771.1, any Contractor bidding and subcontractors to be listed on a Bid Proposal are subject to Public Contract Code Section 4104 and shall not be eligible to bid unless currently registered with the Department of Industrial Relations and qualified to perform public works pursuant to Labor Code Section 1725.5. No Contractor or subcontractor may be awarded a public works project or enter into a Contract without proof of current registration to perform public works.

General prevailing rate of per diem wages and general prevailing rate of per diem wages for holiday and overtime work, including employer payments for health and welfare, pension, vacation, apprentices and similar purposes for each craft, classification or type of workman needed for execution of

contracts under the jurisdiction of District have been obtained by the Board of Supervisors of the District from the Director of Industrial Relations of the State of California for the area where the work is to be done. The said determinations are on file in the principal office of the District, and will be made available to any interested person upon request.

THIS PROJECT IS SUBJECT TO COMPLIANCE MONITORING AND ENFORCEMENT BY THE DEPARTMENT OF INDUSTRIAL RELATIONS. The awarded prime Contractor shall post job site notices, including a copy of the prevailing rate of per diem wages determinations made by the Director for the Department of Industrial Relations and other notices prescribed by regulations and comply with the provisions of the California Labor Code, including, without limitation, Sections 1771.4, 1773.1, 1773.2, 1774, 1775, 1776, and 1777.5.

Contractor shall furnish the records specified in Labor Code Section 1776, including but limited to the certified payroll records, directly to the Labor Commissioner for the Department of Industrial Relations.

Substitution of securities for any moneys withheld by District shall be permitted as provided for by Section 22300 of the California Public Contract Code.

Contractors submitting proposals for this project shall have an active and in good standing Class "A" Contractor's license from the State of California in order to be considered eligible for the contract award. The license(s) shall remain active and in good standing throughout the entire duration of the project.


With the submittal of the Bid Proposal, the Contractor shall submit for approval by the District documented evidence of satisfaction of all of the Bidder Qualifications listed above. As part of this submittal, Experience Statement shall be completed indicating at a minimum, the name, address, and phone number of the project owner and owner's representative, the location of the project, the amount of material installed, and completion date.

Dated: October 22, 2019

RIVERSIDE COUNTY FLOOD CONTROL
AND WATER CONSERVATION DISTRICT

KECIA HARPER
Clerk of the Board

BY


Deputy

INSTRUCTIONS TO BIDDERS

ARTICLE 1 GENERAL CONDITIONS

1.1 DEFINITIONS

Capitalized terms used on the Contract Documents shall have the meanings assigned to them in the Construction Agreement, Bonds, other Forms, General Provisions, and Specifications and Contract Documents that are included in the Contract Documents. Capitalized terms not so defined shall have the meanings assigned to them in, or if none is assigned as reasonably interpreted according to the context of, the portion of the Contract Documents where such terms are used.

1.2 QUANTITIES

The amount of work to be done or materials to be furnished under the contract as noted in the proposal, are but estimates and are not to be taken as an expressed or implied statement that the actual amount of work or materials will correspond to the estimate.

The right is reserved to increase or decrease or to entirely eliminate certain items from the work or materials if found desirable or expedient.

The Contractor will be allowed no claims for anticipated profits, loss of profits or for any damages of any sort because of any difference between the estimated and the actual amounts of work done, or materials furnished or used in the completed project.

The Contractor is cautioned against unbalancing of his bid by prorating his overhead into one or two items only when there are a number of items on the schedule. The overhead and indirect charges should be prorated on all items in schedule.

1.3 AGREEMENT OF FIGURES

If the unit prices and the total amounts named by the bidder in the proposal do not agree, the unit prices alone will be considered as representing the bidder's intention.

1.4 "OR EQUAL"

Pursuant to Division 2, Chapter 3, Article 5, commencing at Section 3400 of the Public Contract Code, all specifications shall be deemed to include the words "or equal", provided, however, that permissible exceptions or other requirements shall be specifically noted in the specifications. Any "equal" proposed by the Contractor must be described in the Contractor's Proposal.

1.5 INSPECTION OF SITE

Bidders must examine the site and acquaint themselves with all conditions affecting the work.

Information derived from maps, plans or specifications, or from the Chief Engineer or his assistants, will not relieve the successful bidder from properly carrying out all the terms of the written contract.

By the submitting of a proposal, the bidder will be held to have personally examined the site and the drawings, to have carefully read the specifications and to have satisfied himself as to his ability to meet all the difficulties attending the execution of the proposed contract before the delivery of his proposal and agrees that if he is awarded the contract, he will make no claim against the District and the County of Riverside, (including their respective officers, districts, special districts and departments, their respective directors, officers, Board of Supervisors, elected and appointed officials, employees, agents and representatives) based on ignorance or misunderstanding of the contract provisions.

1.6 QUALIFICATIONS OF BIDDERS

No proposal will be accepted from a Contractor who is not licensed under laws of California, as evidenced by the submittal of the Statement of Licensure. No award will be made to any bidder who cannot give satisfactory assurance to the District as to his own ability to carry out the contract, both from his financial standing and by reason of his previous experience as a Contractor on work of the nature contemplated in the contract. The bidder is required to submit his record of work of similar nature to that proposed under these specifications, and unfamiliarity with the type of work may be sufficient cause for rejection of a proposal.

A bid shall be rejected and a bidder shall be disqualified to bid on a District project if the bidder or any officer, manager, partner or shareholder of the bidder within the eighteen month period prior to the bid date shall have been an officer or employee of the District.

1.7 CONTRACTOR REGISTRATION

In accordance with the Labor Code (especially Sections 1725.5 and 1771.1), prior to submitting a proposal to District, all Contractors and Subcontractors must register as a "Public Works Contractor" with the Department of Industrial Relations (DIR) using the online application. Contractor's and Subcontractor's DIR Registration Number must be listed in the appropriate space on Contractor's Proposal form. This project is subject to compliance monitoring and enforcement by the DIR.

1.8 BALANCE BID

The Contractor is cautioned against unbalancing of its Bid by including its overhead and profit into one or two items only when there are a number of items on the schedule. The overhead and indirect charges should be prorated on all items in the schedule.

1.9 ANTI-DISCRIMINATION

It is the policy of the District that, in connection with all work performed under the Construction Agreement, there be no discrimination against any prospective or active employee engaged in the Work because of race, color, ancestry, national origin, religious creed, sex, age, marital status, or sexual preference. The Contractor agrees to comply with applicable Federal and California laws including, but not limited to, the California Fair Employment Practice Act, beginning with Labor Code Section 1410, and Labor Code Section 1735. In addition, the Contractor agrees to require like compliance by any subcontractors employed on the Work.

1.10 REQUIRED SUBMITTALS

There are a number of forms and other documents required as submittals by the Bidder during the various stages of the project. The following table provides a checklist of submittals required by the Bidder as requested in the Contract Documents. Bidders shall be made aware that the documents listed in the following table do not guarantee a complete submittal package.

	BID DOCUMENT	SUBMITTAL TIMEFRAME
<input type="checkbox"/>	Contractor's Proposal	with Bid Proposal
<input type="checkbox"/>	List of Subcontractors	with Bid Proposal
<input type="checkbox"/>	Experience Statement (Minimum of 5 References)	with Bid Proposal
<input type="checkbox"/>	Statement of Licensure	with Bid Proposal
<input type="checkbox"/>	Non-Collusion Declaration	with Bid Proposal
<input type="checkbox"/>	Iran Contracting Act Certification	with Bid Proposal
<input type="checkbox"/>	Bid Bond (10% of Contract Price)	with Bid Proposal
<input type="checkbox"/>	Construction Agreement	within 7 days of Notice of Intent to Award
<input type="checkbox"/>	Performance Bond (100% of Contract Price)	within 7 days of Notice of Intent to Award
<input type="checkbox"/>	Payment Bond (100% of Contract Price)	within 7 days of Notice of Intent to Award
<input type="checkbox"/>	Workers' Compensation Contractor Certificate	within 7 days of Notice of Intent to Award
<input type="checkbox"/>	Declaration of Sufficiency of Funds	within 7 days of Notice of Intent to Award
<input type="checkbox"/>	Certificates of Insurance	within 7 days of Notice of Intent to Award
<input type="checkbox"/>	Construction Schedule	within 14 days of Notice of Intent to Award
<input type="checkbox"/>	Affirmative Action Compliance Program (for Contractors with 50+ Employees)	within 30 days of Award of Contract

**ARTICLE 2
BIDDING PROCEDURES**

2.1 PROPOSAL FORMS

Attention of all bidders is called to all bid proposal forms attached hereto. Bidders are cautioned that all bid proposals submitted must be accompanied by all forms properly executed.

2.2 SUBMISSION OF BID PROPOSALS

All copies of the Contractor's Proposal, Bid Security, and other Bid Proposal Submittals shall be enclosed by the Bidder in a sealed opaque envelope. Said envelope, as well as any other, outer envelope or packaging in which said envelope may have been placed by Bidder or the carrier for delivery, shall be addressed and delivered as provided in the Notice Inviting Bids to Contractors.

2.3 TIMELY RECEIPT

The Bidder assumes full and sole responsibility for timely receipt of its Bid Proposal, including its Bid Security and all other Bid Submittals, at the location designated in the Notice Inviting Bids to Contractors.

2.4 DELIVERY METHOD OF BID PROPOSAL

Submittal of Bid Proposals shall be by hand delivery or mail, only. Oral, telephonic, telegraphic, facsimile or other electronic transmission is not permitted.

2.5 INVALID BID PROPOSALS

Bid Proposals submitted by fax or e-mail and those which fail to reach the place fixed for opening of Bid Proposals prior to the date and hour set for opening same will not be considered.

2.6 BID SECURITY:

Bid Security. Each Bid shall be accompanied by a Bid Security in the form of 1) cash, 2) a certified or cashier's check made payable to the Riverside County Flood Control and Water Conservation District, or 3) a Bid Bond (using the form of Bid Bond included in the Bidding Documents) issued by an Admitted Surety, in an amount equal to at least ten percent (10%) of the Bid Amount, as a guarantee that the Bidder, if awarded the Construction Contract, will enter into a Construction Contract with the District and furnish the Performance Bond, Payment Bond and other Post-Award Submittals required by the Bidding Documents. Should the Bidder refuse to enter into the Construction Contract or fail to furnish the Performance Bond, Payment Bond or any other Post-Award Submittals within the required timeframes as applicable, then the Bid Security shall be forfeited to the District in an amount equal to the difference between the amount of Bidder's Bid Amount and the amount for which the District may procure the work from another Bidder plus the costs to the District of redrafting, redrawing and republishing the Bidding Documents.

Retention by District. The District will have the right to retain the Bid Security of any Bidder to whom an Award is being considered until either (1) the Construction Contract has been executed and the Performance Bond, Payment Bond and other Post-Award Submittals have been furnished, or (2) all Bids have been rejected.

Return of Proposal Guarantees. Within ten (10) days after the award of the contract, the District will return the proposal guarantees accompanying such of the proposals as are not considered in making the award. All other proposal guarantees will be held until the contract has been fully executed, after which they will be returned to the respective bidders whose proposal they accompany.

2.7 SUBLETTING AND SUBCONTRACTING

Bidders are required, pursuant to the Subletting and Subcontracting Fair Practices Act (commencing with Section 4100 of the Public Contract Code) to list in their proposal the name and location of place of business of each subcontractor who will perform work or labor or render services in or about the construction of the work or improvement or a subcontractor who specially fabricates and installs a portion of the work or improvement according to detailed drawings contained in the Plans and Specifications, in excess of one-half (½) of one percent (1%) of the prime Contractor's total bid. Failure to list a subcontractor for a portion of the work means that the prime Contractor will do that portion of the work. Contractor shall list only one subcontractor for each portion as is defined by the Contractor in the Contractor's Bid Proposal.

2.8 DISCREPANCIES AND OMISSIONS

Discrepancies, omissions, ambiguities, or requirements likely to cause disputes between trades and similar matters shall be promptly brought to the attention of the Engineer. When appropriate, Addenda will be issued by the District. No communication by anyone as to such matters except by an Addendum affects the meaning or requirements of the Contract Documents.

2.9 ADDENDA

Interpretations, corrections, clarifications and changes to the Contract Documents will be made by Addenda. District reserves the right to issue Addenda to the Contract Documents at any time prior to the time set to open bids. Each potential bidder shall leave with the District its name and address for the purpose of receiving Addenda. District will cause copies of Addenda to be mailed or delivered to such names at such addresses. To be considered, a Contractor's proposal must list and take into account all issued Addenda.

Addenda will be transmitted by District to all prospective Bidders who (1) attended and signed in at the Mandatory Pre-Bid Site Review meeting (if any); (2) are plan holders; or (3) have submitted a written request to District for notice of Addenda at Riverside County Flood Control, 1995 Market Street, Riverside, CA 92501, including in such request the Bidder's name and address for mailing. Each potential Bidder shall leave with the District its name, address, email, and fax number for the purpose of receiving Addenda. To be considered, a Contractor's Proposal must list and take into account all issued Addenda. Failure of the Bidder to receive any Addendum shall not relieve the Bidder from any of its obligations under its Contractor's Proposal. The costs of performance by Bidder of all items of Work and other obligations contained in all Addenda issued by the District shall be deemed included in the amount of the

Contractor's Proposal. The Bidder shall identify and list in its Contractor's Proposal all Addenda received and included by the District as a basis for determining its Bid Proposal non-responsive.

2.10 RESPONSE TO QUESTIONS

Any questions or requests for information must be submitted in writing to the District attention:

Christian Portillo

Email: cportill@rivco.org

OR

Hard Copy: Riverside County Flood Control and Water Conservation District

1995 Market Street, Riverside, CA 92501

Attn: Christian Portillo

Questions or requests must be received **no later than 5:00 p.m. on Tuesday, November 12, 2019.**

2.11 POSTPONEMENT

The District reserves the right to postpone the time and date for the public opening of bids as specified in the Notice Inviting Bids to Contractors by issuance of an Addendum to the Contract Documents at any time prior to the specified time and date for public opening of bids.

2.12 REJECTION OF BID PROPOSALS CONTAINING ALTERATIONS, ERASURES OR IRREGULARITIES

Bid Proposals may be rejected if they show any alterations of form, additions not called for, conditional Bid Proposals, incomplete Bid Proposals, erasures, or irregularities of any kind. Erasures or interlineations in the Bid Proposal must be explained or noted over the signature of the Bidder. The District may determine as unresponsive any Bid Proposal in which any statement or representation made or incorporated by reference in the Contractor's Proposal, including any Bid submittal comprising the Bid Proposal, is false, incorrect or materially incomplete and misleading.

2.13 DISQUALIFICATION OF BIDDERS

More than one proposal from an individual, a firm or partnership, a corporation or an association under the same or different names will not be considered. Reasonable ground for believing that any bidder is interested in more than one proposal for the work contemplated will cause the rejection of all proposals in which such bidder is interested. If there is any reason for believing that collusion exists among the bidders, none of the participants in such collusion will be considered in awarding the contract. Proposals in which the prices obviously are unbalanced may be rejected.

2.14 WITHDRAWAL OF PROPOSALS

Any proposal may be withdrawn at any time prior to the hour fixed in the Notice to Contractors for the opening of proposals, provided that a request in writing, executed by the bidder or his duly authorized representative, for the withdrawal of such proposal, is filed with the Chief Engineer. The withdrawal of a proposal shall not prejudice the right of a bidder to file a new proposal.

2.15 IRAN CONTRACTING ACT

In accordance with Public Contract Code Section 2204(a), prior to bidding on, submitting a proposal or executing a contract or renewal for a District contract for goods or services of \$1,000,000 or more, a Contractor must either:

- a) Certify it is not on the current list of persons engaged in investment activities in Iran created by the California Department of General Services ("DGS") pursuant to Public Contract Code Section 2203(b) and is not a financial institution extending twenty million dollars (\$20,000,000) or more in credit to another person, for 45 days or more, if that other person will use the credit to provide goods or services in the energy sector in Iran and is identified on the current list of persons engaged in investment activities in Iran created by DGS; or
- b) Demonstrate it has been exempted from the certification requirement for that solicitation or contract pursuant to Public Contract Code Section 2203(c) or (d).

To comply with this requirement, please insert your Contractor or financial institution name and Federal ID Number (if available) and complete one of the options on Page XXII. Please note: California law establishes penalties for providing false certifications, including civil penalties equal to the greater of \$250,000 or twice the amount of the contract for which the false certification was made; contract termination; and three-year ineligibility to bid on contracts. (Public Contract Code section 2205.)

2.16 PUBLIC OPENING OF PROPOSALS

Proposals will be opened and read publicly at the time and place indicated in the Notice Inviting Bids to Contractors. Bidders or their authorized agents are invited to be present.

ARTICLE 3 CONSIDERATION OF BIDS

3.1 BASIS OF AWARD

The award of the Contract, if it be awarded, will be to the lowest responsible and qualified Bidder based upon all Bid items.

3.2 NOTICE OF INTENT TO AWARD

Within thirty (30) days following public opening and reading of Bids, the District will issue a Notice of Intent to Award identifying the name of the Bidder to whom the District intends to Award the Construction Contract. Such notice will be mailed to all Bidders submitting a Bid Proposal. The District may, in its sole and absolute discretion, elect to extend the time for its issuance of its Notice of Intent to Award.

3.3 BID PROTESTS

Any Bidder submitting a Bid Proposal to the District may file a protest of the District's proposed Award of the Construction Contract provided that each and all of the following are complied with:

1. The bid protest is in writing.

- X -

2. The bid protest is both: (1) filed with and received by David Garcia at the following address, 1995 Market Street, Riverside, California, not more than five (5) days following the date of issuance of the Notice of Intent to Award. Failure to timely file and serve the bid protest as afore stated shall constitute grounds for the District's denial of the bid protest without consideration of the grounds stated therein.
3. The written bid protest sets forth, in detail, all grounds for the bid protest, including without limitation all facts, supporting documentation, legal authorities and argument in support of the grounds for the bid protest. Any grounds not set forth in the bid protest shall be deemed waived. All factual contentions must be supported by competent, admissible and credible evidence. Any bid protest not conforming to the foregoing shall be rejected as invalid.
4. Provided that a bid protest is filed in conformity with the foregoing, the General Manager-Chief Engineer, or such individual(s) as may be designated by the General Manager-Chief Engineer in his/her discretion, shall review and evaluate the basis of the bid protest, and shall provide a written decision to the Bidder submitting the bid protest, either concurring with or denying the bid protest. The written decision of the General Manager-Chief Engineer or his/her designee shall be final, unless overturned by the Board of Supervisors.
5. An inadvertent error in listing the California contractor license number or DIR public works contractor registration number for a subcontractor shall not be grounds for filing a bid protest or grounds for considering the bid nonresponsive if the corrected number is submitted to the District within 24 hours after the bid opening and provided the corrected number corresponds to the submitted name and location for that subcontractor.

3.4 AWARD OF CONTRACT

The right is reserved to reject any and all proposals and to waive technical defects as the best interests of the District may require. The award of the Contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with the requirements prescribed. The award, if made, will be made within sixty (60) days after the opening of the proposals. All proposals will be compared on the basis of the Engineer's estimate of the quantities of work to be done.

ARTICLE 4 POST-NOTICE OF INTENT TO AWARD

4.1 POST-NOTICE OF INTENT TO AWARD SUBMITTALS

Within the time periods set forth below, the successful Bidder identified in the Notice of Intent to Award as the successful Bidder shall submit the following additional Post-Notice of Intent to Award submittals, completed and signed in the manner required by the Contract Documents, to the District at 1995 Market Street, Riverside, California 92501:

- 4.1.1 Within **seven (7) days** after issuance by District to Bidder of the Notice of Intent to Award and prior to contract award, such Bidder shall submit to the District the following:

- (1) Construction Agreement duly executed by the authorized delegate of the Contractor;
- (2) Performance Bond and Payment Bond (issued by Surety), as set forth in Section 4.2 below;
- (3) Evidence of Insurance, as specified by the Contract Documents;
- (4) Workers' Compensation Certificate, in the form specified by the Contract Documents; and
- (5) Declaration of Sufficiency of Funds (required only if the Bidder has not entered into a collective bargaining agreement covering the workers to be employed for performance of the Work), in the form specified by the Contract Documents.

4.1.2 Within **fourteen (14) days** after issuance by District to Bidder of the Notice of Intent to Award and prior to commencement of the Work, such Bidder shall submit to the District the following:

- (1) Construction Schedule, prepared by Bidder in the manner required by Section 2.02 of the General Provisions

4.2 **CONTRACT SECURITY – PERFORMANCE BOND AND PAYMENT BOND**

The Contractor shall furnish two (2) surety bonds, each in quadruplicate, one as a security for the faithful performance of the contract in the amount equal to one hundred percent (100%) of the contract price, and one as security for the payment of all persons performing labor and furnishing materials in connection with the contract in an amount equal to one hundred percent (100%) of the Contract Price. The penal sums of the Performance Bond and Payment Bond shall each be initially in the amount of one hundred percent (100%) of the Contract Price. The penal sum may be required to be increased for Contract Adjustments increasing the Contract Price that are authorized by Change Order. All bonds must be submitted on forms provided by the District. Bonds submitted in any other form will not be accepted.

Prior to the execution of the Contract, the Contractor shall furnish to the District the required, original, Performance and Payment Bonds, issued by an admitted surety and shall have a A.M. Best's Insurance Rating of A VIII (A:8) or better rated surety company, authorized to do business in the State of California. The Bonds shall be executed by an authorized attorney-in-fact for the Surety company and his/her original or certified copy Power of Attorney must be attached to the Bonds. Premiums for Bonds shall be paid by the Contractor. Notary acknowledgements of the signatures of the Contractor and Surety(ies) is required. The attorney-in-fact who executes the required Performance Bond and Payment Bond on behalf of the Surety shall affix thereto a certified and current copy of the Power of Attorney authorizing such attorney-in-fact to execute same on behalf of such Surety. Should any Surety on the Performance Bond or Payment Bond be deemed unsatisfactory by the District, Contractor shall upon notice promptly substitute new bonds satisfactory to the District.

If the Performance Bond provides for a one-year warranty, a separate Maintenance Bond is not necessary. If the warranty period specified in the contract is for longer than one year, a Maintenance Bond equal to ten percent (10%) of the contract price is required. Bonds shall be duly executed by a responsible corporate surety, authorized to issue such bonds in the State of California and secured through an authorized agent with an office in California.

4.3 FORFEITURE FOR FAILURE TO POST SECURITY AND EXECUTE AGREEMENT

In the event the Bidder, to whom an award will be made, fails or refuses to post the required bonds and provide the required certificates of insurance and fails to return executed copies of the Construction Agreement within seven (7) days after the prescribed forms are presented to it for signature, the District may declare the Bidder's Bid deposit or bond forfeited as damages caused by the failure of the Bidder to post such security and execute such copies of the Construction Agreement and may award the Work to the next lowest responsible Bidder, or may call for new bids.

CONTRACTOR'S PROPOSAL

TO THE BOARD OF SUPERVISORS OF THE RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT:

The undersigned hereby declare(s):

- (a) That the only persons or parties interested in this proposal as principals are the following:

Name of Company (and dba if applicable) ("Contractor"): _____

Southwest General Engineering

(If the Contractor is a corporation, give the name of the corporation and the name of its president, secretary, treasurer, and manager. If a copartnership, give the name under which the copartnership does business, and the names and addresses of all copartners. If an individual, state the name and address under which the contract is to be drawn.)

- (b) That this proposal is made without collusion with any other person, firm or corporation.
- (c) That he has carefully examined the location of the proposed work, and has familiarized himself with all of the physical and climatic conditions, and makes his proposal solely upon his own knowledge.
- (d) That he has carefully examined the attached specifications as referred to, and the plans, and makes this proposal in accordance therewith.
- (e) That, if this proposal is accepted, he will enter into a written contract with the Riverside County Flood Control and Water Conservation District, Riverside, State of California.
- (f) That he proposes to enter into such contract and to accept in full payment for the work actually done thereunder the prices shown in the attached schedule. It is understood and agreed that the quantities set forth are but estimates, and that the unit prices will apply to the actual quantities whatever they may be, subject to such adjustments and alterations as elsewhere provided for in the Contract Documents.

As bid security, accompanying this proposal is a certified or cashier's check or bid bond payable to the order of the Riverside County Flood Control and Water Conservation District, Riverside, California, in the sum of

at least ten percent (10%) of the Dollars (\$ _____)
bid amount

**THE REQUIRED REFERENCES AND OTHER REQUIRED DOCUMENTS
MUST BE ATTACHED TO THIS BID PROPOSAL**

It is understood and agreed that should the Contractor within seven (7) days after the prescribed forms are presented to him for signature fail to return the contract and furnish acceptable surety bond and insurance, then, at the discretion of the District, the proceeds of said check shall become the property of the District, the Contractor shall be found in default and the project may be awarded to another contractor. The bid bond or check shall be held subject to payment to the District of the difference in money between the amount of the contract with another party to perform the work, together with the cost to the District of redrafting, redrawing and publishing documents and papers necessary to obtain new bids on said work. The bid bond or check shall, in addition, be held subject to all other actual damages suffered by the District. But if the contract is entered into and said bonds and insurance are furnished, or if the proposal is not accepted, then the said check shall be returned to the undersigned.

RECEIVED

NOV 21 2019
9:00 am
RIVERSIDE COUNTY FLOOD CONTROL
AND WATER CONSERVATION DISTRICT

Southwest General Engineering

PROPOSAL

For the Construction of **Jurupa-Pyrite MDP Line A-2, Stage 1**, located in the city of Jurupa Valley, Riverside County, consisting of the following estimated quantities:

SECT. NO.	ITEM NO.	ITEM OF WORK	UNIT	QUANTITY	UNIT COST	TOTAL COST
10	1.	Mobilization	L.S.	---	---	\$4,670-
11	2.	Water Control	L.S.	---	---	\$8,310-
12	3.	Traffic Control	L.S.	---	---	\$11,200-
13	4.	Clearing and Miscellaneous Work	L.S.	---	---	\$39,000-
14	5.	Excavation	C.Y.	507	\$44.60	\$22,612.50
14	6.	Street Reconstruction	C.Y.	167	\$57.70	\$9,635.90
14	7.	Backfill	C.Y.	15	\$168-	\$2,520-
16	8.	Class "A" Concrete, Retaining Wall	C.Y.	7	\$1345-	\$9,415-
16	9.	Class "A" Concrete, Concrete Swale	C.Y.	91	\$405-	\$36,855-
16	10.	Class "B" Concrete, 2' Cutoff Wall	L.F.	983	\$15.70	\$15,433.10
16	11.	Class "B" Concrete, Miscellaneous	C.Y.	3	\$2,270-	\$6,810-
19	12.	Aggregate Base, Class 2	C.Y.	73	\$154-	\$11,242-
19	13.	Hot Mix Asphalt (HMA)	TONS	94	\$138-	\$12,972-
20	14.	Modified 6-Foot Chain Link Fence	L.F.	500	\$61.50	\$30,750-
20	15.	Temporary Fencing	L.F.	197	\$14.80	\$2,915.60
20	16.	Modified 14-Foot Double Drive Gates	PAIR	1	\$3,420-	\$3,420-
21	17.	4'W x 1.5'H Grated Trench Drain	L.F.	56	\$1,485-	\$83,160-
21	18.	Midwest Guardrail System	L.F.	35	\$48.50	\$1,697.50
21	19.	Adjust Manhole to Grade	EACH	1	\$1,455-	\$1,455-
21	20.	Extra Directed Work	L.S.	---	---	10,000.00

PROPOSAL contd.

SECT. NO.	ITEM NO.	ITEM OF WORK	UNIT	QUANTITY	UNIT COST	TOTAL COST
26	21.	Rock Slope Protection, Class I (20-lb)	C.Y.	6	\$181-	\$1,086-
26	22.	Crushed Rock	C.Y.	66	\$73.20	\$4,831.20
26	23.	Rock Slope Protection Fabric	S.Y.	17	\$20.70	\$351.90
27	24.	Dust Abatement	L.S.	---	---	\$2,445-
29	25.	Stormwater and Non-Stormwater Pollution Control	L.S.	---	---	\$15,850-

For the Total Bid Proposal of:

TOTAL COST

(State in Figures)

\$ 350,637.40

Southwest
General Engineering
Name of Contractor

[Signature]
Signature of Contractor's authorized representative

Name: Bob Shepherd

Title: President

3625 Placentia Lane
Address

33-0825029
S.S.N. or E.I.N.

Riverside, CA 92501
City, State, Zip

A 762752
Contractor's License No. and Classification


(951) 781-4303 (951) 781-2774
Telephone Number Fax Number

1000004413
Contractor's DIR Registration No.

keith@swvditch.com
Email

If bidder is a corporation, corporate seal and attestation shall be provided below.

Dated: Nov 21, 2019



LIST OF SUBCONTRACTORS

Contractor Southwest General Engineering

Jurupa-Pyrite MDP Line A-2, Stage 1
Project No. 1-0-00234-01

Give the name and the location of the place of business of each Subcontractor who will perform work or labor or render service to the General Contractor in or about the construction of the work or improvement, or a Subcontractor who specially fabricates and installs a portion of the work or improvement, in an amount in excess of one-half (1/2) of one percent (1%) of the General Contractor's total bid. List the bid item numbers of the work each subcontractor will do. If a portion of an item is to be subcontracted, show what percentage of that item is to be subcontracted.

Item No. (s) None

Name of Subcontractor _____

Address/City/Phone _____

License No. _____ Subcontractor's DIR Registration No. _____

Item No. (s) _____

Name of Subcontractor _____

Address/City/Phone _____

License No. _____ Subcontractor's DIR Registration No. _____

Item No. (s) _____

Name of Subcontractor _____

Address/City/Phone _____

License No. _____ Subcontractor's DIR Registration No. _____

Item No. (s) _____

Name of Subcontractor _____

Address/City/Phone _____

License No. _____ Subcontractor's DIR Registration No. _____

Item No. (s) _____

Name of Subcontractor _____

Address/City/Phone _____

License No. _____ Subcontractor's DIR Registration No. _____

EXPERIENCE STATEMENT

Bidder submits, as part of his bid, the following statements as to his experience qualifications. Bidder certifies that all statements and information set forth below are true and accurate. Bidder hereby authorizes the District to make inquiry as appropriate regarding his experience.

Bidder has been engaged in the contracting business under this present business name for 20 years.

Bidder's experience in work of a nature similar in type and magnitude to that set forth in the Specification extends over a period of 33 years.

Within the last three years, Bidder has satisfactorily completed the following contracts covering work similar in type and magnitude to that set forth in these Specifications for the following owners (name person, firms, or authorities):

Name and Address of Owner/Agency	Representative and Telephone	Type of Work, Year Completed and Dollar Amount
Casitas Municipal Water District Oak View, CA	Sulia Aranda 805-649-2251	Canal Repair, 2019 \$97,250-
City of Grass Valley Grass Valley, CA	Bjorn Jones 530-615-7236	Culvert Lining, 2017 Shotcrete Tunnel \$398,045-
City of Victorville Victorville, CA	Brian Gengler 760-955-5000	Concrete Drainage Improvements, 2018 \$58,366-
Gage Canal Company Riverside, CA	Ross Lewis 951-780-1333	Shotcrete Overlay Existing Canal, 2018 \$59,675

STATEMENT OF LICENSURE

Pursuant to California Public Contract Code §3300, the undersigned does certify as follows:

1. That the pocket license/certificate of licensure I have presented to owner as of this date is my own license, being State of California, Contractors License No. 762752 and
2. That said Contractors License is current and valid; and
3. That said Contractors License is of a classification appropriate to the work to be undertaken for owner, a Class A license.

I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct.

DATED: Nov 21, 2019

Signature [Handwritten Signature]

Title President

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA) §
COUNTY OF RIVERSIDE)

On this the 21st day of November, 2019, before me

Jose Luis Hernandez, Notary Public
the undersigned Notary Public, personally appeared


Robert Shepherd

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument, and acknowledged that he/she executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Notary's Signature (Seal) [Handwritten Signature]



NON-COLLUSION DECLARATION

(Public Contract Code Section 7106)


The undersigned declares:

I am the President of Southwest General Engineering the party making the foregoing bid.

The bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation. The bid is genuine and not collusive or sham. The bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid. The bidder has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or to refrain from bidding. The bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder. All statements contained in the bid are true. The bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, to any corporation, partnership, company, association, organization, bid depository, or to any member or agent thereof, to effectuate a collusive or sham bid, and has not paid, and will not pay, any person or entity for such purpose.

Any person executing this declaration on behalf of a bidder that is a corporation, partnership, joint venture, limited liability company, limited liability partnership, or any other entity, hereby represents that he or she has full power to execute, and does execute, this declaration on behalf of the bidder.

I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct and that this declaration is executed on Nov 21, 2019 [date], at Riverside [city], CA [state].



[Signature of Declarant]

Bobo Shepherd

[Printed Name of Person Signing]

Southwest General Engineering

[Name of Bidder]

President

[Office or Title]

IRAN CONTRACTING ACT CERTIFICATION


In accordance with Public Contract Code Section 2204(a), prior to bidding on, submitting a proposal or executing a contract or renewal for a District contract for goods or services of \$1,000,000 or more, a Contractor must either:

- c) Certify it is not on the current list of persons engaged in investment activities in Iran created by the California Department of General Services ("DGS") pursuant to Public Contract Code Section 2203(b) and is not a financial institution extending twenty million dollars (\$20,000,000) or more in credit to another person, for 45 days or more, if that other person will use the credit to provide goods or services in the energy sector in Iran and is identified on the current list of persons engaged in investment activities in Iran created by DGS; or
- d) Demonstrate it has been exempted from the certification requirement for that solicitation or contract pursuant to Public Contract Code Section 2203(c) or (d).

To comply with this requirement, please insert your Contractor or financial institution name and Federal ID Number (if available) and complete one of the options below. Please note: California law establishes penalties for providing false certifications, including civil penalties equal to the greater of \$250,000 or twice the amount of the contract for which the false certification was made; contract termination; and three-year ineligibility to bid on contracts. (Public Contract Code Section 2205.)

Option #1 – Certification

I, the official named below, certify I am duly authorized to execute this certification on behalf of the Contractor/financial institution identified below, and the Contractor/financial institution identified below is **not** on the current list of persons engaged in investment activities in Iran created by DGS and is not a financial institution extending twenty million dollars (\$20,000,000) or more in credit to another person/vendor, for 45 days or more, if that other person/vendor will use the credit to provide goods or services in the energy sector in Iran and is identified on the current list of persons engaged in investment activities in Iran created by DGS.

<i>Contractor Name/Financial Institution (Printed)</i> Southwest General Engineering		<i>Federal ID Number (or n/a)</i> 33-0825029
<i>By (Authorized Signature)</i> 		
<i>Printed Name and Title of Person Signing</i> Bob Shepherd, President		
<i>Date Executed</i> Nov 21, 2019	<i>Executed in</i> Riverside, CA	

Option #2 – Exemption

Pursuant to Public Contract Code Sections 2203(c) and (d), a public entity may permit a Contractor/financial institution engaged in investment activities in Iran, on a case-by-case basis, to be eligible for, or to bid on, submit a proposal for, or enters into or renews, a contract for goods and services.

If you have obtained an exemption from the certification requirement under the Iran Contracting Act, please fill out the information below, and attach documentation demonstrating the exemption approval.

<i>Contractor Name/Financial Institution (Printed)</i>		<i>Federal ID Number (or n/a)</i>
<i>By (Authorized Signature)</i>		
<i>Printed Name and Title of Person Signing</i>		
<i>Date Executed</i>	<i>Executed in</i>	

BID BOND

Page 1 of 2

Recitals

1. The undersigned SOUTHWEST GENERAL ENGINEERING, INC. (Contractor), is herewith submitting to the Riverside County Flood Control and Water Conservation District (District), a Bid Proposal ("Proposal") dated NOVEMBER 21 2019, for the construction of public work for **Jurupa-Pyrite MDP Line A-2, Stage 1** in accordance with a Notice to Contractors dated October 22, 2019.
2. Contractor is obligated as a condition of said Bid to submit security in the amount of at least ten percent (10%) of the Bid Amount, which security may be in the form of a Bid Bond issued by an admitted surety insurer pursuant to Code of Civil Procedure Section 995.120 ("Admitted Surety").
3. THE OHIO CASUALTY INSURANCE COMPANY a NEW HAMPSHIRE corporation, hereafter called (Surety), is the surety on this Bid Bond.

Agreement

We, Contractor as principal and Surety as surety, jointly and severally agree and state as follows:

1. The amount of the obligation of this Bond is ten percent (10%) of the amount of the Contractor's Proposal and inures to the benefit of District.
2. This Bond is exonerated by (1) District rejecting said Proposal or, in the alternate, (2) if said Proposal is accepted, Contractor executes the Construction Agreement and furnishes the Performance Bond, Payment Bond and Insurance as agreed to in its Proposal, otherwise it remains in full force and effect for the recovery of loss, damage and expense of District resulting from failure of Contractor to act as agreed to in its Proposal. Some types of possible loss, damage and expense are specified in the Contractor's Proposal.
3. Surety for value received, stipulates and agrees that its obligations hereunder that no change, any extension of time within which District may accept the Proposal, alteration or addition to the terms of the Contract or the Bidding Documents, or to the work to be performed thereunder, nor any withdrawal of the Proposal in a manner not permitted by the requirements of the Bidding requirements shall in any way impair or affect Surety's obligation under this Bond, and Surety does hereby waive notice of any such changes, extension of time, alterations or additions.
4. This Bond is binding on our heirs, executors, administrators, successors and assigns.
5. In the event any legal proceeding or arbitration is brought upon this Bond by District and judgment or award is entered in favor of District as the prevailing party, Surety shall pay all costs and attorney's fees incurred by the District.

BID BOND
Page 2 of 2

IN WITNESS WHEREOF the undersigned parties have executed this instrument under their several seals this day of NOVEMBER 8, 20 19, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

Dated: NOVEMBER 8, 2019

SOUTHWEST GENERAL ENGINEERING, INC.
(Proper name of Contractor)

(Corporate Seal of Contractor,
if Corporation)

By: [Signature]
Signature of Contractor's authorized representative

Bodo Shepherd, President
Print or type authorized representative's Name and Title

3625 PLACENTIA LANE, RIVERSIDE, CA 92501
Print or type Contractor's Address

(Corporate Seal of Surety)

Surety THE OHIO CASUALTY INSURANCE COMPANY

By: [Signature]
Attorney-in-Fact, SPENCER FLAKE

(Attach Attorney-in-Fact
Certificate and Required
Acknowledgments)

CULBERTSON INSURANCE SERVICES, INC.
Name and Address of California Agent of Surety

5500 E. SANTA ANA CANYON RD., SUITE 201

ANAHEIM, CA 92807

(714) 921-0530
Telephone Number of California Agent of Surety

NOTE: Notary acknowledgment of signatures of Contractor and Surety, and Surety's Power of Attorney, must be included or attached.

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT


A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA

County of Orange

On 11/08/19 before me, Lexie Sherwood, Notary Public,
Date Insert Name of Notary exactly as it appears on the official seal

personally appeared Spencer Flake
Name(s) of Signer(s)



Place Notary Seal Above

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

Witness my hand and official seal.

Signature Lexie Sherwood
Signature of Notary Public Lexie Sherwood

OPTIONAL

Though the information below is not required by law, it may prove valuable to persons relying on the document and could prevent fraudulent removal and reattachment of the form to another document.

Description of Attached Document

Title or Type of Document: _____

Document Date: _____ Number of Pages: _____

Signer(s) Other Than Named Above: _____

Capacity(ies) Claimed by Signer(s)

Signer's Name: _____

- Individual
- Corporate Officer — Title(s): _____
- Partner Limited General
- Attorney in Fact
- Trustee
- Guardian or Conservator
- Other: _____

RIGHT THUMBPRINT OF SIGNER
Top of thumb here

Signer is Representing:

Signer's Name: _____

- Individual
- Corporate Officer — Title(s): _____
- Partner Limited General
- Attorney in Fact
- Trustee
- Guardian or Conservator
- Other: _____

RIGHT THUMBPRINT OF SIGNER
Top of thumb here

Signer is Representing:



This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

Certificate No: 8201821-971919

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, David L. Culbertson, Charles L. Flake, Spencer Flake, Lexie Sherwood, Heather Willis

all of the city of Anaheim state of California each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 9th day of August, 2019.



Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

By: David M. Carey, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

State of PENNSYLVANIA ss
County of MONTGOMERY

On this 9th day of August, 2019 before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Teresa Pastella, Notary Public
Upper Merion Twp., Montgomery County
My Commission Expires March 28, 2021
Member, Pennsylvania Association of Notaries

By: Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV - OFFICERS: Section 12. Power of Attorney.

Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII - Execution of Contracts: Section 5. Surety Bonds and Undertakings.

Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation - The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization - By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 8th day of November, 2019.



By: Renee C. Llewellyn, Assistant Secretary

To confirm the validity of this Power of Attorney call 1-610-832-8240 between 9:00 am and 4:30 pm EST on any business day.

CONSTRUCTION AGREEMENT

THIS CONSTRUCTION AGREEMENT ("Agreement") is made as of February 25, 2020 and is by and between RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT, a body politic, (District) and SOUTHWEST GENERAL ENGINEERING (Contractor).

IT IS AGREED BY THE PARTIES AS FOLLOWS:

1. The Work. Contractor shall furnish all tools, equipment, apparatus, facilities, labor, supervision, services, transportation, materials and other required items and materials and do all things necessary to perform, accomplish and complete the work for **Project No. 1-0-00234-01, Jurupa-Pyrite MDP Line A-2, Stage 1** of District, in exact conformity with the Contract Documents (identified below) for the Project, subject to such inspection as District deems appropriate and pursuant to orders and instructions, drawings, etc., issued by District in accordance with the Contract Documents.

2. Contract Documents. The Contract Documents for **Project No. 1-0-00234-01, Jurupa-Pyrite MDP Line A-2, Stage 1** of District are:

- (a) Notice Inviting Bids to Contractors;
- (b) Instructions To Bidders;
- (c) Contractor's Proposal, including List of Subcontractors, Statement of Licensure, Non-Collusion Declaration, Iran Contracting Act Certification;
- (d) Bid Bond
- (e) Construction Agreement, including Exhibit A, Workers' Compensation Contractor Certificate, Declaration of Sufficiency of Funds, and Evidence of Insurance;
- (f) Performance Bond;
- (g) Payment Bond;
- (h) General Provisions;
- (i) Special Provisions;
- (j) Detailed Specifications;
- (k) Plans;
- (l) Appendices and any other documents included in or incorporated into the Contract Documents;
- (m) Orders, Instructions, Drawings and Plans issued by District during the course of the work in accordance with the provisions of the Contract Documents; and
- (n) Addenda No(s), if any N/A.

Each of the above-mentioned documents presently in existence are by this reference incorporated herein and each of said documents not now in existence are incorporated herein as of the time of their issuance.

The Bid Bond is exonerated upon execution and delivery to District in a form satisfactory to District, of the following, duly executed by Contractor and also by its Surety as to the Bonds, Construction Agreement, Certificate of Insurance, Performance Bond, and Payment Bond.

3. Bonds - Insurance. Contractor must deliver to District and District must approve, a fully executed Performance Bond in the amount of 100% of the estimated contract price, a fully executed Payment Bond in the amount of 100% of the estimated contract price, and fully executed certificates of insurance evidencing the existence of the insurance required by Subsection 8.02 of the General Provisions. The Payment Bond and Performance Bond must be on forms furnished by District.

Should any surety on the Performance Bond or Payment Bond be deemed unsatisfactory by the Board of Supervisors of District, Contractor shall upon notice promptly substitute new Bonds in form satisfactory to District.

4. Contract Price - Payment. The District agrees to pay and the Contractor agrees to accept in full consideration for the performance of the Agreement, the sum of the total amount provided in Exhibit A, attached hereto, marked Exhibit A and by this reference made a part hereof, is provision for the Contract Price and its payment, subject to additions and deductions as provided in the Specifications and Contract Documents.

5. Contract Time for Completion. The Work shall be commenced on a date to be specified in a written "Notice To Proceed" to be issued by the District and shall be completed within the duration specified in the Specifications and Contract Documents. It is expressly agreed that except for extensions of time duly granted in the manner and for the reasons specified in the General Provisions, time shall be of the essence.

RIVERSIDE COUNTY FLOOD CONTROL
AND WATER CONSERVATION DISTRICT

FORM APPROVED COUNTY COUNSEL
BY: Synthia M. Gunzel 2/13/2020
SYNTHIA M. GUNZEL DATE

By Karen S. Spiegel
Chairwoman of its Board of Supervisors
KAREN SPIEGEL

ATTEST:

KECIA HARPER
Clerk of the Board

By [Signature]
Deputy

(Seal)

Southwest General Engineering
Contractor
By [Signature]
Title President

(If corporation affix corporate seal)

EXHIBIT A

(To Agreement for Riverside County Flood Control and Water Conservation District's Project No. 1-0-00234-01, Jurupa-Pyrite MDP Line A-2, Stage 1, located in the city of Jurupa Valley, Riverside County, California.)

Contract Price - Payment - District shall pay Contractor the following sums for the items set forth below in accordance with Contractor's Proposal as accepted by District, which sums shall be paid as provided in the General Provisions and subject to additions and deductions as provided in the Contract Documents.

It is understood that the quantities listed, except for those shown as "Final" or "Lump Sum" are but estimates only and final payment will be based on actual work performed, subject to such adjustments and alterations as elsewhere provided.

ITEM NO.	ITEM OF WORK	UNIT	QUANTITY	UNIT COST	TOTAL COST
1.	Mobilization	L.S.	---	---	\$6,670.00
2.	Water Control	L.S.	---	---	8,310.00
3.	Traffic Control	L.S.	---	---	11,200.00
4.	Clearing and Miscellaneous Work	L.S.	---	---	39,000.00
5.	Excavation	C.Y.	507	\$44.60	22,612.20
6.	Street Reconstruction	C.Y.	167	\$57.70	9,635.90
7.	Backfill	C.Y.	15	\$168.00	2,520.00
8.	Class "A" Concrete, Retaining Wall	C.Y.	7	\$1,345.00	9,415.00
9.	Class "A" Concrete, Concrete Swale	C.Y.	91	\$405.00	36,855.00
10.	Class "B" Concrete, 2' Cutoff Wall	L.F.	983	\$15.70	15,433.10
11.	Class "B" Concrete, Miscellaneous	C.Y.	3	\$2,270.00	6,810.00
12.	Aggregate Base, Class 2	C.Y.	73	\$154.00	11,242.00
13.	Hot Mix Asphalt (HMA)	TONS	94	\$138.00	12,972.00
14.	Modified 6-Foot Chain Link Fence	L.F.	500	\$61.50	30,750.00
15.	Temporary Fencing	L.F.	197	\$14.80	2,915.60

EXHIBIT A contd.

ITEM NO.	ITEM OF WORK	UNIT	QUANTITY	UNIT COST	TOTAL COST
16.	Modified 14-Foot Double Drive Gates	PAIR	1	\$3,420.00	3,420.00
17.	4'W x 1.5'H Grated Trench Drain	L.F.	56	\$1,485.00	83,160.00
18.	Midwest Guardrail System	L.F.	35	\$48.50	1,697.50
19.	Adjust Manhole to Grade	EACH	1	\$1,455.00	1,455.00
20.	Extra Directed Work	L.S.	---	---	10,000.00
21.	Rock Slope Protection, Class I (20-lb)	C.Y.	6	\$181.00	1,086.00
22.	Crushed Rock	C.Y.	66	\$73.20	4,831.20
23.	Rock Slope Protection Fabric	S.Y.	17	\$20.70	351.90
24.	Dust Abatement	L.S.	---	---	2,445.00
25.	Stormwater and Non-Stormwater Pollution Control	L.S.	---	---	15,850.00
				TOTAL	\$350,637.40

PERFORMANCE BOND

Page 1 of 3

(Public Work – Public Contract Code Section 21091)

WHEREAS, the Riverside County Flood Control and Water Conservation District ("District") on JANUARY 8, 2020, has awarded Construction Contract Number: 1-0-00234-01 ("Contract") to the undersigned SOUTHWEST GENERAL ENGINEERING, INC. as Principal ("Principal") to perform the work ("Work") for the following project; Jurupa-Pyrite MDP Line A-2, Stage 1, which Contract is by this reference hereby incorporated herein and made a part hereof;

WHEREAS, said Principal is required by the Contract and/or by California Public Contract Code, Section 20129 (b) to furnish a performance bond for the faithful performance of the Contract;

NOW THEREFORE, we, the Principal and THE OHIO CASUALTY INSURANCE COMPANY ("Surety"), an admitted surety insurer pursuant to Code of Civil Procedure, Section 995.120, are held and firmly bound unto District in the penal sum of ** Dollars (\$ 350,637.40), this amount being not less than one hundred percent (100%) of the total sum payable by District under the Contract at the time the Contract is awarded by District to the Principal, lawful money of the United States of America, for the payment of which sum well and truly to be made, we, Principal and Surety, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents, to:

** THREE HUNDRED FIFTY THOUSAND SIX HUNDRED THIRTY-SEVEN & 40/100 DOLLARS

1. Perform all the work required to complete the Project; and
2. Pay to the District all damages the District incurs as a result of the Contractor's failure to perform all the Work required to complete the Project.

THE CONDITION OF THIS OBLIGATION IS SUCH that if Principal, its heirs, executors, administrators, successors or assigns approved by District, shall in all things stand to and abide by and well and truly keep and perform all the undertakings, terms, covenants, conditions and agreements in the Contract, including, without limitation, all obligations during the original term and any extensions thereof as may be granted by District, with or without notice to Surety thereof (including, without limitation, the obligation for Principal to pay liquidated damages), all obligations during the period of any warranties and guarantees required under the Contract and all other obligations otherwise arising under the terms of the Contract (such as, but not limited to, obligations of indemnification), all within the time and in the manner therein designated in all respects according to their true intent and meaning, then this obligation shall become null and void; otherwise, it shall be and remain in full force and effect.

As a condition precedent to the satisfactory completion of the Contract, the above obligation shall hold good for a period equal to the warranty and/or guarantee period of the Contract, during which time Surety's obligation shall continue if Contractor shall fail to make full, complete, and satisfactory repair and replacements and totally protect the District from loss or damage resulting from or caused by defective materials or faulty workmanship. The obligations of Surety hereunder shall continue so long as any obligation of Contractor remains. Nothing herein shall limit the District's rights or the Contractor or Surety's obligations under the Contract, law or equity, including, but not limited to, California Code of Civil Procedure section 337.15.

PERFORMANCE BOND

Page 2 of 3

Whenever Principal shall be, and is declared by District to be, in default under the Contract, the Surety shall promptly either remedy the default, or, if the Contract is terminated by District or the Principal's performance of the Work is discontinued, Surety shall promptly complete the Contract through its agents or independent contractors, subject to acceptance of such agents or independent contractors by District as hereinafter set forth, in accordance with its terms and conditions and to pay and perform all obligations of Principal under the Contract (including, without limitation, all obligations with respect to payment of liquidated damages) less the "Balance of the Contract Price" (as hereinafter defined); subject to the penal amount of this bond as set forth above. The term "Balance of the Contract Price", as used in this paragraph, shall mean the total amount payable to Principal by District under the Contract and any modifications thereto, less the amount previously paid by District to the Principal and less amounts that District is authorized to withhold under the terms of the Contract.

If District determines that completion of the Contract by Surety or its agents or independent contractors must be performed by a lowest responsible bidder selected pursuant to a competitive bidding process, then Surety shall comply with such processes in accordance with the requirements of District and applicable laws. Unless otherwise approved by District, in the exercise of its sole and absolute discretion, Surety shall not utilize Principal in completing performance of the Work.

No right of action shall accrue on this bond to or for the use of any person or entity other than District or its successors or assigns.

In the event any legal proceeding or arbitration is brought upon this bond by District and judgment or award is entered in favor of District as the prevailing party, Surety shall pay all costs and attorney's fees incurred by the District.

Correspondence or claims relating to this bond shall be sent to Surety at the address set forth below.

Surety, for value received, agrees that no change, extension of time, alteration or addition to the terms of the Contract, or to the work to be performed thereunder, shall in any way impair or affect Surety's obligation under this bond, and Surety does hereby waive notice of any such changes, extensions of time, alterations or additions.


Surety's obligations hereunder are independent of the obligations of any other surety for the performance of the Contract, and suit may be brought against Surety and such other sureties, joint and severally, or against any one or more of them or against less than all of them, without impairing District's rights against the others.

PERFORMANCE BOND

Page 3 of 3

(Corporate Seal of Principal,
if Corporation)

SOUTHWEST GENERAL ENGINEERING, INC.
(Proper name of Principal)


By: 
Signature of Principal's authorized representative

Print or type authorized representative's Name and Title

3625 PLACENTIA LANE, RIVERSIDE, CA 92501-1119
Print or type Principal's Address

(Corporate Seal of Surety)

Surety THE OHIO CASUALTY INSURANCE COMPANY

By: 
Attorney-in-Fact SPENCER FLAKE

(Attach Attorney-in-Fact
Certificate and Required
Acknowledgments)

CULBERTSON INSURANCE SERVICES, INC.
Name and Address of California Agent of Surety

5500 E SANTA ANA CANYON RD., #201

ANAHEIM, CA 92807

714-921-0530

Telephone Number of California Agent of Surety

NOTE: Notary acknowledgment of signatures of Principal and Surety, and Surety's Power of Attorney, must be included or attached.

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT


A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

STATE OF CALIFORNIA

County of Orange }

On 1-08-2020 before me, Lexie Sherwood, Notary Public,
Date Insert Name of Notary exactly as it appears on the official seal

personally appeared Spencer Flake
Name(s) of Signer(s)



Place Notary Seal Above

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

Witness my hand and official seal.

Signature Lexie Sherwood
Signature of Notary Public Lexie Sherwood

OPTIONAL

Though the information below is not required by law, it may prove valuable to persons relying on the document and could prevent fraudulent removal and reattachment of the form to another document.

Description of Attached Document

Title or Type of Document: _____

Document Date: _____ Number of Pages: _____

Signer(s) Other Than Named Above: _____

Capacity(ies) Claimed by Signer(s)

Signer's Name: _____

- Individual
- Corporate Officer — Title(s): _____
- Partner Limited General
- Attorney in Fact
- Trustee
- Guardian or Conservator
- Other: _____

**RIGHT THUMBPRINT
OF SIGNER**

Top of thumb here

Signer is Representing:

Signer's Name: _____

- Individual
- Corporate Officer — Title(s): _____
- Partner Limited General
- Attorney in Fact
- Trustee
- Guardian or Conservator
- Other: _____

**RIGHT THUMBPRINT
OF SIGNER**

Top of thumb here

Signer is Representing:

This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

Certificate No: 8202720- 971919

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, David L. Culbertson, Charles L. Flake, Spencer Flake, Lexie Sherwood, Heather Willis

all of the city of Anaheim state of CA each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 11th day of December, 2019.



Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

By: David M. Carey

David M. Carey, Assistant Secretary

State of PENNSYLVANIA
County of MONTGOMERY ss

On this 11th day of December, 2019 before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Teresa Pastella, Notary Public
Upper Merion Twp., Montgomery County
My Commission Expires March 28, 2021
Member, Pennsylvania Association of Notaries

By: Teresa Pastella
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV – OFFICERS: Section 12. Power of Attorney.

Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII – Execution of Contracts: Section 5. Surety Bonds and Undertakings.

Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 8th day of January, 2020.



By: Renee C. Llewellyn

Renee C. Llewellyn, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

To confirm the validity of this Power of Attorney call 1-610-832-8240 between 9:00 am and 4:30 pm EST on any business day.

PAYMENT BOND

Page 1 of 2

(Public Work - Civil Code Sections 9550 et seq.)

WHEREAS, the Riverside County Flood Control and Water Conservation District ("District") by action of the Board of Supervisors on JANUARY 8, 2020, has awarded Construction Contract Number: 1-0-00234-01 ("Contract") to the undersigned SOUTHWEST GENERAL ENGINEERING, INC., as Principal ("Principal") to perform the work ("Work") for the following project; Jurupa-Pyrite MDP Line A-2, Stage 1.

WHEREAS, said Principal is required by the Contract and/or by the California Civil Code Section 9550 et seq. to furnish a payment bond in connection with the Contract;

NOW THEREFORE, we, the Principal and THE OHIO CASUALTY INSURANCE COMPANY ("Surety"), an admitted surety insurer pursuant to Code of Civil Procedure, Section 995.120, are held and firmly bound unto District in the penal sum of ** Dollars (\$ 350,637.40), this amount being not less than one hundred percent (100%) of the total sum payable by District under the Contract at the time the Contract is awarded by District to the Principal, lawful money of the United States of America, for the payment of which sum well and truly to be made, we, Principal and Surety, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

** THREE HUNDRED FIFTY THOUSAND SIX HUNDRED THIRTY-SEVEN & 40/100 DOLLARS

THE CONDITION OF THIS OBLIGATION IS SUCH that if Principal, its heirs, executors, administrators, successors, or assigns approved by District, or its subcontractors, of any contracting tier, shall fail to pay any amounts or any person or persons named and described in California Civil Code, Section 9554, then Surety will pay for the same, in or to an amount not exceeding the penal amount hereinabove set forth, and also will pay to the prevailing party if suit is brought upon this bond, reasonable attorney's fees as provided in California Civil Code, Section 9564.

Surety, for value received, agrees that no change, extension of time, alteration or addition to the terms of the Contract, or to the Work to be performed thereunder, nor any rescission or attempted rescission of the Contract or this bond, nor any conditions precedent or subsequent in the bond or Contract attempting to limit the right of recovery of any claimant otherwise entitled to recover under the Contract or this bond shall in any way impair or affect Surety's obligation under this bond, and Surety does hereby waive notice of any such changes, extensions of time, alterations or additions.

Surety is not released from liability to those for whose benefit this bond has been given, by reason of any breach of the Contract by District or Principal.

It is hereby expressly stipulated and agreed that this bond shall inure to the benefit of any and all persons, companies, and corporations entitled to file claims under Section 9100 of the Civil Code, so as to give a right of action to them or their assigns in any suit brought upon this bond.

PAYMENT BOND

Page 2 of 2

Surety's obligations hereunder are independent of the obligations of any other surety for the performance of the Contract, and suit may be brought against Surety and such other sureties, joint and severally, or against any one or more of them or against less than all of them, without impairing District's rights against the others.

SOUTHWEST GENERAL ENGINEERING, INC.

(Proper name of Principal)

(Corporate Seal of Principal,
if Corporation)

By: 

Signature of Principal's authorized representative

Print or type authorized representative's Name and Title

3625 PLACENTIA LANE, RIVERSIDE, CA 92501-1119

Print or type Principal's Address

(Corporate Seal of Surety)

Surety THE OHIO CASUALTY INSURANCE COMPANY

By: 

Attorney-in-Fact SPENCER FLAKE

(Attach Attorney-in-Fact
Certificate and Required
Acknowledgments)

CULBERTSON INSURANCE SERVICES, INC.

Name and Address of California Agent of Surety

5500 E SANTA ANA CANYON RD., #201

ANAHEIM, CA 92807

714-921-0530

Telephone Number of California Agent of Surety

NOTE: Notary acknowledgment of signatures of Principal and Surety, and Surety's Power of Attorney, must be included or attached.

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.


STATE OF CALIFORNIA

County of Orange }

On 1-08-2020 before me, Lexie Sherwood, Notary Public,
Date Insert Name of Notary exactly as it appears on the official seal

personally appeared Spencer Flake

Name(s) of Signer(s)



Place Notary Seal Above

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

Witness my hand and official seal.

Signature

Lexie Sherwood
Signature of Notary Public Lexie Sherwood

OPTIONAL

Though the information below is not required by law, it may prove valuable to persons relying on the document and could prevent fraudulent removal and reattachment of the form to another document.

Description of Attached Document

Title or Type of Document: _____

Document Date: _____ Number of Pages: _____

Signer(s) Other Than Named Above: _____

Capacity(ies) Claimed by Signer(s)

Signer's Name: _____

- Individual
- Corporate Officer — Title(s): _____
- Partner Limited General
- Attorney in Fact
- Trustee
- Guardian or Conservator
- Other: _____

RIGHT THUMBPRINT
OF SIGNER

Top of thumb here

Signer is Representing: _____

Signer's Name: _____

- Individual
- Corporate Officer — Title(s): _____
- Partner Limited General
- Attorney in Fact
- Trustee
- Guardian or Conservator
- Other: _____

RIGHT THUMBPRINT
OF SIGNER

Top of thumb here

Signer is Representing: _____

This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

Certificate No: 8202720-971919

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, David L. Culbertson, Charles L. Flake, Spencer Flake, Lexie Sherwood, Heather Willis

all of the city of Anaheim state of CA each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 11th day of December, 2019.



Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

By: David M. Carey

David M. Carey, Assistant Secretary

State of PENNSYLVANIA
County of MONTGOMERY ss

On this 11th day of December, 2019 before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Teresa Pastella, Notary Public
Upper Merion Twp., Montgomery County
My Commission Expires March 28, 2021
Member, Pennsylvania Association of Notaries

By: Teresa Pastella
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV – OFFICERS: Section 12. Power of Attorney.

Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII – Execution of Contracts: Section 5. Surety Bonds and Undertakings.

Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 8th day of January, 2020



By: Renee C. Llewellyn

Renee C. Llewellyn, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

To confirm the validity of this Power of Attorney call 1-610-832-8240 between 9:00 am and 4:30 pm EST on any business day.

WORKERS' COMPENSATION CONTRACTOR CERTIFICATE

(Labor Code Sections 1860, 1861 & 3700)

In accordance with the provisions of Section 3700 of the Labor Code, every Contractor shall secure compensation in one or more of the following ways:

- (a) By being insured against liability to pay compensation by one or more insurers duly authorized to write compensation insurance in this state.
- (b) By securing from the Director of Industrial Relations a certificate of consent to self-insure either as an individual employer, or as one employer in a group of employers, which may be given upon furnishing proof satisfactory to the Director of Industrial Relations of ability to self-insure and to pay any compensation that may become due to his or her employees.
- (c) For any county, city, city and county, municipal corporation, public district, public agency, or any political subdivision of the state, including each member of a pooling arrangement under a joint exercise of powers agreement (but not the state itself), by securing from the Director of Industrial Relations a certificate of consent to self-insure against workers' compensation claims, which certificate may be given upon furnishing proof satisfactory to the director of ability to administer workers' compensation claims properly, and to pay workers' compensation claims that may become due to its employees. On or before March 31, 1979, a political subdivision of the state which, on December 31, 1978, was uninsured for its liability to pay compensation, shall file a properly completed and executed application for a certificate of consent to self-insure against workers' compensation claims. The certificate shall be issued and be subject to the provisions of Section 3702.

Labor Code Section 1861 requires each Contractor to whom a public works Contract is awarded shall sign and file with the District the following certification prior to performing the Work of the public works construction Contract:

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the Work of this Contract.

By signing this certification, the Contractor understands the requirements of and agrees to comply with the aforementioned requirements.

Name of Contractor: Southwest General Engineering
By: [Signature]
Title: President

DECLARATION OF SUFFICIENCY OF FUNDS

Page 1 of 3

(California Labor Code Section 2810)

I, the undersigned, an authorized representative of Southwest General Engineering ("Bidder") with authority to make the statements contained in this Declaration on behalf of Bidder, hereby declare the following:

1. The Bidder's employer identification number for state tax purposes is:
33-0825029

2. The Bidder's workers' compensation insurance policy number is:
WC5513739-05

and the name, address, and telephone number of the insurance carrier providing said insurance is:

Zurich American Insurance Co.

3. The following information is provided concerning any and all vehicles that are owned by the Bidder and that will be used for transportation in connection with any service provided for the performance of the Work that is the subject of the Bidder's Bid [Insert information requested. Attach additional sheets, if needed.]: Please see Attached

<i>Vehicle</i>	<i>Vehicle ID #</i>	<i>Vehicle Liability Insurance Policy Number (of policy covering vehicle)</i>	<i>Name, Address and Telephone Number of Vehicle Liability Insurance Carrier (issuing policy covering vehicle)</i>

4. The following is the address of any real property that will be used to house workers in connection with the performance of the Work that is the subject of the Bidder's Bid [If no such housing will be provided, enter "none"]:
None

DECLARATION OF SUFFICIENCY OF FUNDS

5. The actual or estimated number of workers that will be employed to perform the Work that is the subject of the Bidder's Bid, the total amount of wages to be paid to said workers, and the dates on which said wages will be paid are as follows [Attach additional sheets, if needed.]:

<i>Total Number of Workers</i>	<i>Total Amount of Wages</i>	<i>Date(s) for Payment of Wages</i>
7	\$ 70,000 -	Thursdays

6. Check only one of the following boxes, as applicable:

- The statement of number of workers declared in Paragraph 5, above, is a statement of the actual number of workers that will be employed.
- The actual number of workers requested in Paragraph 5, above, is unknown and therefore the statement of number of workers declared therein is based on the Bidder's best estimate available at the time of submitting its Bid, rather than the actual number of workers that will be employed and if and when the actual number of workers and the other information requested above is available, it will be reported to the District by Bidder in writing.

7. The actual or estimated total number of persons who will be utilized as independent Contractors to perform the Work of the Project that is the subject of the Bidder's Bid (together with their known, current local, state, and federal Contractor license identification numbers that each is required to have under local, state or federal laws or regulations) are as follows [Attach additional sheets, if needed.]:

<i>List of Independent Contractors</i>	<i>Current, local, state and federal Contractor license identification number</i>
None	

DECLARATION OF SUFFICIENCY OF FUNDS

Page 3 of 3

8. Check only one of the following boxes, as applicable:

- The statement of number of independent Contractors declared in Paragraph 7, above, is a statement of the actual number of independent Contractors that will be utilized.
- The actual number of independent Contractors requested in Paragraph 7, above, is unknown and therefore the statement of number of independent Contractors declared therein is based on the Bidder's best estimate available at the time of submitting its Bid, rather than the actual number of independent Contractors that will be utilized, and if and when the actual number of independent Contractors and the other information requested above is available, it will be reported to the District by Bidder in writing.

I, the undersigned, declare under penalty of perjury that the foregoing statements are within my personal knowledge and are true and correct. Executed on this 15 day of January, in the year 2020 at Riverside, California.

(Signature)

Bob Shepherd
Type Name of Signer:

Southwest General Engineering
Type Name of Bidder:

1/16/2020
8:23:34AM

SOUTHWEST V-DITCH, INC.
Fixed Asset List

Auto Policy: BAP 5513740-05
AMERICAN ZURICH INS. CO.

ID	Description	Acquisition Date	Serial Number	License Number	Category	Location
	JD 710 Backhoe	01/04/2017				
CO	Compressor 125	01/11/2017				
DEPR	Depreciation Exp - Equip	10/12/2017				
EX	JD Excavator	01/11/2017				
FB	Flatbed Truck	08/10/2016				
FL4	Manitou M30-2T Forklift	07/26/2017	80545111			
GE	General EQ Rpr	01/01/2015				
ME	JD Mini Excavator	01/04/2017				
OT	Operator Truck	04/21/2017				
PU	Shotcrete Pump	01/01/2016				
RENTS	Equip & Veh Rents	07/14/2016				
SB	Sand Blaster	04/21/2017				
SK1	Skiploader	01/01/2016				
T030	Peterbilt 379 Semi	08/15/2000	1XP5DB9X4XD484			
T041	Ford F450	01/11/2017				
T042	Ford F450	01/11/2017				
T043	Ford F450 Dump Trk	11/04/2016	1FDXF46F0YEC754			
T047	Ford F450	01/11/2017				
T048	Ford F550 4x4 Crew Cab	01/11/2017				
T052	Chevrolet Silverado 2500 HD	01/11/2017				
T053	Ford F450 4x4	11/04/2016				
T054	Ford F750	11/04/2016	3FD9F7563YMA374			
T056	Ford F750 Dump Trk	11/04/2016				
T057	Ford F550XL 4x4	11/04/2016				
T061	Freightliner FL70 Dump Trk	11/04/2016				
T064	Shotcrete Rig	11/04/2016				
T066	Ford F550	01/11/2017				
T069	Peterbilt 379 Semi	01/11/2017				
T070	Chevrolet Trailblazer LT 4WD	01/11/2017				
T071	Ford F550 4x4	01/11/2017				
T073	Ford F550	01/11/2017				
T074	Shotcrete Rig	01/11/2017				
T077	Ford F550	01/11/2017				
T	Ford F550 Crew Cab	01/11/2017				
T081	Ford F350 4x4 Supercab	01/11/2017				

Southwest V-Ditch, Inc. Fixed Asset List

ID	Description	Acquisition Date	Serial Number	License Number	Category	Location
T084	Shotcrete Rig	01/11/2017				
T085	GMC Sierra	01/11/2017				
T087	Ford F550	01/11/2017				
T097	Ford F550 Supercab	01/11/2017				
T098	Ford F550 Supercab 4x4	01/11/2017				
T099	Ford F550 Reg Cab	01/11/2017				
T100	Ford F350 Pickup	01/11/2017				
T101	Ford F550 Crew Cab	01/11/2017				
T102	Shotcrete Rig	01/11/2017				
T103	GMC Sierra 2500 4WD Crew	04/26/2017	3FRNF6FB5BV0828			
T104	Ford F550 4WD Reg Cab	07/22/2017	1GT12SEY4HF1856	47222G2		
T105	Ford F550 4WD Reg Cab	07/22/2017	1FDUF5HT9HEE20	64633H2		
T114	Ford F-750 Reg Cab	07/22/2017	1FDUF5HT7HEE20	64707H2		
T115	2019 Ford F-550	05/20/2019	1FDXF7DX4KDF10			
WB	Water Buggy	09/01/2019				
WT1	Freightliner FL70 2500 Water Truck	01/01/2016				
		01/11/2017				



CERTIFICATE OF LIABILITY INSURANCE

SOUTH-H

OP ID: MAI

DATE (MMDD/YYYY)

02/11/2020

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER Crosby Insurance 8181 E. Kaiser Blvd Anaheim Hills, CA 92808	CONTACT NAME: 2019B	
	PHONE (A/C, No, Ext): 714-221-5200 FAX (A/C, No): 714-221-5210 E-MAIL: ADDRESS:	
INSURED: Southwest General Engineering Inc. 3625 Placentia Lane Riverside, CA 92501-1119	INSURER(S) AFFORDING COVERAGE	NAIC #
	INSURER A: United Specialty Insurance Co.	12537
	INSURER B: AMERICAN ZURICH INS.CO.	40142
	INSURER C: Starr Indemnity & Liability Co	38318
	INSURER D: Zurich American Ins. Co.	16535
	INSURER E: INSURER F:	

COVERAGES

CERTIFICATE NUMBER:

REVISION NUMBER: 001

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL SUBR INSD / WVD	POLICY NUMBER	POLICY EFF (MMDD/YYYY)	POLICY EXP (MMDD/YYYY)	LIMITS
A	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input checked="" type="checkbox"/> PROJECT <input type="checkbox"/> LOC <input type="checkbox"/> OTHER	X	ATN1985221	10/01/2019	10/01/2020	EACH OCCURRENCE \$ 1,000,000
						DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 50,000
						MED EXP (Any one person) \$ 5,000
						PERSONAL & ADV INJURY \$ 1,000,000
						GENERAL AGGREGATE \$ 2,000,000
						PRODUCTS - COMP/OP AGG \$ 2,000,000
						Emp Ben. \$ 1,000,000
B	<input checked="" type="checkbox"/> AUTOMOBILE LIABILITY <input type="checkbox"/> ANY AUTO <input type="checkbox"/> ALL OWNED AUTOS <input type="checkbox"/> HIRED AUTOS <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> NON-OWNED AUTOS		BAP5513740-05	10/01/2019	10/01/2020	COMBINED SINGLE LIMIT (Ea accident) \$ 1,000,000
						BODILY INJURY (Per person) \$
						BODILY INJURY (Per accident) \$
						PROPERTY DAMAGE (Per accident) \$
						\$
C	<input type="checkbox"/> UMBRELLA LIAB <input checked="" type="checkbox"/> OCCUR <input checked="" type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE DED RETENTION \$		1000584615191	10/01/2019	10/01/2020	EACH OCCURRENCE \$ 5,000,000
						AGGREGATE \$ 5,000,000
						\$
D	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below	Y/N <input type="checkbox"/> N/A	X WC5513739-05	10/01/2019	10/01/2020	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTHER
						E.L. EACH ACCIDENT \$ 1,000,000
						E.L. DISEASE - EA EMPLOYEE \$ 1,000,000
						E.L. DISEASE - POLICY LIMIT \$ 1,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

TEN DAYS NOTICE OF CANCELLATION WILL BE GIVEN FOR NON-PAYMENT OF PREMIUM

RE: Project #1-0-00234-01 Jurupa-Pyrite MDP Line A-2, Stage 1
The District, the County of Riverside, and City of Jurupa Valley are named as additional insured per the attached endorsements as required by written contract. XCU exclusions are waived.

CERTIFICATE HOLDER

CANCELLATION

COURIVS

County of Riverside
1995 Market Street
Riverside, CA 92502

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

Jackie Nguyen

© 1988-2014 ACORD CORPORATION. All rights reserved.

NOTEPAD:

HOLDER CODE **COURIVS**
INSURED'S NAME **Southwest General Engineering**

SOUTH-H
OP ID: MAI

PAGE 2
Date **02/11/2020**

Builders Risk endorsement effective 3/15/2020 to 5/15/2020. Hard cost limit \$350,637. Will forward the endorsement copy upon receipt.

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

**ADDITIONAL INSURED – OWNERS, LESSEES OR
CONTRACTORS – SCHEDULED PERSON OR
ORGANIZATION**

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART

SCHEDULE

Name Of Additional Insured Person(s) Or Organization(s)	Location(s) Of Covered Operations
As Required By Written Contract, Fully Executed Prior To The Named Insured's Work	As Required By Written Contract, Fully Executed Prior To The Named Insured's Work
Information required to complete this Schedule, if not shown above, will be shown in the Declarations.	

A. Section II – Who Is An Insured is amended to include as an additional insured the person(s) or organization(s) shown in the Schedule, but only with respect to liability for "bodily injury", "property damage" or "personal and advertising injury" caused, in whole or in part, by:

1. Your acts or omissions; or
2. The acts or omissions of those acting on your behalf;

in the performance of your ongoing operations for the additional insured(s) at the location(s) designated above.

However:

1. The insurance afforded to such additional insured only applies to the extent permitted by law; and
2. If coverage provided to the additional insured is required by a contract or agreement, the insurance afforded to such additional insured will not be broader than that which you are required by the contract or agreement to provide for such additional insured.

B. With respect to the insurance afforded to these additional insureds, the following additional exclusions apply:

This insurance does not apply to "bodily injury" or "property damage" occurring after:

1. All work, including materials, parts or equipment furnished in connection with such work, on the project (other than service, maintenance or repairs) to be performed by or on behalf of the additional insured(s) at the location of the covered operations has been completed; or
2. That portion of "your work" out of which the injury or damage arises has been put to its intended use by any person or organization other than another contractor or subcontractor engaged in performing operations for a principal as a part of the same project.

C. With respect to the insurance afforded to these additional insureds, the following is added to Section III - Limits Of Insurance:

If coverage provided to the additional insured is required by a contract or agreement, the most we will pay on behalf of the additional insured is the amount of insurance:

1. Required by the contract or agreement; or

2. Available under the applicable Limits of Insurance shown in the Declarations; whichever is less.

This endorsement shall not increase the applicable Limits of Insurance shown in the Declarations.

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

ADDITIONAL INSURED – OWNERS, LESSEES OR CONTRACTORS – COMPLETED OPERATIONS

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART
PRODUCTS/COMPLETED OPERATIONS LIABILITY COVERAGE PART

SCHEDULE

Name Of Additional Insured Person(s) Or Organization(s)	Location And Description Of Completed Operations
As Required By Written Contract, Fully Executed Prior To The Named Insured's Work	Any project or premises where work was performed by or on behalf of the insured other than a residential tract project which is defined as any project comprised of a piece or parcel of land that is subdivided into five or more lots for the construction of freestanding one, two, three or four family dwellings.

Information required to complete this Schedule, if not shown above, will be shown in the Declarations.

A. Section II – Who Is An Insured is amended to include as an additional insured the person(s) or organization(s) shown in the Schedule, but only with respect to liability for "bodily injury" or "property damage" caused, in whole or in part, by "your work" at the location designated and described in the Schedule of this endorsement performed for that additional insured and included in the "products-completed operations hazard".

However:

1. The insurance afforded to such additional insured only applies to the extent permitted by law; and
2. If coverage provided to the additional insured is required by a contract or agreement, the insurance afforded to such additional insured will not be broader than that which you are required by the contract or agreement to provide for such additional insured.

B. With respect to the insurance afforded to these additional insureds, the following is added to **Section III – Limits Of Insurance:**

If coverage provided to the additional insured is required by a contract or agreement, the most we will pay on behalf of the additional insured is the amount of insurance:

1. Required by the contract or agreement; or
2. Available under the applicable Limits of Insurance shown in the Declarations;

whichever is less.

This endorsement shall not increase the applicable Limits of Insurance shown in the Declarations.

WORKERS' COMPENSATION AND EMPLOYERS' LIABILITY INSURANCE POLICY

WC 04 03 06 (Ed. 4-84)

**WAIVER OF OUR RIGHT TO RECOVER FROM OTHERS ENDORSEMENT—
CALIFORNIA**

This endorsement changes the policy to which it is attached effective on the inception date of the policy unless a different date is indicated below.

(The following "attaching clause" need be completed only when this endorsement is issued subsequent to preparation of the policy.)

This endorsement, effective on 10/01/2019 at 12:01 A.M. standard time, forms a part of
(DATE)

Policy No. WC5513739-05

Endorsement No.

of the Zurich American Ins. Co.

(NAME OF INSURANCE COMPANY)

issued to Southwest V-Ditch, Inc.

Premium (if any) \$

Authorized Representative

We have the right to recover our payments from anyone liable for an injury covered by this policy. We will not enforce our right against the person or organization named in the Schedule. (This agreement applies only to the extent that you perform work under a written contract that requires you to obtain this agreement from us.)

You must maintain payroll records accurately segregating the remuneration of your employees while engaged in the work described in the Schedule.

The additional premium for this endorsement shall be % of the California workers' compensation premium otherwise due on such remuneration.

Schedule

Person or Organization

Job Description

All persons and/or organizations that are required by written contract or agreement with the insured, executed prior to the accident or loss, that waiver of subrogation be provided under this policy for work performed by you for that person and/or organization.

GENERAL PROVISIONS

GENERAL PROVISIONS

SECTION I - DEFINITION OF TERMS

1.01 TERMS. Whenever in these specifications, or in any documents or instruments where these specifications govern, the following terms or pronouns in place of them are used, the intent and meaning shall be interpreted as follows:

(a) DISTRICT: The Riverside County Flood Control and Water Conservation District of the State of California, as created by law, also sometimes referred to as the Flood Control District, or party of the first part.

(b) BOARD OF SUPERVISORS: The Board of Supervisors of the Riverside County Flood Control and Water Conservation District as created by law, also sometimes referred to as the Board.

(c) ENGINEER: The Chief Engineer of the Riverside County Flood Control and Water Conservation District, also sometimes referred to as the Flood Control Engineer, the Chief Engineer, or the General Manager-Chief Engineer, acting either directly or through properly authorized agents, such agents acting within the scope of the particular duties entrusted to them.

(d) LABORATORY: The established laboratory of the District or laboratories authorized by the District to test materials and work involved in the contract.

(e) BIDDER: Any individual, firm or corporation submitting a proposal for the work contemplated, acting directly or through a duly authorized representative.

(f) CONTRACTOR: The person or persons, co-partnership or corporation, private or municipal, who have entered into a contract with the District, as party or parties of the second part or his or their legal representatives.

(g) SUPERINTENDENT: The Executive representative of the Contractor, present on the work at all times during progress, authorized to receive and execute instruction from the Engineer.

(h) PLANS or PROJECT DRAWINGS: The official plans, profiles, typical cross sections, general cross sections, working drawings, and supplemental drawings, or exact reproductions thereof, approved by the Engineer, which show the location, character, dimensions and details of the work to be done, and which are to be considered as a part of the contract supplementary to these specifications.

(i) SPECIFICATIONS: The directions, provisions, and requirements contained herein as supplemented by such special provisions, as may be necessary, pertaining to the method and manner of performing the work or to the quantities and qualities of materials to be furnished under the contract. The Special Provisions are specific clauses setting forth conditions or requirements peculiar to the project under consideration and covering work or materials involved in the proposal and estimate but not satisfactorily covered by these General Provisions. Supplemental agreements

or contract change orders are written agreements executed by the Contractor and by the District, covering alterations, amendments or extensions to the project, as hereinafter provided.

(j) CONTRACT: The written agreement covering the performance of the work and the furnishing of labor and materials in the construction of the work. The contract shall include the Notice to Contractors, the Proposal, Plans, Specifications, Special Provisions, and Contract Bonds, also, any and all supplemental agreements or contract change orders amending or extending the work contemplated and which may be required to complete the work in a substantial and acceptable manner.

(k) CONTRACT PRICE: Shall mean either the lump sum, unit price, or unit prices to be named in the contract, or the total of all payments under the contract at the lump sum, unit price, or unit prices, as the case may be.

(l) SURETY OR SURETIES: The bondsmen or party or parties, approved by the Engineer, who may guarantee the fulfillment of the contract by bond, and whose signatures are attached to said bond.

(m) RIGHT OF WAY: The whole right of way which is reserved for and secured for use in constructing the improvement.

(n) THE WORK: All the work specified in the Specifications and Contract Documents, including the Special Provisions, proposal and contract, or indicated on the plans as the contemplated complete improvement covered by the contract.

1.02 SIMILARITY OF WORDS. Wherever in the specifications or upon the plans the words directed, required, permitted, ordered, designated, prescribed, or words of like import are used, it will be understood that the direction, requirements, permission, order, designation, or prescription of the Flood Control Engineer is intended, and similarly the words approved, acceptable, satisfactory, or words of like import, shall mean approved by, or acceptable to, or satisfactory to, the Flood Control Engineer, unless otherwise expressly stated.

SECTION II - SCOPE OF WORK

2.01 WORK TO BE DONE

It is the intent of these General Provisions, Special Provisions, Detailed Specifications, and the plans herein referred to, that the Contractor shall provide all labor, power, light, water, materials, equipment, tools, scaffolding, machinery, transportation, insurance, permits, bonds, temporary protection, watchmen, and superintendence necessary to construct and complete all work, and to furnish all materials included in the contract, except those furnished by the District and as specifically mentioned in these specifications.

The contract documents are complementary, and the work called for by any one shall be as binding as if called for by all.

2.02 CONSTRUCTION SCHEDULE

The Contractor shall submit at such times as may be requested by the Engineer, a schedule which shall show the order and dates in which the Contractor proposes to carry on the various parts of the work; including estimated completion dates. The District's receipt of such schedule(s) shall not indicate any concurrence by the District in the items or dates described in the schedule(s).

2.03 DRAWINGS AND SPECIFICATIONS ON THE WORK

The Contractor shall keep one copy of all drawings and specifications on the work, in good order, available to the Engineer and his representatives.

2.04 ESTIMATE OF QUANTITIES

The quantities of work to be done and the materials to be furnished under this contract are approximate only. The District is not to be held responsible for the accuracy of the estimate of quantities.

The Contractor shall judge for himself, after considering all circumstances and conditions, the costs and quantities of materials involved in the contract. The Contractor shall not at any time assert that there was any misunderstanding in regard to the depth or class of the excavations to be made, or the nature or kind or amount of materials to be furnished for the work.

The Contractor shall not at any time assert that there was any misunderstanding in regard to the nature of the work or the kind or amount of materials to be furnished for the work. The Contractor herewith agrees that he will not ask, demand, sue for, or seek to recover, for compensation in excess of the amounts payable for the various unit costs or lump sum charges for the work, as stipulated in the proposal, which he actually performs as specified.

2.05 PROTESTS

If the Contractor considers any work demanded of him to be outside of the requirements of the contract, or considers any record or ruling of the Engineer to be unfair, he shall immediately, upon such work being demanded or such record or ruling being made, ask, in writing, for written instructions covering protested items of work. Immediately on receipt of written instructions from the Engineer he shall proceed without delay to diligently perform the work in conformance with the written record or ruling. Immediately upon receipt of the written instructions or ruling and before the start of such work, and no later than five (5) business days, the Contractor shall file a written protest with the Engineer stating clearly and in detail the basis of his protest. Except for such protests as are made of record in the manner herein specified and within the time limit stated, the records, rulings, instructions, or decisions of the Engineer shall be final and conclusive.

2.06 ALTERATIONS

The Contractor understands and agrees that such reasonable alterations and modifications may be made by the Chief Engineer, as may be deemed desirable, and that this may be done without notices to the Sureties on the Contractor's bonds. If such changes result in increased or decreased quantities under the items specified in the Agreement, the Contractor will be paid on the

basis of actual quantities as measured by the Engineer, and such changes shall not affect the unit prices bid by the Contractor. If, however, such changes result in delay to the work, the Contractor may request an extension of time on the completion of his contract and the Chief Engineer may grant such extension as the Chief Engineer may deem equitable.

2.07 EXTRA WORK

A. General

The District reserves and shall have the right, for any reason whatsoever, or when confronted with unpredicted conditions, unforeseen events, or emergencies, to revise the details of the contemplated work, or to add work of a different character or function and have the Contractor perform such revised or added work as "Extra Work", when such extra work is considered by the Chief Engineer to be appurtenant to the satisfactory completion of the project.

"Extra Work" is defined as added work of a different character or function and for which no basis for payment is prescribed; or that involving revisions of the details of the work in such manner as to render inequitable payment under items upon which the Contractor bid; or that work which is indeterminate at the time of advertising and is specifically designated as extra work in the plans and Special Provisions.

The signing of the contract by the Contractor will be deemed to be an agreement on his part to perform extra work, as and when ordered by the Chief Engineer. Notice to the Sureties on the Contractor's bonds will not be given unless the estimated total value of the contract, as changed or supplemented, shall exceed the original total bid price by more than 25%.

If required extra work results in delay to the work, the Contractor will be given an equivalent extension of time.

Approval of extra work shall be obtained from the Board of Supervisors before such work is authorized to be done, if:

- a. For contracts with a total contract price of \$250,000 or less, a change due to extra work exceeds ten percent (10%) of the original contract amount; or
- b. For contracts with a total contract price of more than \$250,000, a change due to extra work exceeds \$25,000 plus one percent (1%) of the original contract amount in excess of \$250,000; or
- c. An individual change exceeds \$100,000; or
- d. Cumulative contract changes exceed ten percent (10%) of the original contract amount.

Extra work specially authorized by the Board of Supervisors shall not be included in the cost limitations above stated.

B. Procedure for Extra Work

1. Extra work may not be done by the Contractor without prior request and proper written approval by the District. Upon decision of the District to have extra work performed, the Chief Engineer will so inform the Contractor, acquainting him with the essential details of the new work. The Contractor shall thereupon present in writing a price for said work based upon his estimate of cost and submit said price and estimate to the Chief Engineer whose approval shall be secured before work is started; excepting that the Chief Engineer may, when in the best interest of the District, order the Contractor to proceed with the extra work in advance of the submission of such prices, provided that preliminary estimates, as made by the District, show that the cost will not exceed \$1,000.

2. Prices for extra work shall be prepared by the Contractor on one or both of the following methods, as requested by the District, and submitted to the Chief Engineer for approval:

a. For a stated unit price or lump sum amount based upon current prevailing fair prices for materials, labor, plant, overhead and profit.

b. On a cost basis (force account by the Contractor). The cost of all work done by the Contractor will be computed in the manner described in Section 7.03, and the compensation thus provided shall be accepted as payment in full by the Contractor, and no additional payment will be allowed for the use of small tools, superintendent's and foreman's services, timekeeper's services, pickup or yard trucks, except as specifically essential to the work, nor any other overhead expenses incurred in the prosecution of the force account work.

3. Upon receipt of the Contractor's price, the Chief Engineer will make an analysis thereof and adopt one of the following procedures:

a. Accept the Contractor's price for lump sum or unit price amount in the original or amended form and direct him to proceed with the work; or direct him to perform the work on a cost plus basis.

b. Have the work performed by District's forces or separate contract, without undue interference or hindrance to the Contractor and without claim or suit by the Contractor for damages on account thereof.

c. Direct the Contractor to proceed with the work and accept payment therefor in the amount as adjudicated later in a court of law.

4. The price agreed to by the Contractor for the extra work shall be full compensation to the Contractor for all labor, materials, equipment or other costs related to the extra work.

2.08 PAYMENT FOR EXTRA WORK

At the end of each month the Contractor shall make and deliver to the Chief Engineer a statement of the cost of the extra work completed during the current month, itemized and in a form

satisfactory to the Chief Engineer. Upon verification of said statement by the Chief Engineer, the Contractor's claim for the full amount, as shown on said statement, will be added to the monthly partial payment made in accordance with Paragraph 7.06 of the General Provisions.

2.09 RIGHTS OF WAY

The District shall provide the rights of way upon which the work under this contract is to be done, except that the Contractor shall provide land required for the erection of temporary construction facilities and storage of his material, together with right of access to same. The District will not be responsible for any delay in furnishing the rights of way and such delay shall not be made the basis for a claim for additional compensation by the Contractor. However, in case the failure of the District to furnish the required rights of way delays the prosecution of the work, the time allowed for completion will be extended by a period of time equal to that lost by the Contractor due to such delay.

2.10 CLEANING UP

The Contractor shall, as directed by the Engineer, remove from the District's right of way and from all public and private property, at his own expense, all temporary structures, rubbish and waste materials resulting from his operations.

SECTION III - CONTROL OF THE WORK

3.01 AUTHORITY OF THE ENGINEER

The Engineer shall have general supervision and direction of the contract under authority of the Board of Supervisors. He has the authority to stop the work whenever such stoppage may be necessary to ensure the proper execution of the contract. The Engineer shall decide all questions which may arise as to the quality or acceptability of materials furnished, work performed, and rate or progress of the work; all questions which may arise as to the interpretation of the plans and specifications; all questions as to the acceptable fulfillment of the contract on the part of the Contractor; and all questions as to compensation.

His determination and decision thereon shall be final and conclusive; and such determination and decision, in case any question shall arise, shall be a condition precedent to the right of the Contractor to receive any money hereunder.

3.02 DETAIL DRAWINGS

The approved plans shall be supplemented by such working drawings as are necessary to control the work adequately. All authorized alterations affecting the requirements and information given on the approved plans shall be in writing. No changes shall be made of any plan or drawing after the same has been approved by the Engineer, except by his direction.

It is expressly understood, however, that approval by the Engineer of the Contractor's working drawings does not relieve the Contractor of any responsibility for accuracy of dimensions and details. It is mutually agreed that the Contractor shall be responsible for agreement and conformity of his working drawings with the approved plans and specifications.

Full compensation for furnishing all working drawings shall be considered as included in the prices paid for the various contract items of work, and no additional allowance will be made therefor.

3.03 CONFORMITY WITH PLANS AND ALLOWABLE DEVIATIONS

Finished surfaces in all cases shall conform with the elevations, lines, grades, cross-sections, and dimensions shown on the approved plans or as described in the Specifications and Contract Documents. Deviations from the approved plans and working drawings, will in all cases be in the Engineer's discretion and as determined by the Engineer and preauthorized in writing.

3.04 INTERPRETATION OF PLANS AND SPECIFICATIONS

Should it appear that the work to be done or any of the matters relative thereto are not sufficiently detailed or explained in these specifications and the Special Provisions, the Contractor must bring this to District's attention in writing and shall apply to the Engineer for such further explanations as may be necessary and shall conform to the same part of the contract, so far as may be consistent with the original specifications; and in the event of any doubt or questions arising respecting the true meaning of the specifications; reference shall be made to the Engineer, whose decision thereon shall be final. The requirements in this Section 3.04 shall also apply during the bidding process and before submittal of the Contractor's Proposal.

In the event of any discrepancy between any drawings and the figures written thereon, the figures shall be taken as correct. The Contractor will not be allowed to take advantage of errors and omissions in the drawings and specifications. When errors or omissions are found, they will be corrected or supplied by the Engineer.

3.05 SUPERINTENDENCE

The Contractor shall keep on his work, continually during its progress, a competent Superintendent responsible for the construction of the work, and any necessary assistants; all satisfactory to the Engineer. All such persons shall be acceptable to the District continuously throughout the duration of the Project. The Superintendent shall represent the Contractor in his absence and all directions given to him shall be as binding as if given to the Contractor. Important directions shall be confirmed in writing to the Contractor. Other directions shall be so confirmed on written request in each case.

3.06 LINES AND GRADES

The Contractor shall provide reasonable and necessary opportunities and facilities for setting points and making measurements. He shall not proceed until he has made timely demand upon the Engineer for, and has received from him, such lines and grades as may be necessary as the work progresses. The work shall be done in strict conformity with such lines and grades.

The Contractor shall carefully preserve benchmarks, reference points and stakes, and in case of willful or careless destruction, he shall be charged with the resulting expense and shall be responsible for any mistakes that may be caused by their unnecessary loss or disturbance.

3.07 INSPECTION OF WORK

The Engineer and his representatives shall at all times have access to the work during its construction, and shall be furnished with every reasonable opportunity and facility for ascertaining that the stock and materials used and employed, and the workmanship, are in accordance with the requirements and intentions of these specifications. All work done and all materials furnished shall be subject to the Engineer's inspection and approval to ensure design objectives.

The inspection of the work shall not relieve the Contractor of any of his obligations to fulfill his contracts as prescribed, and defective work shall be made good and unsuitable materials may be rejected, notwithstanding that such defective work and materials have been previously overlooked by the Engineer and accepted or estimated for payment.

3.08 REMOVAL OF DEFECTIVE AND UNAUTHORIZED WORK

All work which has been rejected shall be remedied, or removed and replaced by the Contractor in an acceptable manner and no compensation will be allowed him for such removal or replacement. Any work done beyond the lines and grades shown on the plans or established by the Engineer, or any extra work done without written authority, will be considered as unauthorized and will not be paid for. Work so done may be ordered removed at the Contractor's expense. Upon failure on the part of the Contractor to comply forthwith with any order of the Engineer made under the provisions of this article, the Engineer shall have authority to cause defective work to be remedied, or removed and replaced, and unauthorized work to be removed and to deduct the costs for this work from any monies due or to become due the Contractor.

3.09 EQUIPMENT AND PLANT

Equipment not suitable to produce the quality of work required will not be permitted to operate on the project. Plants shall be designed and constructed in accordance with general practice for such equipment and shall be of sufficient capacity and of such character to ensure the production of sufficient material to carry the work to completion within the time limit.

The Contractor shall provide adequate and suitable equipment and plants to meet the above requirements and, when ordered by the Engineer, shall remove unsuitable equipment from the work and discontinue the operation of unsatisfactory plants. No worn or obsolete equipment shall be used, and in no case shall the maker's rating of the capacity for any equipment be exceeded.

All vehicles used to haul materials over existing highways shall be equipped with pneumatic tires.

3.10 FINAL INSPECTION

The Engineer will not make the final inspection until the work provided for and contemplated by the contract has been completed and the final cleaning up performed.

SECTION IV - CONTROL OF MATERIAL

4.01 DISTRICT FURNISHED MATERIALS

The Contractor shall furnish all materials required to complete the work, except those specified in the Special Provisions to be furnished by the District. Materials furnished by the District will be delivered to the Contractor at the points specified in the Special Provisions.

The Contractor will be held responsible for all materials so delivered to him, and deductions will be made from any monies due him to make good any shortages and deficiencies, from any cause whatsoever, which may occur after such delivery, or for any demurrage charges due to delinquency in unloading.

4.02 SOURCE OF SUPPLY AND QUALITY OF MATERIALS

At the option of the Engineer the source of supply of each of the materials shall be approved by him before the delivery is started. Only materials conforming to the requirements of these specifications and approved by the Engineer shall be used in the work. All materials proposed for use may be inspected or tested at any time during their preparation and use. If, after trial, it is found that sources of supply which have been approved do not furnish a uniform product, or if the product from any source proves unacceptable at any time, the Contractor shall furnish approved material from other approved sources. No material which, after approval, subsequently becomes unfit for use shall be used in the work.

Wherever the name, or brand, or manufacturer of an item is specified, it is used as a measure of quality and utility or a standard. Except in those instances where the product is designated to match others presently in use, or as otherwise stated in the Contract Documents, specifications calling for a designated material, product, thing or service by specific brand or trade name shall be deemed to be followed by the words "or equal" so that the Contractor may propose in the Contractor's bid any equal material, product, thing or service. If the Contractor desires to use any other brand or manufacturer of equal quality or utility to that specified, he shall list definite particulars of that which it considers equivalent to the specified item in its bid. The District will then determine whether or not the proposed name brand or article is equal in quality and utility to that specified, and the District's determination in that regard shall be final and binding upon the Contractor.

4.03 SAMPLES AND TESTS

All tests of materials furnished by the Contractor shall be made by the District in accordance with commonly recognized standards of national organizations, and such special methods and tests as are in use at the District's approved laboratory and described in the Detailed Specifications.

Field tests of materials will also be made by the Engineer when deemed necessary and these tests shall be made in accordance with standard practices of the District.

The Contractor shall furnish such samples of all materials as are requested by the Engineer without charge. No material shall be used until it has been approved by the Engineer. Samples will be secured and tested whenever necessary to determine the quality of the material.

Promptly after the approval of the contract, the Contractor shall notify the Engineer of the proposed sources of supply of all materials to be furnished by him, using a form which will be supplied by the Engineer upon request.

Whenever reference is made in these specifications to standard tests or requirements of the laboratory of the District, the American Society for Testing Materials, the American Railway Engineering Association, or the American Association of State Highway Officials, the reference shall be construed to mean the standards that are in effect at the date of these specifications with subsequent amendments, changes, or additions as thereafter adopted and published by the organization referred to.

4.04 DIGGING TRENCHES OR OTHER EXCAVATIONS

Any work that involves digging trenches or other excavations extending deeper than four feet below the surface, then the following terms shall apply:

4.04.1 Contractor shall promptly, and before the following conditions are disturbed, notify the District, in writing, of any:

- 4.04.1.1 Material that the Contractor believes may be material that is hazardous waste, as defined in Section 25117 of the Health and Safety Code, that is required to be removed to a Class I, Class II, or Class III disposal site in accordance with provisions of existing law.
- 4.04.1.2 Subsurface or latent physical conditions at the site differing from those indicated by information about the site made available to bidders prior to the deadline for submitting bids.
- 4.04.1.3 Unknown physical conditions at the site of any unusual nature, different materially from those ordinarily encountered and generally recognized as inherent in work of the character provided for in the contract.

4.04.2 The District shall promptly investigate the conditions, and if it finds that the conditions do materially so differ, or do involve hazardous waste, and cause a decrease or increase in the Contractor's cost of, or the time required for, performance of any part of the work shall issue a change order under the procedures described in the contract.

4.04.3 In the event that a dispute arises between the District and the Contractor whether the conditions materially differ, or involve hazardous waste, or cause a decrease or increase in the Contractor's cost of, or time required for, performance of any part of the work, the Contractor shall not be excused from any scheduled completion date provided for by the contract, but shall proceed with all work to be performed under the contract. The Contractor shall retain any and all rights provided either by contract or by law which pertain to the resolution of disputes and protests between the contracting parties.

4.04.4 Contractor shall submit to District, in advance of excavation, a detailed plan showing the design of shoring, bracing, sloping, or other provisions to be made for worker protection from the hazard of caving ground during the excavation of such trench or trenches. Prior to any excavation is commenced, District shall accept said plan. If such plan varies from the shoring system standards, the plan shall be prepared by a registered civil or structural engineer.

4.04.5 Nothing in this section shall be deemed to allow the use of a shoring, sloping, or protective system less effective than that required by the Construction Safety Orders.

4.04.6 Nothing in this section shall be construed to impose tort liability on the awarding body or any of its employees.

4.05 STORAGE OF MATERIALS

Materials shall be so stored as to ensure the preservation of their quality and fitness for the work. When considered necessary by the Engineer, they shall be placed on wooden platforms or other hard, clean surfaces and not on the ground. They shall be placed under cover when so directed. Stored materials shall be so located as to facilitate prompt inspection.

4.06 DEFECTIVE MATERIALS

All materials not conforming to the requirements of these specifications shall be considered as defective and all such materials, whether in place or not, shall be rejected and shall be removed immediately from the site of the work unless otherwise permitted by the Engineer. No rejected materials, the defects of which have been subsequently corrected, shall be used until approval in writing has been given by the Engineer. Upon failure on the part of the Contractor to comply forthwith with any order of the Engineer made under the provisions of this article, the Engineer shall have authority to remove and replace defective material and to deduct the cost of removal and replacement from any monies due or to become due the Contractor.

4.07 ASSIGNMENT OF CLAIMS

In submitting a bid on this public works project, or any subcontractor agreeing to supply goods, services, or materials, and entering a contract pursuant thereto, the Contractor and/or subcontractor do offer and agree to assign to the District all rights, title, and interest in and to all causes of action it may have under Section 4 of the Clayton Act (15 U.S.C. Section 15) or under the Cartwright Act (Chapter 2 (commencing with Section 16700) of Part 2 of Division 7 of the Business and Professions Code), arising from purchases of goods, services, or materials pursuant to the public works contract or the subcontract. This assignment shall be made and become effective at the time the awarding body tenders final payment to the Contractor, without further acknowledgment by the parties.

SECTION V - LEGAL RELATIONS AND RESPONSIBILITY

5.01 LAWS TO BE OBSERVED

(a) Compliance with Applicable Law. Reference to and/or incorporation into the Contract Documents of a particular law, statute, ordinance, rule or regulation is not, nor is it

intended to be, a definitive statement of the law applicable to the Contract Documents and the accomplishment of the work. Contractor must keep informed as to all such applicable law - Federal, State, County, Municipal, District - as it affects the conduct of the work and comply with such law, including, but not limited to, having requisite licenses, obtaining necessary permits, paying necessary fees and taxes, posting notices and installing, operating and maintaining safety precautions and facilities. It is likewise Contractor's responsibility to see to it that his subcontractors also fully comply with such applicable law.

If at any time Contractor is of the opinion that there is a discrepancy or inconsistency in the plans, drawings, specifications or other Contract Documents, he shall immediately cease work involving such alleged discrepancies or inconsistencies and report the same in writing to the Chief Engineer and shall not proceed with such work until ordered so to do, and in the manner instructed by the Chief Engineer.

Contractor shall protect and defend District, its officers, agents and employees against any claim or liability arising from or based upon any alleged violation of such applicable law. See also Subsection 8.02.

(b) Labor Code - The Contractor shall comply with all applicable requirements of the California Labor Code including but not limited to Labor Code, Chapter 2, Subchapter 1, Article 10, Required Apprentices on Public Works Contracts. Reference is made to Chapter 1, Part 7, Division 2 of the California Labor Code (commencing with Section 1720). By this reference said Chapter 1 is incorporated herein with like effect as if it were here set forth in full. The parties recognize that said Chapter 1 deals with, among other things, discrimination, penalties and forfeitures, their disposition and enforcement, wages, working hours and securing workers' compensation insurance and directly affect the method of prosecution of the work by Contractor and subject it under certain conditions to penalties and forfeitures. Execution of the Agreement by the parties constitutes their agreement to abide by said Chapter 1. Their stipulation as to all matters which they are required to stipulate as to by the provisions of said Chapter 1, constitutes Contractor's certification that it is aware of the provisions of said Chapter 1 and will comply with them and further constitutes Contractor's certification as follows: "I am aware of the provisions of Section 3700 of the California Labor Code which requires every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that Code, and I will comply with such provisions before commencing the performance of the work of this contract." Contractor and its subcontractors shall comply with the provisions of S1777.5 of the Labor Code regarding apprentices.

Contractor shall post at each job site during the course of the work a copy of District's "Determination of Prevailing Wage Rates", copies of said Determination are available from District for this purpose and at <http://www.dir.ca.gov/OPRL/DPreWageDetermination.htm>.

(c) Equal Employment Opportunity

General - The Contractor shall comply with all applicable non-discrimination and equal employment laws. The Contractor shall not discriminate in its recruiting, hiring, promotion, demotion or termination practices on the basis of race, religious creed, color, national origin, ancestry, sex, age or physical handicap in the performance of this Contract and shall comply with the provisions of the California Fair Employment Practice Act (commencing with Section 1410 of

the Labor Code), the Federal Civil Rights Act of 1964 (P.L. 88-352) and all amendments thereto, Executive Order No. 11246 (30 Federal Register 12319), as amended, and all administrative rules and regulations issued pursuant to said Acts and Order. See particularly 41 Code of Federal Regulation (CFR) Chapter 60.

Contractor shall require each of its subcontractors to comply with the preceding paragraph and shall include in each subcontract language similar to the preceding paragraph.

Contractor shall permit access to its records of employment, employment advertisement, application forms and other pertinent data and records (including but not limited to certified payroll information) by District and any state or federal agency having jurisdiction for the purpose of investigation to ascertain compliance with this Section.

District may assign an affirmative action representative to monitor Contractor and its subcontractor(s) conduct required by this Section, including the right of entry to the construction site for the purpose of obtaining information from persons performing work on the project providing such inspection does not interfere with the progress of the work.

Elsewhere in the Contract Documents specific requirements may be contained covering the same subject matter of this Section. If so, such specific requirements prevail over this Section in case of conflict.

Transactions of \$10,000 or under - Contracts and subcontracts not exceeding \$10,000 are exempt from the requirements of this Section. No Contractor or subcontractor shall procure supplies and/or services in less than usual quantities to avoid applicability of this Section. With respect to contracts and subcontracts for indefinite quantities, this Section applies unless the amount required in any one year under such contract will reasonably be expected not to exceed \$10,000.

Transactions in Excess of \$10,000 but less than \$50,000 - At District's request, Contractor shall certify that it has in effect an affirmative action plan and agrees to comply with all state and federal laws and regulations regarding Fair Employment Practices. Contractor shall maintain a written copy of its affirmative action plan and furnish District a copy of the plan upon request. District may require Contractor to complete an Affirmative Action Compliance Report, on a form furnished by District, setting forth definite goals during the term of this contract.

Transactions of \$50,000 or more - If Contractor has 50 or more employees and a contract for \$50,000 or more, it shall develop and submit to District, within 30 days after award, a written affirmative action compliance program providing in detail specific steps to guarantee equal employment opportunity. Contractor shall include in its affirmative action program a table of job classifications, which table shall include but need not be limited to job titles, duties and rates of pay.

Contractor shall in each subcontract let to do a portion of the work covered hereunder, where the subcontractor involved has 50 or more employees and the subcontract is for \$50,000 or more, impose in the subcontract the above requirements.

For the purpose of determining the number of employees, the average of the Contractor's or its subcontractor's employees for the 12 month period immediately prior to award, or the total number of employees Contractor or its subcontractor will have when performing this contract, whichever is higher, shall be used.

Federally Assisted Construction - If this project is a Federally assisted construction project, then the contract provisions contained 41 CFR S60-1.4(b) are incorporated herein and Contractor shall likewise incorporate said provisions in each subcontract entered into by Contractor to perform the work. Federally assisted construction is identified as such in the Notice Inviting Bids.

(d) Registration of Contractors - In order to be considered a prospective bidder must be licensed in accordance with Division 3, Chapter 9 (commencing with Section 7000) of the Business and Professions Code.

(e) Accident Prevention - Particular attention shall be given to relevant Division of Industrial Safety Construction and Electrical Safety Orders. Said Orders are contained in Title 8 of the California Code of Regulations, Chapter 4, Subchapters 4 and 5. Specific attention shall be taken of the California Occupational Safety and Health Act of 1973 (commencing with Section 6300 of the Labor Code) and the Federal Occupational Safety and Health Act of 1970 (P.L. 91-596) and rules and regulations issued pursuant to said Acts. Specific reference is made to Article 6 of said Construction Safety Orders. Contractor shall submit to Engineer, who will accept in advance of excavation, a detailed plan showing the design of shoring, bracing, sloping of the sides of trenches, or other provisions to be made for protection of personnel during earthwork operations. In event the Contractor's plan does not conform with the shoring system requirements of Article 6, the Contractor's proposed shoring design shall be prepared and signed by a civil or structural engineer registered in the State of California.

The Contractor shall also impose the foregoing requirements on all subcontractors involved and enforce compliance therewith.

The duties here set forth are nondelegable by Contractor who shall protect and defend District, its officers, agents and employees in connection therewith. See Subsection 8.02.

5.02 CONTRACTOR'S RESPONSIBILITY

Contractor is under the absolute duty in fulfilling its contractual obligations hereunder to proceed, and cause its subcontractors to proceed, in a safe, workmanlike manner, with adequate safeguards for the protection of the public, the workmen and persons from time to time inspecting the work. If at any time Contractor finds any of its subcontractors are allowing work to proceed in an unsafe manner and contrary to the intent of these Contract Documents, Contractor shall immediately cause such action to stop and immediately take all action necessary to protect workmen, inspectors and the general public and cause the work to proceed in a safe manner.

Contractor shall protect and defend District, its officers, agents and employees in reference to acts or omissions contrary to the above. See particularly Subsection 8.02.

District may withhold funds otherwise due Contractor whenever, in its judgment, this subsection is not being complied with.

5.03 CONTRACTOR'S RESPONSIBILITY FOR WORK

Until the formal acceptance of the work by the District, the Contractor shall have the charge and care thereof and shall bear the risk of injury or damage to any part thereof by the action of the elements or from any other cause, whether arising from the execution or from the non-execution of the work. The Contractor shall rebuild, repair, restore, and make good all injuries or damages to any portion of the work occasioned by any of the above causes before its completion and acceptance and shall bear the expense thereof, except for such injuries or damages as are occasioned by acts of the Federal Government and the public enemy. In case of suspension of work from any cause whatsoever, the Contractor shall be responsible for all materials and shall properly store them if necessary and shall erect temporary structures where necessary.

5.04 PROPERTY RIGHTS IN MATERIALS

Nothing in the contract shall be construed as vesting in the Contractor any right of property in the materials used after they have been attached or affixed to the work or the soil. All such materials shall become the property of the District upon being so attached or affixed.

5.05 PERMITS AND LICENSES

The Contractor shall procure all permits and licenses, (including but not limited to: National Pollution Discharge Elimination System (NPDES) and South Coast Air Quality Management District (AQMD) permit requirements), pay all charges and fees, and give all notices necessary and incident to the due and lawful prosecution of the work.

5.06 ROYALTIES AND PATENTS

The Contractor shall assume all costs arising from the use of patented materials, equipment, devices, or processes used on or incorporated on the work, and agrees to indemnify and save harmless the Riverside County Flood Control and Water Conservation District, the Board of Supervisors, the Flood Control Engineer, and their duly authorized representatives, from all suits at law, or actions of every nature for, or on account of, the use of any patented materials, equipment, devices, or processes.

5.07 SANITARY PROVISIONS

Necessary conveniences, properly secluded from public observation shall be provided by the Contractor where needed for the use of laborers on the work. Their location, construction and maintenance shall be subject to the approval of the Engineer, and their use shall be strictly enforced. The Contractor shall obey and enforce such sanitary regulations as may be prescribed by the State Department of Health or other authorities having jurisdiction.

5.08 PUBLIC SAFETY

The Contractor at his own expense shall furnish, erect, and maintain such fences, barriers, lights, and signs as are necessary to give adequate warning to the public at all times that the bridges, culverts, and work along public highways are under construction; and of any dangerous conditions to be encountered as a result thereof; and he shall erect such warning and directional signs and employ such flagmen as are required and maintain same throughout the construction period.

Full compensation for the work involved in carrying out the precautionary measures above specified shall be considered as included in the prices paid for the various contract items of work and no additional allowance will be made therefor.

5.09 USE OF EXPLOSIVES

When the use of explosives is necessary for the prosecution of the work, the Contractor shall use the utmost care not to endanger life or property.

All explosives shall be stored in accordance with the provisions of Division II, Part I, Chapter 3, of the Health and Safety Code of the State of California.

5.10 PROVISIONS FOR EMERGENCIES

Unusual conditions may arise on the work which will require that immediate and unusual provisions be made to protect the public from danger or loss or damage to life and property, due directly or indirectly to the prosecution of the work, and it is part of the service required of the Contractor to make such provisions and to furnish such protection.

The Contractor shall use such foresight and shall take such steps and precautions as his operations make necessary to protect the public from danger or damage, or loss of life or property, which would result from the interruption or contamination of public water supply, irrigation or other public service, or from the failure of partly completed work.

Whenever work is undertaken pursuant to the above provisions, Contractor shall promptly file with District a verified report setting forth the nature of the emergency and the action taken by the Contractor by reason of the emergency.

Whenever, in the opinion of the Engineer, an emergency exists against which the Contractor has not taken sufficient precaution for the safety of the public or the protection of utilities or of adjacent structures or property which may be injured by process of construction on account of such neglect; and whenever, in the opinion of the Engineer, immediate action shall be considered necessary in order to protect public or private, personal or real property interests, or prevent likely loss of human life or damage on account of the operations under the contract, then and in that event the Engineer may provide suitable protection to said interests by causing such work to be done and material to be furnished as, in the opinion of the Engineer, may seem reasonable and necessary.

The cost and expense of all such emergency work shall be borne by the Contractor, and if he shall not pay said cost and expense upon presentation of the bills therefor, duly certified by the

Engineer, then said cost and expense will be paid by the District and shall thereafter be deducted from any amounts due, or which may become due said Contractor. Failure of the District, however, to take such precautionary measures, shall not relieve the Contractor of his full responsibility for public safety.

5.11 UNFORESEEN DIFFICULTIES

All loss or damages, except as noted in Section 8.03, arising out of the nature of the work to be done under the contract, or from any unforeseen obstructions or difficulties which may be encountered during the progress of the work and in the prosecution of the same, or from the action of the elements, or from encumbrances in the line of work, shall be sustained by the Contractor.

5.12 ACCESS TO THE WORK

Access to the work from existing roads shall be provided by the Contractor at his expense and maintained in a manner so as not to create a public nuisance. The Board of Supervisors, Flood Control District and Engineer assume no responsibility for the condition or maintenance of any existing road or structure thereon that may be used by the Contractor for performing the work under these specifications and for traveling to and from the site of the work. No direct payment will be made to the Contractor for constructing temporary roads used for construction operations or for improving, repairing, or maintaining any existing road or structure thereon that may be used by the Contractor for performance of the work under these specifications. The cost of all work described in this paragraph shall be included in the prices bid in the schedule for other items of construction work.

5.13 GUARANTEE OF WORK

All work is guaranteed by Contractor for a period of one year from the recordation of the Notice of Completion against defects resulting from the use of inferior materials, equipment, or workmanship. Upon notice from District, Contractor shall promptly remedy such defects at his expense, including payment to District of its expenses in connection with remedying such defects, otherwise District shall proceed to remedy such defects and Contractor shall upon demand reimburse District for its expenses in connection therewith.

The above one year guarantee is in addition to any specific guarantee(s) provided for elsewhere in the Contract Documents.

The performance of guarantee and conditions specified in Section 5.13., shall be secured by a surety bond which shall be delivered by the Contractor to the District prior to the date on which final payment is made to the Contractor. Said bond shall be in an approved form and executed by a surety company or companies satisfactory to the District, in the amount of 10% of the final contract price. Said bond shall remain in force for the duration of the guarantee period specified in Section 5.13. Instead of providing such a bond as described above, the Contractor may, at its option, provide for the performance bond furnished under the contract to remain in force for said amount until the expiration of said guarantee period; and the amount of said performance bond may be reduced to 10% of the final contract price beginning at the time of recordation of the Notice of Completion.

5.14 DAMAGES BY ACT OF GOD

If the construction of the project herein is damaged, which damage is determined to have been proximately caused by an act of God, in excess of 5% of the contract amount, provided that the work damaged is built in accordance with applicable building standards and the plans and specifications, then the District, may, without prejudice to any other right or remedy, terminate the contract.

SECTION VI - PROSECUTION AND PROGRESS

6.01 PROGRESS OF THE WORK

The Contractor shall begin the work within ten (10) calendar days after the date of the receipt by him of notice to proceed from the Chief Engineer and shall diligently and continuously prosecute the same to completion within the time limit provided in the Special Provisions.

6.02 OVERTIME WORK AND WORK AT NIGHT

It is intended that the Contractor prosecute the work on a five (5) day, forty (40) hour work week with no work on legal holidays. If the Contractor feels it is necessary to work more than the normal forty (40) hour work week, he will make a written request for permission from the Engineer, outlining the reasons for such request. The decision of granting permission for overtime work shall be made by the Engineer and shall be final. A condition will be imposed on the granting of a request to work overtime, requiring the Contractor to pay the District the cost incurred at overtime rates for additional inspection and engineering time required in connection with the overtime work.

When any work is performed at night, only such classes of work shall be done as can be properly inspected. Adequate light must be provided for the safety of the workers and for proper inspection.

6.03 SUBCONTRACTING

Reference is made to the Subletting and Subcontracting Fair Practice Act contained in the Public Contract Code (commencing §4100). By this reference, said Act is incorporated herein with like effect as if it were here set forth in full and the parties shall abide by its terms and substitution shall be only as allowed by that Act.

Contractor shall be responsible for the acts and omissions of its subcontractors and shall make certain that at all times its subcontractors comply with the terms of the Contract Documents and applicable law insofar as such compliance relates to the work.

District reserves the right to approve all subcontractors whether or not they are required to be listed in the Contractor's Proposal. As used in this Section "subcontractor" includes any person who fabricates or manufactures any article for incorporation into the work whether or not they install or test after installation or contract to install or test after installation, but does not include suppliers of fungible goods for incorporation into the work unless such supplier also installs or tests or contracts to install or test.

The Contractor shall give his personal attention to the fulfillment of the contract and shall keep the work under his control. The Contractor shall perform with his own organization work of a value amounting to not less than 60% of the remainder obtained by subtracting from the total original contract value the sum of any item designated herein or in the Special Provisions as Specialty Items. The furnishing and placing of reinforcing steel, when placing is performed by the supplier, will be considered as a Specialty Item for this purpose; however, he shall be designated in the list of subcontractors. The value of the work subcontracted will be based on the contract item bid price. When a portion of an item is subcontracted, the value of work subcontracted will be based on the estimated percentage of the Contract Unit Price. This will be determined from information submitted by the Contractor, and subject to approval by the Engineer.

Where a portion of the work which has been subcontracted by the Contractor is not being prosecuted in a manner satisfactory to the District, the subcontractor shall be removed immediately on the requisition of the Engineer and shall not again be employed on the work.

6.04 CHARACTER OF WORKMEN

If any subcontractor or person employed by the Contractor shall fail or refuse to carry out the directions of the Engineer or shall appear to the Engineer to be incompetent or to act in a disorderly or improper manner, he shall be discharged immediately on the requisition of the Engineer, and such person shall not again be employed on this work.

6.05 TEMPORARY SUSPENSION OF THE WORK

The Engineer shall have the authority to suspend the work wholly or in part, for such period as he may deem necessary, due to unsuitable weather, or to such other conditions as are considered unfavorable for the suitable prosecution of the work, or for such time as he may deem necessary due to the failure on the part of the Contractor to carry out orders given, or to perform any provision of the contract. The Contractor shall immediately comply with the written order of the Engineer to suspend the work wholly or in part. The work shall be resumed when conditions are favorable and methods are corrected, as ordered or approved in writing by the Engineer.

6.06 TIME OF COMPLETION AND DAMAGES

The Contractor shall complete the work called for under the contract in all parts and requirements within the number of working days specified in the Special Provisions. Liquidated damages shall apply as stated in the Special Provisions and the Contract Documents.

A working day is hereby defined as any day; except Saturdays, Sundays, and legal holidays and days on which the Contractor is specifically required by the Special Provisions to suspend construction operations; on which the Contractor is not prevented by inclement weather or conditions resulting immediately therefrom adverse to the current controlling operation or operations, as determined by the Engineer, from proceeding with at least 60% of the normal labor and equipment force engaged in such operation or operations for at least five hours toward completion of such operation or operations.

The Engineer will furnish the Contractor a weekly statement showing the number of working days charged to the contract for the preceding week, the number of working days specified

for completion of the contract, and the number of working days remaining to complete the contract. The Contractor will be allowed one week in which to file a written protest setting forth in what respects said weekly statement is incorrect, otherwise the statement shall be deemed to have been accepted by the Contractor as correct.

The following holidays will be considered as legal holidays: New Year's Day; Martin Luther King Jr.'s Birthday, Lincoln's Birthday; Washington's Birthday; Memorial Day; Independence Day; Labor Day; Columbus Day; Veteran's Day; Thanksgiving Day; Christmas; and such other days as are declared holidays by ordinance passed by the Board of Supervisors of the District.

Contractor acknowledges that failure to perform in strict accordance with the Contract Documents and within the time limit specified in the Special Provisions will cause District to suffer special damages in addition to cost of completion of the work in accordance with the provisions of the Contract Documents. Such special damage could include, but is not limited to, lease and rental cost, additional salaries and overhead, interest during construction, attorney expense, additional engineering, inspection expense, cost of maintaining or constructing alternate facilities and injury to the property of the District or others. The daily cost to the District for inspection and superintendence by the District shall be the amount specified in the Special Provisions. The District may withhold from any money due or that may become due the Contractor under the contract, such amount as the District may elect to offset the damages incurred and any withholding or failure to withhold shall not in any way limit recovery for damages actually incurred.

It is further agreed that in case the work called for under the contract is not finished and completed in all parts and requirements within the time specified, the Board of Supervisors shall have the right to extend the time for completion or not, as may seem best to serve the interest of the District, and if it decides to extend the time limit for the completion of the contract, it shall further have the right to charge to the Contractor, his heirs, assigns or sureties and to deduct from the final payment for the work all or any part, as it may deem proper, of the actual cost of engineering, inspection, superintendence, and other overhead expenses which are directly chargeable to the contract, and which accrue during the period of such extension, except that cost of final surveys and preparation of final estimate shall not be included in such charges.

The Contractor shall not be assessed damages nor the cost of engineering and inspection during any delay in the completion of the work caused by acts of God or of the public enemy, acts of the District, encountering unknown utility facilities, fire, floods, epidemics, quarantine restrictions, strikes, freight embargoes, and severe weather or delays of subcontractors due to such causes, provided that the Contractor shall notify the Engineer in writing of the causes of delay within 10 days from the beginning of any such delay, and his findings of the facts thereon shall be final and conclusive. Contractor shall not be assessed damages for delay in the completion of the project, when such delay was caused by the failure of the District or the owner of the utility facilities.

The term "severe weather" shall be construed to mean only such weather as is unreasonable or extraordinary and in the opinion of the Engineer, the work could not be prosecuted by the Contractor during the period throughout which such weather prevailed.

6.07 DELAYS AND EXTENSION OF TIME

If delays are caused by unforeseen causes beyond the control of either the Contractor or the District, such as war, strikes, fire, floods, or other action of the elements, such delays will entitle the Contractor to an equivalent extension of time for the completion of the contract, but the Contractor shall not be entitled to damages or additional payments over and above the contract price due to delay caused by any of the above-mentioned causes. Furthermore, if the Contractor suffers any delay caused by the failure of the District to furnish the necessary right of way or materials agreed to be furnished by it, or by failure to supply necessary plans or instructions concerning the work to be done after written request therefor has been made, the Contractor shall be entitled to an extension of time equivalent to the time lost for any of the above-mentioned reasons, but shall not be entitled to any damages for such delay.

6.08 ASSIGNMENT

The contract may be assigned only upon written consent of the District. Such written consent to sublet, assign or otherwise dispose of any portion of the contract, shall not be construed to relieve the Contractor of any responsibility for the fulfillment of the contract.

6.09 TERMINATION OF CONTRACT

Subject to all applicable provisions of these specifications and/or the contract to be entered into hereunder, the Engineer is hereby empowered to direct the time and rate of delivery of materials at the site of work and to direct the time, rate and sequence of work. If the Contractor fails to begin delivery of material and equipment or to commence work within the time specified herein, and/or in the contract, or to maintain the rates of delivery of materials, or to execute the work in the manner and at such locations as directed by the Engineer, or fails to maintain a program of work in such a manner as will, in the judgment of the Engineer inure to interests of the District, or, if in the judgment of the Engineer, the Contractor is not carrying out the provisions of the contract in their true intent and meaning, written notice by the Chief Engineer may be served upon him and the Surety on his faithful performance bond demanding a satisfactory compliance with the contract, and with these specifications. If the Contractor and/or his Surety refuses or neglects to comply with such notice within five (5) days after receiving same, or after commencing so to do, fails to continue so to do, or has assigned or sublet the contract without the consent of the District, then the District may exclude him from the premises and take possession thereof, together with all material and equipment thereon, and may complete the work itself, either by force account or by letting the unfinished portion of the work to another Contractor or by a combination of such methods. In any event, the cost of the completion of said work shall be a charge against the Contractor and his Surety and may be deducted from any money due or becoming due from the District, and if the sums due under the contract are insufficient, said Contractor and/or his Surety shall pay to the District within five (5) days after the completion of the work all of such cost in excess of the contract price.

The Surety, in the event that it assumes part of the work, shall take the Contractor's place in this contract in all respects for that part and shall be paid by the District for all work performed by it in accordance with the terms of this contract. If the Surety assumes the entire contract, all monies remaining due the Contractor at the time of his default shall be made payable to the Surety as the work progresses, subject to the terms of the contract.

SECTION VII - PAYMENT

7.01 SCOPE OF PAYMENTS

The Contractor shall accept compensation, as herein provided, in full payment for furnishing all materials, labor, tools, and equipment necessary to the completed work and for performing all work contemplated and embraced under the contract; also for loss or damage arising from the nature of the work, or from the action of the elements, except as hereinbefore provided, or from any unforeseen difficulties which may be encountered during the prosecution of the work until the final acceptance by the Board of Supervisors; and for all risks of description connected with the prosecution of the work, also for all expenses incurred in consequence of the suspension or discontinuance of the work as herein specified; and for completing the work according to the plans and specifications. Neither the payment of any estimate nor of any retained percentage shall relieve the Contractor of any obligation to make good any defective work or material.

7.01A Measurement and Computation of Quantities - All items of the work to be paid for at a contract price per unit of measurement will be measured by the Engineer in accordance with United States Standard Measures. A ton shall mean 2,000 pounds, avoirdupois. Except as otherwise expressly provided in the specifications, the methods of measurement and computation of quantities of such items will be determined by the Engineer, taking into account the price of the item relative to its quantity and the costs of measurement.

The weights of metalwork, pipe, and other metal parts to be paid for by weight will be determined by the Engineer on the basis of handbook weights, scale weights, or manufacturer's catalog weights, or in the absence of any of the foregoing, on the basis of estimated weights; provided, that weights of nonmetallic coatings will be excluded.

7.01B Payment at Contract Prices - The contract price for an item of the work shall include full compensation for all costs of that item, including the costs of any work, materials and equipment incidental to the item but not specifically shown or described in the drawings and specifications, subject only to such express limitations as may be stated in the specifications defining the item or prescribing payment therefor.

The contract prices shall include full compensation for all costs of any work, materials, and equipment required by the drawings and specifications at the time of contract award, but not covered by a contract price or otherwise expressly made the subject of direct payment.

7.02 PAYMENT AND COMPENSATION FOR ALTERED QUANTITIES

When alterations in plans or quantities of work are ordered and performed, the Contractor shall accept payment in full at the contract unit price for the actual quantities of work done and no allowance will be made for anticipated profits. Increased or decreased work involving supplemental agreements will be paid for as stipulated in such agreements.

7.03 FORCE ACCOUNT PAYMENT

When extra work is to be paid for on a force account basis, compensation will be determined as follows:

7.03A Work Performed by Contractor - The Contractor will be paid for labor, materials, and equipment rental as hereinafter provided, except where agreement has been reached to pay in accordance with Section 7.03B. Only materials incorporated in the work will be paid for.

To the total computed as provided in Sections 7.03A(1), 7.03A(2) and 7.03A(3) will be added the following percentages:

Labor	-	24%
Materials	-	15%
Equipment Rental	-	15%

It is understood labor, materials, and equipment may be furnished by the Contractor or by the subcontractor or by others on behalf of the Contractor.

When extra work paid for on a force account basis is performed by forces other than the Contractor's organization, the Contractor shall reach agreement with such other forces as to the distribution of the payment made by the District for such work and no additional payment therefor will be made by the District.

7.03A(1) Labor - The Contractor will be paid the cost of labor for the workmen used in the actual and direct performance of the work. The cost of labor, whether the employer is the Contractor, subcontractor, or other forces, will be the sum of the following:

7.03A(1a) Actual Wages - The actual wages paid will be as published by the Director of Industrial Relations of the State of California for the region where work is performed and that are in effect at the time of award of the contract. The classification of workmen used shall not be in excess of the industry standard for the region where work is performed. Copies of the published labor rates are on file at the District office.

7.03A(1b) Labor Surcharge - To the actual wages as defined in Section 7.03A(1a), will be added a labor surcharge set forth in the Special Provisions, which labor surcharge shall constitute full compensation for all payments imposed by State and Federal laws and for all other payments made to, or on behalf of, the workmen, other than actual wages as defined in Section 7.03A(1a) and subsistence and travel allowance as specified in Section 7.03A(1c).

7.03A(1c) Subsistence and travel allowance paid to such workmen as required by collective bargaining agreements.

7.03A(2) Materials - The cost of materials incorporated in the work will be the cost to the purchaser, whether Contractor, subcontractor or other forces, from the supplier thereof, except as the following are applicable:

7.03A(2a) If a cash or trade discount by the actual supplier is offered or available to the purchaser, it shall be credited to the District notwithstanding the fact that such discount may not have been taken.

7.03A(2b) If the materials are procured by the purchaser by any method which is not a direct purchase from and a direct billing by the actual supplier to such purchaser, the cost of such materials shall be deemed to be the price paid to the actual supplier as determined by the Engineer. No markup except for actual costs incurred in the handling of such materials will be permitted.

7.03A(2c) If the materials are obtained from a supply or source owned wholly or in part by the purchaser, payment therefor will not exceed the price paid by the purchaser for similar materials furnished from said source on contract items or on the current wholesale price for such materials delivered to the job site whichever price is lower.

7.03A(2d) If the cost of such materials is, in the opinion of the Engineer, excessive, then the cost of such materials shall be deemed to be the lowest current wholesale price at which such materials are available in the quantities concerned delivered to the job site, less any discounts as provided in Section 7.03A(2a).

7.03A(2e) If the Contractor does not furnish satisfactory evidence of the cost of such materials from the actual supplier thereof, the cost shall then be determined in accordance with Section 7.03A(2d).

The District reserves the right to furnish such materials as it deems advisable, and the Contractor shall have no claims for costs and profit on such materials.

7.03A(3) Equipment Rates - The Contractor will be paid for the use of equipment at the rental rates listed for such equipment in the Special Provisions, regardless of ownership and any rental or other agreement, if such may exist, for the use of such equipment entered into by the Contractor. If it is deemed necessary by the Engineer to use equipment not listed in the Special Provisions, a suitable rental rate for such equipment will be established by the Engineer. The Contractor may furnish any cost data which might assist the Engineer in the establishment of such rental rate.

The rental rates paid as above provided shall include the cost of fuel, oil, lubrication, supplies, necessary attachments, repairs and maintenance of any kind, depreciation, storage, insurance, and all incidentals.

Operators will be paid for as provided under Section 7.03A(1).

All equipment shall, in the opinion of the Engineer, be in good working condition and suitable for the purpose for which the equipment is to be used.

Unless otherwise specified, manufacturer's ratings and manufacturer approved modifications shall be used to classify equipment for the determination of applicable rental rates. Equipment which has no direct power unit shall be powered by a unit of at least the minimum rating recommended by the manufacturer.

Individual pieces of equipment or tools having a replacement value of \$25.00 or less, whether or not consumed by use, shall be considered to be small tools and no payment will be made therefor.

Rental time will not be allowed while equipment is inoperative due to breakdowns.

In computing the rental time of equipment, less than 30 minutes shall be considered ½ hour.

7.03A(3a) Equipment on the Work - The rental time to be paid for equipment on the work shall be the time the equipment is in operation on the extra work being performed, and in addition, shall include the time required to move the equipment to location of the extra work and return it to the original location or to another location requiring no more time than that required to return it to its original location, except that moving time will not be paid for if the equipment is used at the site of the extra work on other than such extra work. Loading and transporting costs will be allowed, in lieu of moving time, when the equipment is moved by means other than its own power, except that no payment will be made if the equipment is used at the site of the extra work on other than such extra work.

7.03A(3b) Equipment not on the Work - For the use of equipment moved in on the work and used exclusively for extra work paid for on a force account basis, the Contractor will be paid the rental rates listed in the Special Provisions or as agreed to as provided in Section 7.03A(3) and for the cost of transporting the equipment to the location of the work and its return to its original location, all in accordance with the following provisions:

(1) The original location of the equipment to be hauled to the location of the work shall be agreed to by the Engineer in advance.

(2) The District will pay the costs of loading and unloading such equipment.

(3) The cost of transporting equipment on low bed trailers shall not exceed the hourly rates charged by established haulers.

(4) The cost of transporting equipment shall not exceed the applicable minimum established rates of the Public Utilities Commission.

(5) The rental period shall begin at the time the equipment is unloaded at the site of the extra work, shall include each day that the equipment is at the site of the extra work, excluding Saturdays, Sundays, and legal holidays unless the extra work is performed on such days, and shall terminate at the end of the day on which the Engineer directs the Contractor to discontinue the use of such equipment. The rental time to be paid per day will be in accordance with the following:

<u>Hours Equipment is in Operation</u>	<u>Hours to be Paid</u>
0.....	4
0.5.....	4.25
1.....	4.5
1.5.....	4.75
2.....	5
2.5.....	5.25
3.....	5.5
3.5.....	5.75
4.....	6
4.5.....	6.25
5.....	6.5
5.5.....	6.75
6.....	7
6.5.....	7.25
7.....	7.5
7.5.....	7.75
8.....	8
Over 8.....	hours in operation

When hourly rates are listed, less than 30 minutes of operation shall be considered to be 1/2 hour of operation.

When daily rates are listed, payment for 1/2 day will be made if the equipment is not used. If the equipment is used, payment will be made for one day.

The minimum rental time to be paid for the entire rental period on an hourly basis shall not be less than 8 hours or if on a daily basis shall not be less than one day.

(6) Should the Contractor desire the return of the equipment to a location other than its original location, the District will pay the cost of transportation in accordance with the above provisions, provided such payment shall not exceed the cost of moving the equipment to the work.

(7) Payment for transporting, loading and unloading equipment, as above provided, will not be made if the equipment is used on the work in any other way than upon extra work paid for on a force account basis.

7.03B Work Performed by Special Forces or Other Special Services - When the Engineer and the Contractor, by agreement, determine that a special service or an item of extra work cannot be performed by the forces of the Contractor or those of any of his subcontractors, such service or extra work item may be performed by a specialist. Invoices for such service or item of extra work on the basis of the current market price thereof may be accepted without complete itemization of labor, material, and equipment rental costs when it is impracticable and not in accordance with the established practice of the special service industry to provide such

complete itemization. In those instances wherein a Contractor is required to perform extra work necessitating a fabrication or machining process in a fabrication or machine shop facility away from the job site, the charges for that portion of the extra work performed in such facility may, by agreement, be accepted as a specialist billing.

To the specialist invoice price, less a credit to the District for any cash or trade discount offered or available, whether or not such discount may have been taken, will be added 15% in lieu of the percentages provided in Section 7.03A.

7.03C Records - The Contractor shall maintain his records in such a manner as to provide a clear distinction between the direct costs of extra work paid for on a force account basis and the costs of other operations.

The Contractor shall furnish the Engineer report sheets in duplicate of each day's extra work paid for on a force account basis no later than the working day following the performance of said work. The daily report sheets shall itemize the materials used, and shall cover the direct cost of labor and the charges for equipment rental, whether furnished by the Contractor, subcontractor, or other forces, except for charges described in Section 7.03B. The daily report sheets shall provide names or identifications and classifications of workmen, the hourly rate of pay and hours worked, and also the size, type and identification number of equipment, and hours operated.

Material charges shall be substantiated by valid copies of vendor's invoices. Such invoices shall be submitted with the daily report sheets, or if not available, they shall be submitted with subsequent daily report sheets. Should said vendor's invoices not be submitted within 15 days after acceptance of the work, the District reserves the right to establish the cost of such materials at the lowest current wholesale prices at which said materials are available in the quantities concerned delivered to the location of the work, less any discounts provided in Section 7.03A(2a).

Said daily report sheets shall be signed by the Contractor or his authorized agent.

The Engineer will compare his records with the daily report sheets furnished by the Contractor, make any necessary adjustments, and compile the costs of work paid for on a force account basis on daily extra work report forms furnished by the District. When these daily extra work reports are agreed upon and signed by both parties, they shall become the basis of payment for the work performed, but shall not preclude subsequent adjustment based on a later audit.

The Contractor's cost records pertaining to work paid for on a force account basis shall be open to inspection or audit by representatives of the District, during the life of the contract and for a period of not less than 18 months after the date of acceptance thereof, and the Contractor shall retain such records for that period. Where payment for materials or labor is based on the cost thereof to forces other than the Contractor, the Contractor expressly guarantees that the cost records of such other forces shall be open to inspection and audit by representatives of the District on the same terms and conditions as the cost records of the Contractor. If an audit is to be commenced more than 60 days after the acceptance date of the contract, the Contractor will be given a reasonable notice of the time when such audit is to begin.

7.03D Payment as provided above in Sections 7.03A and 7.03B shall constitute full compensation to the Contractor for performance of work paid for on a force account basis and no additional compensation will be allowed therefor.

7.04 ACCEPTANCE

The work shall be inspected for acceptance by the Engineer promptly upon receipt of notice in writing from the Contractor that the work is ready for such inspection.

The structures will not be finally accepted until the completion of the entire work under the contract.

7.05 DEDUCTIONS FROM PAYMENTS

The Riverside County Flood Control and Water Conservation District, by and through the Board of Supervisors or other appropriate District officer or officers, may at its option and at any time retain out of any amounts due the Contractor sums sufficient to cover any unpaid claims, provided that sworn statements of said claims shall have been filed in the office of the District or in the office of any other District officer or officers having jurisdiction thereover.

7.06 PARTIAL PAYMENTS

On or about the last day of each month, the Engineer shall make an estimate in writing of the total amount of work done by the Contractor to the time of such estimate and the value thereof. The District shall retain 5% of such estimated value of the work done as part security for the fulfillment of the contract by the Contractor. At no time shall the amount retained by the District be less than 5% of the total value of the work completed at the time such payments are made.

After deducting all previous payments and all sums to be kept or retained under the provisions of the contract, the District shall make monthly progress payments to the Contractor. No such estimate or payment shall be required to be made when, in the judgment of the Chief Engineer, the work is not proceeding in accordance with the provisions of the contract.

In accordance with Public Contract Code Section 22300 and other applicable law, the Contractor may substitute securities for any monies withheld to ensure performance under the contract. Such substitution shall be made only upon a separate agreement between the District and the Contractor which contains terms and conditions in compliance with all laws applicable to monies withheld under the contract.

7.07 DELAYED PAYMENTS

All the monies due the Contractor under the contract will be paid by demand on the Treasurer of the District, prepared and approved as required by law, and it is understood that any delay in the preparation, approval and payment of these demands will not constitute a breach of contract on the part of the District.

7.08 FINAL PAYMENT

The Engineer, after the completion of the contract, shall make a final estimate in writing to the Board of Supervisors of the amount of work done thereunder, and the value of such work, and the District shall pay the entire sum so found to be due after deducting therefrom all previous payments and all amounts to be kept and all amounts to be retained under the provisions of the contract. All prior partial estimates and payment shall be subject to correction in the final estimate and payment. The final payment shall not be due and payable until the expiration of 45 days from the date of acceptance of the work by the Board of Supervisors.

It is mutually agreed between the parties to the contract that no certificate given or payments made under the contract, except the final payment, shall be conclusive evidence of the performance of the contract, either wholly or in part against any claim of the party of the first part, and no payment shall be construed to be an acceptance of any defective work or improper materials.

And the Contractor further agrees that the payment of the final amount due under the contract, and the adjustment and payment for any work done in accordance with any alterations of the same, shall release the Riverside County Flood Control and Water Conservation District, the Board of Supervisors, and the Engineer from any and all claims or liability on account of work performed under the contract or any alteration thereof.

7.09 CLAIMS RESOLUTION - CLAIMS UP TO \$375,000

In accordance with Public Contract Code Section 20104 - 20104.8 and other applicable law, public works claims of \$375,000 or less which arise between the Contractor and the District shall be resolved following the statutory procedure.

1. All claims shall be submitted in writing and accompanied by substantiating documentation. Claims must be filed on or before processing of the final payment unless other notice requirements are provided in the contract. "Claim" means a separate demand by the claimant for (1) a time extension, (2) payment of money or damages arising from work done by or on behalf of the claimant and payment of which is not otherwise expressly provided for or the claimant is not otherwise entitled, or (3) an amount the payment of which is disputed by the District.

(a) Claims under \$50,000. The District shall respond in writing to the claim within 45 days of receipt of the claim, or, the District may request, in writing, within 30 days of receipt of the claim, any additional documentation supporting the claim or relating to defenses or claims the District may have against the claimant. If additional information is needed thereafter, it shall be requested and provided upon mutual agreement of the District and the claimant. The District's written response shall be submitted 15 days after receiving the additional documentation, or within the same period of time taken by the claimant to produce the additional information, whichever is greater.

(b) Claims over \$50,000 but less than or equal to \$375,000. The District shall respond in writing within 60 days of receipt, or, may request in writing within 30 days of receipt of the claim, any additional documents supporting the claim or relating to defenses or claims the

District may have against the claimant. If additional information is needed thereafter, it shall be requested and provided pursuant to mutual agreement between the District and the claimant. The District's response shall be submitted within 30 days after receipt of the further documents, or within the same period of time taken by the claimant to produce the additional information or documents, whichever is greater.

2. If the claimant disputes the District's response, or if the District fails to respond within the statutory time period, the claimant may so notify the District within 15 days of the receipt of the District's response or within 15 days of the District's failure to respond within the time prescribed, and demand an informal conference to meet and confer for settlement of the issues in dispute. Upon such demand, the District shall schedule a meet and confer conference within 30 days for settlement of the dispute.

3. If following the meet and confer conference, the claim or any portion thereof remains in dispute, the claimant may file a claim pursuant to Government Code § 900 et seq. and Government Code § 910 et seq. For purposes of those provisions, the time within which a claim must be filed shall be tolled from the time the claimant submits the written claim until the time the claim is denied as a result of the meet and confer process, including any time utilized for the meet and confer conference.

4. If a civil action is filed to resolve any claim, the provisions of Public Contract Code § 20104.4 shall be followed, providing for nonbinding mediation and judicial arbitration.

5. Location for Filing of Claims, Jurisdiction. Any legal action related to the performance of the work or the terms of the Contract Documents shall be filed only in the Superior Court of the State of California located in Riverside, California.

7.10 CLAIMS RESOLUTION - ALL CLAIMS (PUBLIC CONTRACT CODE SECTION 9204)

This section is intended to help resolve disputes between the parties related to this project. Such disputes shall be brought to the attention of the District at the earliest possible time, so that such disputes may be promptly resolved, if possible, or other appropriate action or investigation may be promptly undertaken. Claims must be filed on or before the date of final payment as required in Public Contract Code Section 20104.2. Public works claims which arise between the Contractor and the District shall be resolved using the following procedure:

A "claim" means a separate demand by the Contractor sent by registered mail or certified mail return receipt requested for one or more of the following: (a) a time extension including, without limitation, for relief from damages or penalties for delay assessed by the District; (b) payment by the District of money or damages arising from work done by or on behalf of the Contractor and payment for which is not otherwise expressly provided or to which the Contractor is not otherwise entitled; (c) payment of an amount that is disputed by the District. The Contractor shall furnish reasonable documentation to support the claim.

A. Form and Contents of Claim(s)

The Contractor shall furnish reasonable documentation to support the Claim, which shall be sent by registered mail or certified mail with return receipt requested to the District at the address provided herein this Section 7.10. The Contractor's written Claim must include, but not limited to, the following:

- 1) A statement to identify that it is a Claim under this Section 7.10, on a company letterhead, and a request for a decision on the Claim;
- 2) A detailed description or narrative of pertinent events, act, error, omission, unforeseen condition, event or other circumstance giving rise to the Claim;
- 3) Citation to contract provisions;
- 4) Theory of entitlement that provides a detailed justification for any remedy or relief sought by the Claim. This includes, but not limited to: a detailed cost breakdown, invoices, material tickets, staff logged time, summary of quantities, other cost records and total cost calculations;
- 5) Complete pricing of all cost impacts;
- 6) A time impact analysis of all time delays that shows actual time impact on the critical path; and
- 7) Documentation, District letters, notifications, related drawings and photos supporting items (1) through (6).

The Claim must be verified under penalty of perjury by Contractor's project superintendent as to the Claim's accuracy, and shall be priced like a Change Order, and must be updated at regular intervals as to cost and entitlement if a continuing Claim. Routine contract materials, for example, correspondence, RFI, Change Order requests, or payment requests shall not constitute a Claim. Contractor shall bear all costs incurred in the preparation and submission of a Claim.

Claims and support documentation related must be sent to:

Mr. Claudio M. Padres
Chief of Design and Construction Division
Riverside County Flood Control
and Water Conservation District
1995 Market Street
Riverside, CA 92501

B. Claims Procedure

- 1) Upon receipt of a Claim and the supporting documentation, the District shall conduct a reasonable review of the Claim and within 45 days, or an extended period as may be set by mutual agreement of the District and Contractor, provide the Contractor with a written statement identifying what portion of the Claim is still disputed and what portion is undisputed.
- 2) Notwithstanding the time period set forth in B.1) above, if the District needs approval from the Board of Supervisors to provide the Contractor with a

written statement identifying the disputed portion and the undisputed portion of the Claim, and the Board of Supervisors does not meet within the 45 days or within the mutually agreed to extension of time following receipt of the Claim, the District shall have up to three (3) days following the next duly publicly noticed meeting of the Board of Supervisors after the forty-five (45) day period, or extension, expires to provide Contractor a written statement identifying the disputed portion and the undisputed portion of the Claim.

- 3) Any payment due on the undisputed portion of the Claim under this section shall be processed and made within 60 days after the District issues its written statement. Amounts not paid in a timely manner as required by this Section 7.10 shall bear interest at 7% per annum. If the District fails to issue a written statement, the Claim shall be deemed rejected in its entirety. Failure by the District to respond to a claim from a Contractor within the time periods described in this subdivision or to otherwise meet the time requirements of this section shall result in the claim being deemed rejected in its entirety. A Claim that is denied by reason of the District's failure to have responded to the Claim, or its failure to otherwise meet the time requirements of this section, shall not constitute an adverse finding with regard to the merits of the Claim or the responsibility or qualifications of the Contractor.
- 4) If the Contractor disputes the District's written response, or if the District fails to respond within the time prescribed, the Contractor may demand in writing, sent by registered mail or certified mail return receipt requested, an informal meet and confer conference for settlement of the portion of the Claim in dispute. Upon receipt of the demand, the District shall schedule a meet and confer conference within 30 days.
- 5) Within 10 business days following the conclusion of the meet and confer conference, if the Claim or any portion thereof remains in dispute, the District shall provide the Contractor a written statement identifying the portion of the Claim that remains in dispute and the portion that is undisputed. Any payment due on an undisputed portion shall be processed and made within 60 days after the District issues its written statement. Any disputed portion of the Claim, as identified by the Contractor in writing, shall be submitted to nonbinding mediation, with the District and Contractor sharing the associated costs equally. The District and Contractor shall mutually agree to a mediator within 10 business days after the disputed portion of the Claim has been identified in writing. If the parties cannot agree upon a mediator, each party shall select a mediator and those mediators shall select a qualified neutral third party to mediate with regard to the disputed portion of the Claim. Each party shall bear the fees and costs charged by its respective mediator in connection with the selection of the neutral mediator.

- 6) For purposes of this section, mediation includes any nonbinding process, including but not limited to, neutral evaluation or a dispute review board, in which an independent third party or board assists the parties in dispute with resolution through negotiation or by issuance of an evaluation. Any mediation utilized shall conform to the timeframes in this section. Unless otherwise agreed to by the District and the Contractor in writing, the mediation conducted pursuant to this Section 7.10 shall excuse any further obligation under Section 20104.4 of the Public Contract Code to mediate after litigation has been commenced.
- 7) If mediation is unsuccessful to resolve all issues, the parts of the Claim remaining in dispute shall be subject to applicable procedures outside of this section and the requirements of Public Contract Code § 9204. The Claim resolution procedures in this Section do not preclude the District from requiring arbitration of disputes under private arbitration or the Public Works Contract Arbitration Program, if mediation under this Article does not resolve the parties' dispute.
- 8) Following the procedures set forth in this Section 7.10, including the mediation, if the Claim or any portion of it remains in dispute, the Contractor may file a Claim as provided in Chapter 1 (commencing with § 900) and Chapter 2 (commencing with § 910) of Part 3 of Division 3.6 of Title 1 of the Government Code.
- 9) If the Government Code claim is denied, Contractor may file an action in court. If a civil action is filed to resolve any claim, such action shall be subject to the provisions of Public Contract Code Sections 9204 or 20104.4 and shall be followed, providing for non-binding mediation and judicial arbitration. This Section applies only to claims subject to Public Contract Code Sections 9204 or 20104. If a claim is not subject to Public Contract Code Sections 9204 or 20104, the Contractor's right to file a civil action shall be as otherwise provided by law.

C. Subcontractor Claim(s)

If a subcontractor or a lower tier subcontractor has a Claim, the Contractor may present to the District a Claim on behalf of a subcontractor or lower tier subcontractor. A subcontractor may request in writing, either on his or her own behalf or on behalf of a lower tier subcontractor, that the Contractor present a Claim for work which was performed by the subcontractor or by a lower tier subcontractor on behalf of the subcontractor. The subcontractor requesting that the Claim be presented to the District shall furnish reasonable documentation as set forth in Section 7.10 to support the Claim. Within 45 days of receipt of this written request, the Contractor shall notify the subcontractor in writing as to whether the Contractor presented the Claim to the District, and if the Contractor did not present the Claim, provide the subcontractor with a statement of the reasons for not having done so.

D. Consistency with Public Contract Code Sections 9204 and 20104

If any Claim(s) arising under this Contract is subject to the provisions of Public Contract Code Sections 9204 or 20104 et seq. (Div. 2, Part 3, Chapter 1, Article 1.5), and if provisions of those statutory sections require a procedure or procedural element different from that established in this Contract, then the provisions of those statutory sections shall apply in place of the conflicting procedure or procedural element established herein.

E. Any legal action related to the performance of the work or the terms of the Contract Documents shall be filed only in the Superior Court of the State of California located in Riverside, California.

SECTION VIII - GENERAL

8.01 COOPERATION BETWEEN CONTRACTORS

The Contractor shall be required to cooperate fully with all utility and public agency representatives engaged in construction, relocation, altering or otherwise rearranging any facilities interfering with the progress of the work.

Full compensation for any delay or inconvenience to the Contractor's operation due to such operations as described above shall be considered included in the unit price paid for other items of work and no additional allowance will be made therefor.

8.02 INSURANCE - INDEMNIFICATION/HOLD HARMLESS/DEFEND

1. Insurance.

Contractor shall not commence work under this contract until he has obtained the insurance required hereunder and satisfactory proof of said insurance has been submitted to District and has been approved as to form by Riverside County Counsel.

Without limiting or diminishing the Contractor's obligation to indemnify, defend or hold the District harmless, Contractor shall procure and maintain or cause to be maintained, at its sole cost and expense, the following insurance coverages during the term of this Contract. In respects to the requirements for the Project and as further described in this section, the District herein refers to the Riverside County Flood Control and Water Conservation District, the County of Riverside, its Agencies, Districts, Special Districts and Departments, and any municipal corporation or governmental entity in which the work is to be accomplished, their respective directors, officers, Board of Supervisors, governing boards or councils, employees, elected and appointed officials, agents, representatives as Additional Insured.

Workers' Compensation - If the Contractor has employees as defined by the State of California, the Contractor shall maintain statutory Workers' Compensation Insurance (Coverage A) as prescribed by the laws of the State of California. Policy shall include Employers' Liability (Coverage B) including Occupational Disease with limits not less than **\$1,000,000** per person per accident. The policy shall be endorsed to waive subrogation in favor of the District and County of Riverside.

Commercial General Liability - Commercial General Liability insurance coverage, including but not limited to, premises liability, contractual liability, products and completed operations liability, personal and advertising injury, cross liability coverage, and covering claims which may arise from or out of Contractor's performance of its obligations hereunder. Policy shall name the District, all Agencies, Districts, Special Districts, and Departments of the County of Riverside, together with their respective directors, officers, Board of Supervisors, employees, elected or appointed officials, agents or representatives as Additional Insureds. Policy's limit of liability shall not be less than **\$2,000,000** per occurrence combined single limit. If such insurance contains a general aggregate limit, it shall apply separately to this agreement or be no less than two (2) times the occurrence limit.

Vehicle Liability - If Contractor's vehicles or mobile equipment are used in the performance of the obligations under this Agreement, then Contractor shall maintain liability insurance for all owned, non-owned or hired vehicles so used in an amount not less than **\$1,000,000** per occurrence combined single limit. If such insurance contains a general aggregate limit, it shall apply separately to this agreement or be no less than two (2) times the occurrence limit. Policy shall name the District, all Agencies, Districts, Special Districts, and Departments of the County of Riverside, together with their respective directors, officers, Board of Supervisors, employees, elected or appointed officials, agents or representatives as Additional Insureds.

Builder's Risk - Contractor shall obtain, at Contractor's expense, and keep in effect until final acceptance by the District, Builder's Risk Insurance (including earthquake and flood) covering the real and personal property of others in the care, custody, and control of the Contractor. Builder's Risk Insurance shall include theft and damage coverage. The minimum amount of coverage to be carried shall be equal to the full amount of the contract. Contractor shall be financially responsible for any deductible applied to loss. This insurance shall include the District, County of Riverside, the Contractor and its subcontractors as their interests may appear.

Professional Liability - Contractor shall maintain Professional Liability Insurance providing coverage for the Contractor's performance of work included within this Agreement, with a limit of liability of not less than \$2,000,000 per occurrence and \$4,000,000 annual aggregate. If Contractor's Professional Liability Insurance is written on a claims made basis rather than an occurrence basis, such insurance shall continue through the term of this Agreement and Contractor shall purchase at his sole expense either 1) an Extended Reporting Endorsement (also, known as Tail Coverage); or 2) Prior Dates Coverage from new insurer with a retroactive date back to the date of, or prior to, the inception of this Agreement; or 3) demonstrate through Certificates of Insurance that Contractor has Maintained continuous coverage with the same or original insurer. Coverage provided under items; 1), 2), or 3) will continue as long as the law allows.

Pollution and Asbestos Liability - If hazardous material is encountered during construction, the Project Manager must be notified immediately, and if any work is done to remove it, any Contractor performing work shall obtain and keep in effect during the term of their contract with Contractor, Pollution Liability Insurance, including Asbestos Liability Insurance, covering the subcontractor's liability for bodily injury, property damage, and environmental damage resulting from "sudden accidental" or "gradual" pollution and related cleanup costs incurred by the subcontractor, all arising out of the work or services (including the transportation risk, when applicable) to be performed under this contract. Combined single limit per occurrence shall not

be less than \$2,000,000, or the equivalent. Annual aggregate limit shall not be less than \$4,000,000.

If the Contractor maintains broader coverage and/or higher limits than the minimums shown above, the District requires and shall be entitled to the broader coverage and/or higher limits maintained by the Contractor. Any available insurance proceeds in excess of the specified minimum limits of insurance and coverage shall be available to the District.

General Insurance Provisions - All lines -

a) Any insurance carrier providing insurance coverage hereunder shall be admitted to the State of California and have an A.M. Best rating of not less than A: VIII (A:8) unless such requirements are waived, in writing, by the District Risk Manager. If the District's Risk Manager waives a requirement for a particular insurer such waiver is only valid for that specific insurer and only for one policy term.

b) The Contractor's insurance carrier(s) must declare its insurance deductibles or self-insured retentions. If such deductibles or self-insured retentions exceed \$500,000 per occurrence such deductibles and/or retentions shall have the prior written consent of the District's Risk Manager before the commencement of operations under this Agreement. Upon notification of deductibles or self-insured retentions unacceptable to the District, and at the election of the District's Risk Manager, Contractor's carriers shall either, 1) reduce or eliminate such deductibles or self-insured retentions as respects this Agreement with the District, or 2) procure a bond which guarantees payment of losses and related investigations, claims administration, and defense costs and expenses.

c) Contractor shall cause Contractor's insurance carrier(s) to furnish the District with either 1) a properly executed original Certificate(s) of Insurance and certified original copies of Endorsements effecting coverage as required herein, or 2) if requested to do so orally or in writing by the District's Risk Manager, provide original certified copies of policies including all Endorsements and all attachments thereto, showing such insurance is in full force and effect. Further, said Certificate(s) and policies of insurance shall contain the covenant of the insurance carrier(s) that 30 days written notice shall be given to the District prior to any material modification, cancellation, expiration or reduction in coverage of such insurance. In the event of a material modification, cancellation, expiration, or reduction in coverage, this Agreement shall terminate forthwith, unless the District receives, prior to such effective date, another properly executed original Certificate of Insurance and original copies of endorsements or certified original policies, including all endorsements and attachments thereto evidencing coverages set forth herein and the insurance required herein is in full force and effect. Contractor ***shall not commence operations until the District has been furnished original Certificate(s) of Insurance and certified original copies of endorsements or policies of insurance including all endorsements and any and all other attachments as required in this Section. An individual authorized by the insurance carrier to do so on its behalf shall sign the original endorsements for each policy and the Certificate of Insurance.***

d) It is understood and agreed to by the parties hereto and the insurance company(s), that the Certificate(s) of Insurance and policies shall so covenant and shall be construed as primary insurance, and the District's insurance and/or deductibles and/or self-insured retentions or self-insured programs shall not be construed as contributory.

e) The District's Reserved Rights--Insurance. If, during the term of this Agreement or any extension thereof, there is a material change in the scope of services; or, there

is a material change in the equipment to be used in the performance of the scope of work (such as the use of aircraft or watercraft), the District reserves the right to adjust the types of insurance required under this Agreement and the monetary limits of liability for the insurance coverages currently required herein, if, in the District's Risk Manager's reasonable judgment, the amount or type of insurance carried by the Contractor has become inadequate.

f) Contractor shall pass down the insurance obligations contained herein to all tiers of subcontractors working under this Agreement.

g) The insurance requirements contained in this Agreement may be met with a program(s) of self-insurance acceptable to the District.

h) Said insurance must contain an endorsement that District, County of Riverside, and any municipal corporation or governmental entity in which the work is to be accomplished, are named as an additional insured as respects the work covered hereunder. Said insurance must not contain, as respects the work covered hereunder, any exclusions as to bodily injury or death or property damage arising out of blasting, explosion, or underground damage to wire, pipes, conduits, mains, sewers, tank tunnels or any similar property, i.e., the so-called "x c u" exclusions. The insurance certificate evidencing such insurance must affirmatively state that the insurance carrier(s) will give District 30 days written notice prior to cancellation of the insurance or a reduction in coverage; must state that the "x c u" exclusions are waived or do not exist in the policy(s); and that District, County of Riverside, and any municipal corporation in which the work is to be accomplished, are named as an additional insured as respects the work covered hereunder.

The cost of this insurance shall be included in the prices bid for the various items of work and no additional compensation will be made therefor.

2. Indemnification - Hold Harmless and Defend.

Contractor shall indemnify and hold harmless the District, County of Riverside, and any municipal corporation or governmental entity in which the work is to be accomplished, together with its Agencies, Districts, Special Districts and Departments, their respective directors, officers, Board of Supervisors, elected and appointed officials, employees, agents and representatives (individually and collectively hereinafter referred to as Indemnitees) from any liability whatsoever, based or asserted upon any acts, omissions or services of Contractor, its officers, employees, subcontractors, agents or representatives arising out of or in any way relating to this Contract, relating to or in any way connected with or arising from the accomplishment of the work, whether or not in furtherance of the work, including but not limited to property damage, bodily injury, or death or any other element of any kind or nature whatsoever arising from the performance of Contractor, its officers, employees, subcontractors, agents or representatives Indemnitors from this Contract. Contractor shall defend, at its sole expense, all costs and fees including, but not limited, to attorney fees, cost of investigation, defense and settlements or awards, the Indemnitees in any claim or action based upon such alleged acts or omissions.

With respect to any action or claim subject to indemnification herein by Contractor, Contractor shall, at their sole cost, have the right to use counsel of their own choice and shall have the right to adjust, settle, or compromise any such action or claim without the prior consent of the District; provided, however, that any such adjustment, settlement or compromise in no manner whatsoever limits or circumscribes Contractor's indemnification to Indemnitees as set forth herein.

Contractor's obligation hereunder shall be satisfied when Contractor has provided to District the appropriate form of dismissal relieving the Indemnitees from any liability for the action or claim involved.

The specified insurance limits required in this Agreement shall in no way limit or circumscribe Contractor's obligations to indemnify and hold harmless the Indemnitees herein from third party claims.

In the event there is conflict between this clause and California Civil Code Section 2782, this clause shall be interpreted to comply with Civil Code 2782. Such interpretation shall not relieve the Contractor from indemnifying the Indemnitees to the fullest extent allowed by law.

3. Obligations.

The obligations assumed by Contractor cover all obligations set forth in this Subsection and elsewhere in the Contract Documents, such as Subsections 5.01, 5.02, 5.05, 5.06, 5.08, 5.09, 5.10, 10.01, and 10.02.

8.03 PUBLIC UTILITIES

The locations of all pipelines, power lines, communication lines and other utility components known to District to exist within the limits of the work, are indicated on the drawings and may be the subject of a specific Special Provision(s). Size, location and characteristics of such utilities is based upon information made available to District - primarily from the owner of the utility in question. The exactness of such information is not guaranteed but may be assumed to have been accomplished with reasonable accuracy.

In addition to the drawings and any such provision regarding utilities, Contractor is under a duty to take into account the location of service laterals or other appurtenances which can be inferred from the presence of facilities such as buildings, meters and junction boxes in or about the limits of the work.

Unless otherwise directed by the Contract Documents, all existing utilities - where shown or described or not - shall be left in place and Contractor must conduct its operations so that such utilities are protected from damage at all times during the course of the work and the work must be accomplished so as to give such utilities proper protection and support upon completion of the work by Contractor.

If during the course of the work, Contractor discovers underground utility components not indicated in the drawings, the Special Provisions or elsewhere in the Contract Documents, Contractor must immediately notify, in writing, the Engineer and the utility company (public or private) involved, stating with exactness the condition found.

When Contractor encounters a utility not shown or described in the Contract Documents, Contractor shall cease all work which would disturb such utility and its support until given specific instructions as to how to proceed regarding such utility by Engineer. All work done by Contractor to protect existing utilities shown or described in the Contract Documents, or which can be

reasonably inferred from the presence of other visible facilities, is at Contractor's expense, the cost of which is deemed included in Contractor's Proposal to do the work.

Contractor's cost of locating, repairing damage not due to the failure of Contractor to exercise reasonable care, and removing or relocating utility components and facilities not indicated in the drawings, specifications or elsewhere in the Contract Documents with reasonable accuracy, shall be paid Contractor as Extra Work as provided in Subsection 2.07 and Subsection 7.03 of these General Provisions. Compensation for idle time of equipment shall be paid as provided in Section 8-1.07C, "Payment Adjustments", of the State Standard Specifications. No surcharge rates for equipment will be applied for idled equipment.

District may direct the Contractor to do such repair or relocation work as required. When such repair or relocation work is not elsewhere provided for in these Contract Documents, or reasonably inferred therefrom, a requirement of District that Contractor perform such work shall be compensated for as Extra Work pursuant to Subsections 2.07 and 7.03 of these General Provisions.

Contractor shall not be assessed liquidated damages for delay in completion of the project, if such delay is caused by failure of District, or the owner of the utility in question, to provide for removal or relocation of the utility involved.

8.04 PROTECTION OF EXISTING STREET FACILITIES

The Contractor shall be responsible for the protection of existing signs, fences, concrete curbs, gutters and other facilities which may be encountered. The replacement or repair of any facilities which the District deems necessary as a result of the Contractor's operations shall be done by the Contractor at his own expense and to the satisfaction of the Engineer.

Excavation within the street right of way shall be conducted in a manner to cause the least interruption to traffic. Where traffic must cross open trenches, the Contractor shall provide suitable bridges at street intersections and driveways. Hydrants under pressure, valve pipe covers, valve boxes, curb stop boxes, fire or police call boxes, or other utility controls shall be left unobstructed and accessible during construction.

8.05 DIVERSION AND CONTROL OF WATER

Unless otherwise provided in the Proposal, no separate payment will be made for diversion and control of surface or groundwater. All costs incidental to maintaining dry working areas shall be included in the unit prices paid for other items of work in the schedule.

8.06 DUST ABATEMENT

During the performance of all work included in the contract, the Contractor shall take the necessary precautions to save the District free and harmless from any loss or damage resulting from his operations that raise or produce dust in such amounts that will be objectionable, and/or cause damage to adjacent property or property owners.

The Contractor will be required to have a positive and continuous method of dust control which is satisfactory to the Engineer. The methods to be used for controlling dust in the construction area and along haul roads shall be approved by the Engineer prior to starting any of the work included in the contract. All costs incidental to dust control shall be included in the unit prices paid for other items of work in the schedule.

8.07 PROJECT SIGNS

The Contractor shall erect project signs at the locations designated by the Engineer.

No separate payment will be made for erecting the project signs and all costs in connection therewith will be considered a subsidiary obligation of the Contractor.

8.08 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK

The bidder shall examine carefully the site of the work contemplated, the plans and specifications, and the proposal and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and scope of work to be performed, the quantities of materials to be furnished, and as to the requirements of the proposal, plans, specifications, and the contract.

Where the District has made investigations of subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, such investigations are made only for the purpose of study and design. Where such investigations have been made, bidders or Contractors may, upon request, inspect the records of the District as to such investigations subject to and upon the conditions hereinafter set forth. Such inspection of records may be made at the office of the District.

The records of such investigations are not a part of the contract and are shown solely for the convenience of the bidder or Contractor. It is expressly understood and agreed that the District assumes no responsibility whatsoever in respect to the sufficiency or accuracy of the investigations thus made, the records thereof, or of the interpretations set forth therein or made by the District in its use thereof and there is no warranty or guarantee, either expressed or implied, that the conditions indicated by such investigations or records thereof are representative of those existing throughout such areas, or any part thereof, or that unlooked-for developments may not occur, or that materials other than, or in proportions different from those indicated, may not be encountered.

When a log of test borings showing a record of the data obtained by the District's investigation or subsurface conditions is included with the contract plans, it is expressly understood and agreed that said log of test borings does not constitute a part of the contract, represents only the opinion of the District as to the character of the materials encountered by it in its test borings, is included in the plans only for the convenience of bidders and its use is subject to all of the conditions and limitations set forth in this Section 8.08.

No information derived from such inspection of records of investigations or compilation thereof made by the District or from the Engineer, or his assistants, will in any way relieve the bidder or Contractor from any risk or from properly fulfilling the terms of the contract.

SECTION IX - WATERING

9.01 DESCRIPTION

This work shall consist of developing a water supply for all water required for the work. The application of the water shall be under the control of the Engineer at all times and shall be applied in the amounts and at the locations approved by the Engineer.

At least one mobile unit of at least 1,000-gallon capacity for applying water shall be available on the project at all times.

Water for compacting embankment material and for laying dust shall be applied by means of pressure-type distributors or pipelines equipped with a spray system or hoses with nozzles that will ensure a uniform application of water.

No separate payment or additional allowances will be made for this work and all costs in connection therewith will be considered as included in other items in the schedule.

SECTION X - PUBLIC CONVENIENCE, TRAFFIC CONTROL AND DETOURS

10.01 GENERAL

The Contractor shall so conduct his operations as to offer the least possible obstruction and inconvenience to the public and he shall have under construction no greater length or amount of work than he can prosecute properly with due regard to the rights of the public.

Unless otherwise provided in the Special Provisions, all public traffic shall be permitted to pass through the work with as little inconvenience and delay as possible.

Spillage resulting from hauling operations along or across any public traveled way shall be removed immediately at the Contractor's expense.

Construction operations shall be conducted in such a manner as to cause as little inconvenience as possible to abutting property owners.

Convenient access to driveways, houses and buildings along the line of work shall be maintained and temporary approaches to crossings or intersecting highways shall be provided and kept in good condition.

10.02 SIGNS

It shall be the responsibility of the Contractor to provide and maintain all lights, barricades and signs, both on and off the site of work, as required by the Engineer, and all such devices shall be of a type approved by him.

If, in any case, the Engineer finds it necessary to replace, add to or erect said barricades, signs, or lights, when the Contractor fails to do so when informed, the Contractor shall be billed for all costs thereof including a daily rental fee for signs.

No separate payment, unless otherwise provided for under the Special Provisions, will be made for traffic control and detour signing and all costs incidental to these items shall be included in the unit prices paid for other items of work.

10.03 MATERIALS STORAGE

Storing or stockpiling of excavated material, imported backfill material or construction materials on any street or highway will not be permitted except as approved in writing by the Engineer.

SPECIAL PROVISIONS
AND
DETAILED SPECIFICATIONS

SPECIAL PROVISIONS

SECTION 1 - GENERAL

1.1 Drawings and Specifications - These documents are for the construction of **Jurupa-Pyrite MDP Line A-2, Stage 1**, located in the city of Jurupa Valley, Riverside County, California. This work shall conform with the contract drawings indexed on the cover sheet of the drawings included herewith.

Referenced standard drawings are available on the District web site.

The Contractor shall copy any of the referenced District standard drawings from <http://www.rcflood.org>.

The Contractor shall be responsible to obtain referenced standard plans/drawings of various agencies from their respective office or web site.

References made in these Special Provisions or Detailed Specifications to the "Greenbook Specifications" refer to the "Greenbook" Standard Specifications for Public Works Construction, current edition, including supplements. Standard Specifications of the American Society for Testing and Materials shall be designated by ASTM and the appropriate number of the standard. Unless otherwise specified, wherever the words "Caltrans Specifications" are used in these Special Provisions or Detailed Specifications they shall mean the Standard Specifications of the State of California, Department of Transportation, current edition. Whenever the words "Caltrans Standards" are used they shall mean the Standard Plans of the State of California, Department of Transportation, 2010 edition.

In the event that discrepancies are encountered, the option that provides the method, item or material with the greatest strength or utility shall be chosen, as directed by the Engineer.

In case of conflict between the drawings and the specifications, the drawings shall govern; in case of conflict between the referenced specifications and these specifications, the latter shall govern.

1.2 Submittals to District - Submittals shall be sent in the form of email or postal carrier to the attention of the Engineer. The Contractor shall allow the Engineer ten (10) working days from the time of receipt of the submittal (mailing time is not included) to review and respond in writing. The Contractor shall submit and obtain approvals for all required submittals identified within these specifications prior to the pre-construction meeting.

SECTION 2 - TIME OF COMPLETION, DAMAGES AND LEGAL HOLIDAYS

2.1 General - The Contractor shall begin work within ten (10) calendar days after the date of receipt of Notice to Proceed from the Engineer and shall diligently prosecute the same to completion before the expiration of

THIRTY (30) WORKING DAYS

from the date of receipt of Notice to Proceed.

2.2 Damages - The Contractor and the District expressly agree that the cost to the District for inspection and superintendence of the work for this contract is \$800.00 per working day.

2.3 Legal Holidays - The Contractor will not be permitted to work on Legal Holidays (Reference Sections 6.02 and 6.06 of the General Provisions), except in cases of emergency as directed by the Engineer.

SECTION 3 - FORCE ACCOUNT PAYMENT

3.1 Labor Surcharge - Attention is directed to the provisions of Section VII, Article 7.03A(1b) of the General Provisions. The labor surcharge percentage to be applied to the actual wages paid as defined in Paragraph 7.03A(1a) will be twenty-four percent (24%).

3.2 Equipment Rental - Attention is directed to the provisions of Section VII, Article 7.03A(3) of the General Provisions. The equipment rental rates to be applied will be the rates published by the California Department of Transportation and in effect at the time of the award of the contract. A copy of said Equipment Rental Rates is on file at the District Office.

SECTION 4 - PROTECTION OF EXISTING UTILITIES

4.1 General - All existing underground utility lines, power poles and overhead wiring shall be protected in place at all times, except as noted otherwise on the plans. Any damage to utilities caused by the Contractor's operation shall be repaired or replaced at the Contractor's expense.

Prior to the commencement of any construction activities, the Contractor shall contact all utility companies and local municipalities servicing the project area to review as-built utility drawings and determine appropriate means of protecting utilities.

At the discretion of the Engineer, the Contractor may be required to verify, by potholing, the location of potentially affected utilities.

4.2 Cooperation with Utilities Relocated by Others - Some utilities may require relocation by others during construction if Contractor is unable to protect the utility in place as shown on the drawings and as specified in these specifications and Special Provisions.

Supplement to Section 8.01 of the General Provisions. The Contractor shall coordinate and cooperate with the various utilities or their contractors to ensure the work proceeds in an orderly manner.

The Contractor shall stage his work as required to accommodate the following utility relocation should it be required:

Two Southern California Edison telephone lines at Station 10+57.61 and Station 10+73.32

Should any utility relocation result in delays to the Contractor's work schedule, the Contractor shall be entitled only to an equivalent extension of time for the completion of the contract, and shall not be entitled to damages due to downtime and idled equipment or additional payment over and above the agreed upon contract unit prices.

SECTION 5 - PROJECT SITE MAINTENANCE

Through all phases of construction, the Contractor shall comply with the provisions of Section 7-8 of the Greenbook Specifications. Before final acceptance of the work, the Contractor shall clean the work and the site of the work of all falsework, temporary structures, other construction materials and equipment, excess materials and rubbish, and shall leave the work and the site in a neat and presentable condition. Such final cleanup work shall be performed within the time specified for completion of all work.

SECTION 6 - SPECIAL REQUIREMENTS

6.1 National Pollutant Discharge Elimination System (NPDES) – The Contractor shall comply with the requirements of Board Order No. R8-2010-0033 (NPDES No. CAS618033), NPDES Area-Wide Municipal Stormwater Permit, hereafter referred to in this Section as the "Permit", issued by the California Regional Water Quality Control Board (CRWQCB) – Santa Ana Region. This Permit regulates stormwater discharges associated with construction activities performed under the direction of a municipal stormwater permittee. The Contractor shall prepare and implement a Pollution Prevention Plan (PPP) in accordance with Section 29 "Stormwater and Non-Stormwater Pollution Control" of the Detailed Specifications.

The Contractor's attention is directed to: 1) Section 29.2 "General Requirements" which allows the Engineer to withhold progress payments if the Contractor fails to fully implement Section 29 "Stormwater and Non-Stormwater Pollution Control" or is deemed to be in non-compliance with the provisions of the Permit; 2) Section 29.3 "Pollution Prevention Plan Preparation and Approval" which requires that a PPP be prepared and approved prior to the Pre-Construction meeting; and 3) Section 29.5 "Pollution Prevention Plan Implementation" which allows the Engineer to suspend construction operations if the Contractor fails to implement the approved PPP and any amendments thereto.

Throughout the term of this contract, the total soil-disturbed area of the project site shall be no more than 1 acre.

6.2 Sanitation - Sewage flows shall not be interrupted. Should the Contractor disrupt existing sewer facilities, sewage shall be conveyed in closed conduits and disposed of in a sanitary sewer system. If pumping is required it shall be done at the expense of the Contractor. A backup

pumping system with equal capacity shall be provided at all times. Sewage shall not be permitted to flow in trenches or be covered by backfill.

6.3 Heavy Equipment Working Hours - Heavy construction equipment shall be allowed to work from 7:00 a.m. to 3:30 p.m. each normal working day, unless otherwise approved by the Engineer.

6.4 Encroachment Permits - The Contractor is required to obtain an encroachment permit from the City of Jurupa Valley for work within City right of way. The City of Jurupa Valley will not require the Contractor to pay a fee for the encroachment permit. A copy of the encroachment permit shall be provided to the Engineer prior to commencement of work.

6.5 Toxic Material Disposal - Toxic materials including oil, fuel oil, gasoline, coolant, fluid filters and other contaminants shall not be discharged within the project site. All such materials shall be transported offsite and disposed of at a County approved facility.

6.6 Survey Crew - The Contractor shall notify the Engineer in writing at least 48 hours prior to new construction staking and shall provide safe and unobstructed access to the staking area within this period. Should the staking area be inadequately prepared, unsafe, or obstructed when the District's Survey Crew arrives onsite to perform the new construction staking, the Contractor shall be subjected to delay charges as defined below.

Survey Crews will be available Monday through Thursday from 7:00 a.m. to 3:30 p.m., with a half-hour off for lunch. If the Contractor requires the Survey Crew to work beyond the specified time mentioned above, it shall be considered as overtime and shall be paid by the Contractor at 1.5 times the Survey Crew's hourly rates.

The Contractor shall carefully preserve benchmarks, reference points, and stakes. In case of willful or careless destruction, the Contractor shall be charged with the resulting expense, and shall be responsible for any mistakes that may be caused by their unnecessary loss or disturbance.

If the District's Survey Crew incurs delays or survey re-staking is required as a result of the Contractor's operations, the Contractor shall be charged a rate of \$250/hour, with a minimum charge of two (2) hours for each re-staking request. Payment shall be deducted from the monthly progress payment.

6.7 Survey Monuments - The Contractor shall salvage and give to the District all survey monuments and wells removed during construction. The District will reset monuments after construction.

6.8 Job Trailer Site - The Contractor is required to provide a site and install an office trailer for District personnel. This trailer shall be in good condition and located in a place acceptable to the District. The trailer shall be for the sole use of the District and shall not be used by the Contractor for any activity, including storage. The Contractor shall make provisions for the privacy and security of the office, and provide air conditioning, drinking water, electrical service,

and a private portable toilet for the inspector. The Contractor shall also provide two office chairs and a desk suitable for reviewing plans. The Contractor shall pay the monthly billings for these services. The trailer shall be fully operational and available to District personnel on the first day of work. Should the trailer or office not be available and in working condition, it is agreed by both parties at the time of entering this contract that damages in the amount of \$3,000 per month shall be assessed. It is agreed that this amount may be prorated and shall be deducted from the first contract payment and any successive payments covering any period that the facilities are unavailable.

6.9 Construction Tolerances – Variation in alignment, grade and dimensions of the structures and structural components from the established alignment, grade and dimensions shown on the drawings shall be within the tolerances specified in the following:

Table A – Tolerances for Grading Unlined Channels, and Access Roads		
Departure from established alignment		2 inches on tangents 4 inches on curves
Departure from established profile grade	Channel bottoms, channel sideslopes in cut and fill, levee and access road sideslopes in cut	Zero <u>above</u> and 3 inches <u>below</u> the specified grade
	Top surfaces of levees and access roads in both cut and fill, levee and access road sideslopes in fill	Zero <u>below</u> and 3 inches <u>above</u> the specified grade

Regardless of the construction tolerances specified, the excavation and grading shall be performed so that the finished surfaces are in uniform planes with no abrupt breaks in the surface.

Table B - Tolerances for Concrete Swales		
Departure from established alignment		2 inches on tangents 4 inches on curves
Departure from established profile grade		1 inch
Variation in thickness of lining, sideslopes and invert		5 percent of specified thickness provided average thickness is maintained
Variation from specified width of section at any height		0.0025 times specified width W plus 1 inch. 0.0025W + 1 inch
Variation from specified height of lining		0.005 times specified height H plus 1 inch. 0.005H + 1 inch
Variation in surfaces (gradual)	Invert Sideslopes	¼ inch in 10 feet ½ inch in 10 feet
Variation in surfaces (abrupt)		¼ inch

Gradual Variation tolerance shall be measured by placing a 10-foot straightedge anywhere on the finished concrete structure within 72 hours after concrete placement. The gap at any point between the straightedge and the concrete shall not exceed the specified amount.

Table C - Tolerances for Formed, Cast-in-Place Concrete Structures		
Departure from established alignment		1 inch on tangents 2 inches on curves
Departure from established profile grade		1 inch
Inside dimensions		0.005 times specified dimension
Variation from the plumb or the specified batter in the lines and surfaces of walls, piers and in arises	Exposed, in 10 feet Backfilled, in 10 feet	½ inch 1 inch
Variation in cross-sectional dimensions		Minus ¼ inch Plus ½ inch
Variation in surfaces (gradual)	Invert Soffits, Walls, Sideslopes	¼ inch in 10 feet ½ inch in 10 feet
Variation in surfaces (abrupt)		¼ inch

Table D - Tolerances for Reinforcing Steel Placement		
Variance from indicated position	Spacing between adjacent bars and the distance between layers of bars	one bar diameter nor more than one inch
Concrete cover measured perpendicular to steel in the direction of tolerance		¼ inch

Elements not meeting these requirements shall be removed and replaced as directed by the Engineer.

6.10 Surplus Excavated Material - Any stockpiling, grading or disposal of material outside of the project limits is not covered under the District's permits and is the sole responsibility of the Contractor. Regulatory permits that may be required include, but are not limited to, Federal Clean Water Act (Sections 401 and 404), California Fish and Game Code (Section 1602) and Federal/State Endangered Species Acts. All costs to obtain these Regulatory Permits shall be borne by the Contractor.

6.11 Sewer Line Inspection - Prior to the commencement of construction, the Contractor is required to video record all sewer mains (8" diameter and larger) within the project limits. Additionally, the Contractor shall video record the sewer mains after the backfilling of the storm drain has been completed. Copies of the videotapes shall be provided to the Engineer. All costs associated with this requirement shall be included in the contract price bid for Clearing and Miscellaneous Work. The Contractor is required to replace and/or repair at his own expense, any sewers damaged or misaligned as a result of his construction activities.

6.12 Project Signs - Supplementing Section 8.07 of the General Provisions, the Contractor shall be required to provide two new project signs. The Contractor shall install and maintain the project signs at locations specified by the Engineer, with painting and lettering as shown in Appendix "B" of these Special Provisions. The signs shall be installed as directed by the Engineer within five (5) days after District issuance of the Notice to Proceed. Upon completion of construction, the signs shall be removed.

6.13 Liability Insurance - The Contractor's attention is directed to Section 8.02, Insurance - Indemnification/Hold Harmless/Defend, of the General Provisions. The City of Jurupa Valley shall also be named as additional insureds with the liability insurance coverage required to be maintained by the Contractor.

6.14 Accidental Discovery - In the event that any human remains, hazardous materials, historical, archaeological, or paleontological resources are accidentally discovered within project limits, the Contractor shall immediately cease all construction or ground disturbance activity in the vicinity of find and notify the Engineer. District will provide the appropriate professional to assess the significance of the discovery and, if necessary, develop appropriate management and treatment measures. **The Contractor shall not resume construction in the affected area without Engineer's approval.**

Per State Health and Safety Code 7050.5, if human remains are encountered during construction, no further disturbance shall occur until the Riverside County Coroner has made a determination of origin and disposition pursuant to Public Resources Code Section 5097.98. The Riverside County Coroner must be notified within 24 hours by the Engineer. If the County Coroner determines that the remains are not historic, but prehistoric, the Native American Heritage Commission (NAHC) must be contacted by the Engineer to determine the most likely descendent for this area. Once the most likely descendent is determined, treatment of the Native American human remains will proceed pursuant to Public Resources Code Section 5097.98. The NAHC may become involved with decisions concerning the disposition of the remains.

Should any of the above mentioned discoveries result in delays to the Contractor's work schedule, the Contractor shall be entitled only to an equivalent extension of time for the completion of the contract, and shall not be entitled to damages due to downtime and idle equipment or additional payments over and above the agreed upon contract prices.

6.15 Nesting Bird Pre-Construction Survey - The removal of potential nesting vegetation should be conducted outside of the nesting season to avoid impacts to active bird nests, if possible. The nesting season is defined as February 1st through September 15th. If vegetation must be removed during the nesting season, a nesting bird survey of potentially suitable nesting vegetation shall be conducted by the District prior to removal. Surveys will be conducted no more than three (3) days prior to scheduled removals. If active nests are identified, the District will establish a 150 to 500 foot buffer around the vegetation containing the active nest. The vegetation containing the active nest will not be removed, and no grading will occur within the established buffer, until it has been determined that the nest is no longer active (i.e., the juveniles are surviving independent from the nest). If clearing is not conducted within three (3) days of a negative survey, the nesting survey must be repeated to confirm the absence of nesting birds.

Should nesting birds result in delays to the Contractor's work schedule, the Contractor shall be entitled only to an equivalent extension of time for the completion of the contract, and shall not be entitled to damages due to downtime and idle equipment or additional payments over and above the agreed upon contract prices.

SECTION 7 AND SECTION 8 - NOT USED

SECTION 9 - PAYMENT

The contract prices shall include full compensation for all costs incurred under these Special Provisions and Detailed Specifications.

DETAILED SPECIFICATIONS

SECTION 10 - MOBILIZATION

10.1 Description - The contract item Mobilization shall consist of expenditures for all preparatory work and operations, including but not limited to, those costs necessary for the movement of personnel, equipment, supplies and incidentals to the project site; for the establishment of all offices, buildings, construction yards and other facilities necessary for work on the project; and for all other work and operations which must be performed or costs incurred prior to beginning work on the various contract items on the project site as well as the related demobilization costs anticipated at the completion of the project.

10.2 Payment - The amount credited for Mobilization on each monthly progress payment shall be equal to the total of the amounts credited for work on all the other contract items for that monthly progress payment, up to a cumulative limit of eighty percent (80%) of the lump sum price bid for Mobilization. The remaining twenty percent (20%) of the lump sum price bid for Mobilization will be paid with the final payment.

Payment of the lump sum contract price for Mobilization shall constitute full compensation for all labor, materials, equipment, and all other items necessary and incidental to completion of this item of work.

The deletion of work or the addition of extra work as provided for herein shall not affect the price paid for Mobilization.

SECTION 11 - WATER CONTROL

11.1 Description - This section covers the contract item Water Control. Watersheds and/or urban runoff areas are tributary to the project site at various locations, but do not necessarily follow the alignment of the project under current conditions. Surface water in varying quantities can be expected at any time of the year, and substantial runoff can be expected during periods of rainfall. All bidders shall make their own determination regarding what the surface and/or groundwater conditions will be at the time of construction, and their impact on the bidder's operations and construction phasing.

11.2 Water Control - The contract item Water Control includes the control and/or diversion of surface runoff as well as groundwater within the work area as required to complete the work. All work shall be carried on in areas free of water. Care should be exercised so that runoff or diversion flows do not erode, undermine or otherwise damage either facilities which have been constructed or adjacent private properties. The responsibility for the protection of all existing and proposed improvements lies with the Contractor.

11.3 Measurement and Payment - The methods of controlling both surface and groundwater will be the responsibility of the Contractor. The contract lump sum price paid for Water Control shall include full compensation for all direct and indirect costs incurred under this section, and

for doing all the work involved in controlling surface runoff and groundwater within the construction area, as specified in these Detailed Specifications, and as directed by the Engineer.

Payment will be made on a basis of the percentage of the work completed on the entire project.

SECTION 12 - TRAFFIC CONTROL

12.1 Description - The contract item Traffic Control shall include labor, flagmen, lights, barricades, signs, materials, temporary bridges and equipment necessary to ensure that the vehicular and pedestrian traffic conforms to requirements as set forth in this section and as shown on the drawings.

12.2 Notification of Agencies - The Contractor shall notify the following agencies a minimum of 48 hours in advance of start of any street work and inform them of the proposed construction schedule and provide any additional pertinent information they may request:

AT&T Telecommunications Company (Ronny Stewart)	951.354.5492
City of Jurupa Valley Police Department	951.955.2600
City of Jurupa Valley Public Works	951.332.6464
Jurupa Community Services District (Keith Backus)	951.685.7434
Jurupa Unified School District	951.360.4000
Riverside County Sheriff's Department	951.955.2400
Riverside County Transportation Department	951.955.6885
Southern California Edison	800.655.4555
The Gas Company	800.427.2200
Underground Service Alert	800.227.2600
United States Postal Service	951.727.8346
Waste Management	800.423-9986

The Contractor is not relieved of his responsibility of notifying the various departments and agencies mentioned above, even if their telephone numbers may have changed without notice.

The above agencies shall also be advised by the Contractor of any major change in the construction schedule that could restrict pedestrian or vehicular traffic.

The Contractor shall notify the public a minimum of ten (10) working days prior to start of road closure. The Contractor is also required to notify, in writing, the following as applicable: Fire Department, Sheriff, California Highway Patrol, local newspaper, trash pickup, school districts, Riverside Transit Agency, Post Master, UPS, colleges, local businesses, local residents, and state and local agencies involved, if affected.

12.3 Public Convenience and Access - The Contractor shall comply with the requirements of Section X of the General Provisions and shall provide continuous access to all private property.

Additional provisions shall be made as necessary to protect the public and accommodate traffic with a minimum of inconvenience.

Closures or partial closures of the traveled way implemented by the Contractor shall be related to actual work being performed at the time. Closures shall not be maintained if work is not being performed. If the existing closure is not essential to the type of work being performed at the time, the traveled way shall immediately be restored to a safe condition for public use.

The Contractor shall provide temporary bridge crossings for all driveway entrances to be closed to vehicular access for any period exceeding 4 hours.

Temporary bridges shall have a minimum width of 12 feet for residential driveways and 24 feet for business driveways, and shall be designed for an AASHTO H20 truck loading. Steel plates placed over the trench shall have a minimum thickness of 1.25" and the surface shall be roughened or coated to provide a non-skid surface. For spans greater than 4 feet, a structural design shall be prepared by a Registered Civil Engineer and submitted to the District for review and approval.

The Contractor shall notify each resident in writing 3 days in advance of excavating past the affected driveway entrance. Such notice shall contain the expected day and period of time (not to exceed 4 hours) that the driveway is to be out of service. A copy of each letter shall be submitted to the Engineer.

In addition, road closures shall not span more than three (3) weeks from the start of the road closure, unless otherwise approved by the City of Jurupa Valley. All work within street right of way shall be backfilled or steel plated at the end of each working day to restore residential access.

12.4 Construction Signs and Traffic Control Plans - All construction signs, barricades, delineators, etc., shall conform with the U.S. Department of Transportation, Federal Highway Administration, "Manual on Uniform Traffic Control Devices for Streets and Highways (MUTCD), Part 6, latest edition", and the MUTCD California Supplement, Part 6 along with the Uniform Sign Chart as shown on the drawing.

12.5 Flaggers - All personnel utilized as flaggers must be trained in the proper fundamentals of flagging and signaling.

12.6 Payment - The contract prices paid for Traffic Control shall include full compensation for all material and labor costs incurred under this section. Contractor is advised that traffic plans as shown on the drawings may be modified as field conditions require. No additional payment shall be made for modifications to the traffic plan.

This payment will be made on a basis of the percentage of work completed on the entire project.

SECTION 13 - CLEARING AND MISCELLANEOUS WORK

13.1 Description - This section covers the contract item Clearing and Miscellaneous Work as required for construction of the work. All objectionable materials shall be removed and disposed of outside of the limits of the construction easements and permanent rights of way.

13.2 Clearing and Miscellaneous Work - The contract item Clearing and Miscellaneous Work includes the removal and disposal of all vegetation, trees, roots, stumps, fences, pipes, all abandoned facilities, culverts, rocks, structures, concrete and asphalt excluding those items defined specifically as excavation in the appropriate section.

Included in this item are the following:

1. The Contractor shall leave all improved parkways undisturbed where possible. When this is impractical he shall reurf in kind, areas disturbed in the parkways including removing and replacing interfering portions of sprinkler systems. Sod shall be used to restore disturbed grass. All work is to be done to the satisfaction of the Engineer.
2. The temporary relocation of signs and mailboxes, and their reinstallation. Work involving mailboxes shall be coordinated with the Postal Service.
3. The removal and disposal of existing curb and gutter along the eastern side of Agate Street as shown on Sheet 2 and Sheet 7 on the drawings.
4. The removal and disposal of interfering portions of the existing CMP where directed by the Engineer and as shown on the plans approximately between Station 13+14 and Station 15+03.
5. The removal and disposal of the existing concrete V-ditch at the upstream end of the project at the terminus of Bellmore Street, located approximately between Station 15+03 and Station 15+55.
6. The removal and disposal of interfering trees, including any roots or stumps, along the project's alignment as directed by the Engineer.
7. The removal and disposal of interfering chain link fence as shown on the drawings and as directed by the Engineer.

Finally, included in this item are those types of work as shown on the drawings not specified for pay under any other individual contract item.

13.3 Payment - The contract price paid for Clearing and Miscellaneous Work shall be full compensation for all costs incurred under this section.

This payment will be made on a basis of the percentage of work completed on the entire project.

SECTION 14 - EARTHWORK

14.1 Description - This section covers the contract items Excavation; Street Reconstruction; and Backfill.

14.2 General Excavation Requirements - Access to trenches shall be in conformance with Section 306-1.1.4 and the manner of bracing excavations shall be in conformance with Section 306-1.1.6 of the Greenbook Specifications.

Excavation shall be kept to the minimum widths required for efficient placing and construction of the various concrete structures. The maximum length of open trench shall be in conformance with Section 306-1.1.2 of the Greenbook Specifications.

In excavating for surfaces against which concrete is to be placed, care shall be exercised in removing the final lift. The foundation for all concrete structures including concrete swales and sideslopes will be inspected and tested after excavation. The subgrade shall be ninety percent (90%) relative compaction prior to the placement of concrete. Surfaces against which concrete is to be placed shall be free of debris, mud or ponded water. If subgrade compaction is deficient, subgrade shall be scarified, moisture conditioned to or slightly above optimum moisture content, and the surface proof rolled to a minimum ninety percent (90%) relative compaction. Subgrade preparation will not be measured or paid separately and no additional compensation will be allowed unless overexcavation is directed by Engineer.

Material which will not provide a suitable foundation shall be removed and replaced with compacted select material as directed by the Engineer.

Any overexcavation shall be filled with select material compacted to ninety percent (90%) relative compaction and meeting the material requirements for backfill.

The Contractor shall remove slides and materials eroding into the work, and the slopes and grades refinished to original grades as specified.

The Contractor shall dispose of all surplus excavated material outside of the limits of the construction easements and permanent rights of way.

The removal of rock material from within the excavation paylines which requires the use of blasting or equipment beyond that normally necessary to accomplish the excavation (as determined by the Engineer) shall be paid for in accordance with Section VII, Article 7.03 of the General Provisions. The cost of removal and disposal (including trucking) of rock away from the jobsite will be paid for under the contract item Excavation and no additional compensation will be allowed.

Blasting, when necessary, as approved by the Engineer shall be in accordance with Section 19-2.03E of the Caltrans Specifications.

The Contractor's attention is directed to the General Provisions, Section V, Article 5.09 on the use of explosives and Article 5.11 in regard to unforeseen difficulties.

14.3 Excavation - The contract item Excavation covers the removal of all material including asphalt, aggregate base, abandoned pipelines and concrete from within the excavation paylines as specified, additional excavation and fill outside the proposed edge of pavement to catch existing grade, and as required for the construction and installation of the concrete swale earthen outlet, retaining walls, transitions, concrete aprons, cutoff walls, trench drain, and access road as shown on the standard drawings, and the disposal of all surplus material. All HMA and P.C.C. shall be sawcut unless otherwise specified.

14.4 Street Reconstruction - The contract item Street Reconstruction covers the excavation within the proposed edges of pavement, recompaction of existing subgrade to ninety-five percent (95%) relative compaction per Method (1) defined in Section 14.5, and disposal of all surplus material required to achieve the reconstruction for Agate Street to the subgrade depths and dimensions as shown on the drawings.

Exclusive of this contract item is the street reconstruction within the trench excavation limits for installation of the trench drain which will be measured and paid by the contract item Excavation.

Also exclusive from this contract item is the aggregate base and hot mix asphalt required to achieve the final grades as shown on the drawings, which will be measured and paid by the contract items Aggregate Base, Class 2; and Hot Mix Asphalt (HMA), respectively.

14.5 General Backfill Requirements - Whenever fill is specified or required (except for retaining wall backfill) the work shall be performed as set forth in Sections 300-4.1 to 300-4.8 of the Greenbook Specifications. Backfill for retaining walls shall conform to Section 306-12 of the Greenbook Specifications, except jetting is not allowed.

No backfill materials shall be placed against the outside walls of cast-in-place concrete structures until the concrete has developed eighty percent (80%) of its design strength. No fill or traffic will be permitted on the top of any cast-in-place concrete structure until the concrete in the structure has attained its design strength. Compressive strength will be determined by test cylinders taken by the Engineer. A maximum of six (6) test cylinders per structure will be made and paid by the District for the following day breaks: 7, 14, 21, 28, 28 days, and one break to be agreed upon by the Engineer and Contractor. Any additional test cylinders requested by Contractor shall be deducted from the monthly progress payment at a rate of \$500.00/cylinder.

Regardless of the method of densification, backfill material shall not be placed against any reinforced concrete structure until the structure has been inspected and approved for backfilling by the Engineer.

Backfill will be accomplished by either mechanical methods or by placement of Controlled Low Strength Material (CLSM) as described in (1) and (2) below.

- (1) Mechanical Compaction - Backfill shall be mechanically compacted by means of tamping rollers or other mechanical tampers. Impact-type pavement breakers (stompers) will not be permitted unless otherwise approved by the Engineer.

All backfill material for structures shall be placed in uniform layers and shall be brought up uniformly on each side of the structure. The thickness of each layer of backfill shall not exceed 8 inches before compaction unless otherwise approved by the Engineer. For hand directed mechanical compactors, the thickness of each layer shall not exceed 4 inches before compaction.

All relative compaction tests will be made by the Engineer in conformance with ASTM D1557. Whenever relative compaction is specified to be determined by ASTM D1557.

- (2) Controlled Low Strength Material (CLSM) - Controlled Low Strength Material (CLSM) placement for backfill shall be used when specified or approved by the Engineer. CLSM shall conform to Section 201-6 of the Greenbook Specifications and as specified in Section 16.

Approval to use specific methods and compaction equipment shall not be construed as guaranteeing or implying that the use of such methods and equipment will not result in damage to adjacent ground, existing improvements or improvements installed under the contract, nor shall it be construed as guaranteeing proper compaction. The Contractor shall make his own determination in this regard.

All backfill around structures shall be compacted to not less than ninety percent (90%) relative compaction. Where such material is placed under existing or proposed paved roadways, the top 3 feet, measured from the subgrade plane, shall be compacted to ninety-five percent (95%) and shall be compacted by Method (1).

Trench bottoms for structures shall be graded to provide firm and uniform bearing throughout the entire length of the structures.

14.6 Testing - District personnel shall perform compaction tests as described below using either the ASTM D1556 (sand cone) or ASTM D6938 (nuclear) test method. These tests represent the minimum required. Additional tests may be taken at the Engineer's discretion.

1. A complete series of compaction tests will be taken at approximate maximum intervals of 200 feet for all backfill and surfaces prepared for concrete structures.
2. Any failed test will result in a retest.

14.7 Backfill - The contract item Backfill includes all mechanical backfill material compacted as specified around the various concrete structures within the paylines as shown on the standard drawings.

14.8 Measurement - Excavation; Street Reconstruction; and Backfill; beyond the limits established by the drawings, unless ordered in writing by the Engineer, will not be measured for payment.

The excavated material shall be measured from the ground surface existing at the start of excavation, as determined from surveyed cross sections taken by the District, to the lines, grades and dimensions shown on the drawings. Longitudinal limits of the excavations as shown on the profile drawings terminate at a vertical plane at the limits of the structure, measured along the longitudinal axis of the various structures.

Measurement for payment for the contract item Excavation will be the number of cubic yards of material excavated as shown on the drawings. Longitudinal limits of the excavations terminate at a vertical plane at the limits of structures, measured along the longitudinal axis of the structure.

Measurement for payment for the contract item Street Reconstruction will be the number of cubic yards of material excavated between the proposed edges of pavement and longitudinal limits as shown on the drawings or as directed by the Engineer.

Measurement for payment for the contract item Backfill will be the number of cubic yards of material placed in final position as specified and within the limits of the payment line shown on the drawings. The longitudinal limits shall terminate at a vertical plane at the limits of the structure, measured along the longitudinal axis of the various structures. Volumes occupied by structures, aggregate base, asphalt concrete and other features for which a separate payment is made will be deducted from the gross volume.

14.9 Payment - The contract prices paid for Excavation; Street Reconstruction; and Backfill shall include full compensation for all costs incurred under this section.

SECTION 15 - NOT USED

SECTION 16 - CONCRETE CONSTRUCTION

16.1 Description - This section includes the contract items related to the various classes of Concrete.

16.2 General Requirements - Concrete for all purposes shall be composed of Portland Cement, aggregates and water of the quantities and qualities herein specified, and in the required proportions. The ingredients are to be well mixed (a minimum of 70 drum revolutions, and a maximum of 250 drum revolutions are required to provide sufficient agitation to the concrete mix) and brought to the proper consistency and to have a compressive strength at the age of 28 days of not less than the amount shown in the following tabulation for each type of work listed:

CONCRETE CLASS	MINIMUM SACKS CEMENT/C.Y.	TYPE OF WORK	POUNDS PER SQUARE INCH
A	6	Retaining Wall, Trench Drain Concrete Body	3600*
A	6	Concrete Swale, Concrete Apron, and Transitions	3250*
B	5	Cutoff Walls, Curb and Gutter, Concrete Pad, and Miscellaneous Concrete not otherwise specified	3000*

*Note: Concrete for use in structures constructed from State of California, Department of Transportation Standard Plans shall have compressive strengths as called for on those plans.

16.3 Material and Methods - All concrete materials, methods, forms and proportioning shall conform to Sections 51 and 90, and additionally, curb construction shall conform to Section 73 of the Caltrans Specifications. Concrete test specimens will be made in accordance with ASTM Designation C-31 and C172. Test for concrete compressive strengths will be performed in accordance with ASTM Designation C-39. Combined aggregate grading for all concrete shall be in conformance with Section 90-1.02C(4)(d) of the Caltrans Specifications and the following tabulation for each type of work listed:

TYPE OF WORK	COMBINED AGGREGATE GRADING
The inverts of: Concrete Swale and Concrete Swale Transition	1-1/2" Maximum
Trench Drain Concrete Body, Concrete Apron, Curb and Gutter, Concrete Pad, Driveways, Sidewalks, Cutoff Walls, and Miscellaneous Concrete not otherwise specified. All other concrete structures	1" Maximum

Fly Ash, Class F may be substituted for cement, up to a maximum of 15 percent by weight for all concrete. Fly Ash shall meet the standards of ASTM Designation: C-618. Water reducing agents meeting ASTM Designation: C-494 will be permitted in amounts recommended by the supplier and approved by the Engineer in writing.

No other admixture shall be used in any class of concrete without written permission from the Engineer.

Supplementing Section 90-1.01 of the Caltrans Specifications, the Contractor shall submit the mix designs for all types of concrete to be placed to the Engineer for review, and shall obtain approval prior to the pre-construction meeting and placement of any concrete. Supplementing Section 90-1.02G(3) of the Caltrans Specifications, concrete delivered to the job

site shall be accompanied by a ticket containing the weight of each of the individual ingredients in the mix.

16.4 General Reinforcing Steel Requirements - Reinforcing steel for all reinforced concrete structures shall be Grade 60 Low-Alloy or Grade 60 Billet-Steel. The reinforcing steel for use in structures constructed from State of California, Department of Transportation Standard Plans shall be of Grade 60 or as called for on those plans. Cleaning, bending, placing and spacing of reinforcement shall conform to the applicable provisions of Section 52 of the Caltrans Specifications and to the drawings. The Contractor shall furnish a "Certificate of Compliance" with the specification of ASTM Designation: A-706/A or A-615/A. All splices shall conform to the requirements of A.C.I. Manual, Standard 318, latest edition. Splices requested by the Contractor for his convenience shall be subject to approval by the Engineer. Longitudinal lap shall be 16 inches minimum for #4 bars and 19 inches minimum for #5 bars.

16.5 Consistency - The consistency of the concrete shall be such as to allow it to be worked into place without segregation. Unless otherwise specified, the slump shall be 3 inches plus or minus 1 inch for all concrete.

The slump test shall be performed in accordance with the requirements of ASTM Designation: C-143. Slumps greater than those specified may be cause for rejection of the concrete by the Engineer.

16.6 Placing - Supplementing Section 51-1.03D(1) of the Caltrans Specifications, concrete shall not be placed except in the presence of the Engineer. The Contractor shall give reasonable notice to the Engineer each time he intends to place concrete. Such notice shall be far enough in advance to give the Engineer adequate time to inspect the subgrade, forms, steel reinforcement and other preparations for compliance with the specifications before concrete is delivered for placing.

Formed concrete shall be placed in horizontal layers in lifts of not more than 20 inches. Hoppers and chutes, pipes and "elephant trunks" shall be used as necessary to prevent segregation of the concrete.

16.7 Form Removal and Finish - Forms shall be removed only when the Engineer has given his approval. Forms shall be removed in such a way as to prevent damage to the concrete. Supports shall be removed in a manner that will permit the concrete to take stresses due to its own weight uniformly.

Forms shall not be removed sooner than the following minimum time or strength after the concrete is placed. These times represent cumulative number of days and fractions of days, not necessarily consecutive, during which the temperature of the air adjacent to the concrete is above 50 degrees Fahrenheit. If the temperature falls below 50 degrees Fahrenheit at any time after the concrete is placed in the forms, the Engineer will advise the Contractor of additional time required before forms can be removed.

Element	Strength or Time
Retaining Walls and Trench Drain Concrete Body	3000 psi or 7 days
All other structures	16 hours

The finish on all exposed formed surfaces shall conform to Section 51-1.03F(3) Class 1 Surface Finish of the Caltrans Specifications. A tight wood float finish will be required on the surface of concrete swales and excessive surface working will not be permitted. The exposed concrete surfaces shall be broomed in a transverse direction with a fine textured hair push broom to produce a uniform surface and eliminate float marks. Brooming shall be done when the surface is sufficiently set to prevent deep scarring. If directed by the Engineer, a fine spray of water shall be applied to the surface immediately in advance of brooming.

Exposed corners of all concrete structures shall be finished with a 3/4" chamfer.

Concrete flatwork shall match adjacent surfaces. The concrete shall be struck off and tamped or vibrated until a layer of mortar has been brought to the surface. The top surface and face of curbs, gutters, catch basins and sidewalks shall be finished to match adjacent surfaces.

16.8 Curing - All concrete shall be prevented from drying for a curing period of at least seven (7) days after it is placed. Surfaces exposed to air during the curing process shall be kept continuously moist for the entire period or until curing compound is applied.

Formed surfaces shall be thoroughly wetted immediately after forms are removed and shall be kept wet until patching and repairs are completed. Water or covering shall be applied in such a way that the concrete surface is not eroded or otherwise damaged. Water for curing shall be clean and free from any substances that will cause discoloration of the concrete.

Concrete may be coated with curing compound in lieu of the continued application of moisture. The curing compound shall comply with the requirements of Section 90-1.03B(3) of the Caltrans Specifications and ASTM Designation C-309. The curing compound shall be No. 2 White Pigmented Curing Compound, Type 2, Class B for all concrete surfaces other than for flatwork which shall be coated with No. 6 Nonpigmented Curing Compound, Type 1-D, Class A containing a red fugitive dye.

The curing compound shall be sprayed on the moist concrete surfaces as soon as free water has disappeared, but shall not be applied to any surface until patching, repairs and finishing of that surface are completed. The curing compound shall be thoroughly mixed immediately before applying, and shall be applied at a uniform rate of not less than one gallon per 150 square feet of surface. No separate payment will be made for the curing compound or its application.

16.9 Joints - Joints shall be made at the locations shown on the drawings, or as approved by the Engineer.

The Contractor shall construct, in one continuous concrete placing operation, all work comprised between such joints. Joints shall be kept moist until adjacent concrete is placed.

All construction joints having a keyed, stepped, or roughened surface shall be cleaned by sandblasting prior to placement of the adjacent concrete, unless otherwise directed by the Engineer.

The sandblasting operations shall be continued until all unsatisfactory concrete, laitance, coatings, stains, debris, and other foreign materials are removed. The surface of the concrete shall be washed thoroughly to remove all loose material.

Transverse weakened plane joints shall be required in the concrete swale at 10-foot spacing or as directed by the Engineer. The joints may be formed by placing a continuous strip of plastic or other material which will not react adversely with the chemical constituents of the concrete or bond with the concrete. The strip shall have a minimum thickness of 0.013 foot, a width of not less than 0.12 foot nor more than 0.13 foot for the six-inch thick concrete swale slope and invert. After placement, the vertical axis of the joint material shall be within 10 degrees of a plane normal to the surface of the concrete. The tops of the strip shall not be above nor more than 0.02 foot below the finished concrete. Final alignment of the strip for the transverse weakened plane joints shall not vary more than 0.04 foot from the edge of a 12-foot straight edge. After installation of a joint material the concrete shall be free of segregation, rock pockets or voids and the finished concrete surface on each side of the joint shall be in the same plane.

The Contractor may elect to form the weakened plane joints in the concrete swale surface by cutting a groove in the surface with a power driven saw. The grooves shall be cut to a minimum depth of 0.17 foot and the width shall be the minimum width possible with the type of saw being used, but in no case shall the width exceed 0.02 foot. The weakened plane joints shall be sawed within 12 hours after the concrete has been placed.

Construction joints, when required, shall be located between the transverse joints and, unless otherwise specified on the plans, shall utilize 1/2 inch diameter deformed bars 30 inches long, spaced at 18-inch centers as tie bars. The construction joints shall be straight and finished in a workmanlike manner.

Surfaces of construction joints shall be cleaned as set forth in Section 51-1.03D(4) of the Caltrans Specifications.

16.10 Use of the Concrete Swale Invert - Dump trucks, concrete trucks and earth moving equipment (whether full or empty) will not be allowed to operate on the invert of the concrete swale.

No category of equipment, except that specifically approved by the Engineer in writing will be permitted to use the invert of the concrete swale for access to the work area.

In any event, vehicular access to the invert will not be permitted until the concrete has achieved its design strength. Approval for access to use the invert shall not relieve the Contractor of the responsibility to avoid damage to the concrete. Cracking, displacement or other damage which occurs to the invert will be cause to restrict some or all of the categories of equipment allowed access to the concrete swale invert. Repair or replacement of damaged concrete will be required.

16.11 Class "A" Concrete, Retaining Wall - The contract item Class "A" Concrete, Retaining Wall covers the concrete to be used in the construction of the retaining walls. Included in this pay item is all reinforcing steel, weepholes and all associated appurtenances required for these structures, but exclusive of earthwork.

16.12 Class "A" Concrete, Concrete Swale - The contract item Class "A" Concrete, Concrete Swale includes the concrete paving of the concrete swale, the concrete swale transitions, and the concrete aprons. Included in the pay item is all reinforcing steel required, but exclusive of earthwork.

Finish surface of the concrete swale and concrete apron shall be true to lines and grades, and concrete shall be not less than the minimum thickness indicated on the drawings and as specified in Section 6.10 Construction Tolerances of the Special Provisions.

16.13 Class "B" Concrete, 2' Cutoff Wall - The contract item Class "B" Concrete, 2' Cutoff Wall covers the construction of the transverse cutoff walls, the continuous cutoff walls on each side of the concrete swale, and the northern edge of the concrete apron as shown on the drawings. Included in the pay item is all reinforcing steel required, but exclusive of earthwork.

16.14 Class "B" Concrete, Miscellaneous - The contract item Class "B" Concrete, Miscellaneous includes the complete construction of the curb and gutters, cross gutters, sidewalks, driveways, pipe plugs, concrete pad, and any other concrete not specified. Included in the pay item is all earthwork and reinforcing steel required. The subgrade for cross gutters and driveways shall be recompacted to ninety-five percent (95%) relative compaction prior to the placement of concrete.

16.15 Measurement - Measurement for payment for the contract items Class "A" Concrete, Retaining Wall; Class "A" Concrete, Concrete Swale; and Class "B" Concrete, Miscellaneous will be the number of cubic yards placed as specified, measured to the neat lines as shown on the drawings.

Measurement for payment for the contract item Class "B" Concrete, 2' Cutoff Wall will be the number of lineal feet placed, measured parallel to the top of each side of concrete swale and along the northern edge of the concrete apron as indicated on the drawings.

No measurement or payment will be made for dowels, tie bars, tie wires, blocks, chairs and other accessories.

16.16 Payment - The contract prices paid for the various Concrete items and reinforcing steel items shall include full compensation for all costs incurred under this section.

SECTION 17 AND SECTION 18 – NOT USED

SECTION 19 - FLEXIBLE PAVEMENT CONSTRUCTION

19.1 Description - This section covers the contract items Aggregate Base, Class 2; and Hot Mix Asphalt (HMA).

19.2 Aggregate Base, Class 2 - The contract item Aggregate Base, Class 2 includes furnishing and placing such material as indicated on the drawings. Aggregate Base, Class 2 shall be clean and free from roots, organic material and other deleterious substances, and be of such character that when wet it will compact to form a firm stable base. Material and placing shall be in accordance with Section 26 of the Caltrans Specifications using $\frac{3}{4}$ -inch maximum size.

The aggregate base shall also have a sand equivalent value of not less than 35 when tested in conformance with California Test Method 217.

The aggregate base material shall be spread as specified in Sections 26-1.03A and 26-1.03C of the Caltrans Specifications. The aggregate base material shall be compacted as specified in Section 26-1.03D of the Caltrans Specifications.

The aggregate material used on access roads, shall not contain recycled concrete products.

19.3 General Hot Mix Asphalt (HMA) Requirements - The Contractor shall not start paving Hot Mix Asphalt (HMA) until all compaction on the aggregate base is tested and approved by the Engineer.

The HMA shall be proportioned, mixed, spread and compacted in accordance with the applicable provisions in Section 39 of the Caltrans Specifications and these Detailed Specifications.

The Contractor shall ensure the safe transportation, storage, use and disposal of HMA.

The Contractor shall prevent the formation of carbonized particles caused by overheating HMA during manufacturing or construction.

19.4 Hot Mix Asphalt (HMA) Aggregate - Aggregates shall be clean and free from decomposed materials, organic material, and other deleterious substances. Coarse aggregate is material retained on the No. 4 sieve and fine aggregate is material passing the No. 4 sieve. Supplemental fine aggregate is added fine material passing the No. 30 sieve including, but not limited to, cement and stored fines from dust collectors.

The aggregate grading of the different types of Hot Mix Asphalt (HMA) shall conform to the following, unless otherwise specified on the plans:

HMA Type	Grading
A	3/4-inch and/or 1/2-inch

The base course of the HMA shall consist of 3/4-inch aggregate for Type A and the final course for Type A shall consist of 1/2-inch aggregate.

The combined aggregate gradation and quality characteristics for HMA Type A aggregates, prior to addition of asphalt binder, shall conform to the requirements found in the following tables:

**Aggregate Gradation HMA Type A
(Percentage Passing)
3/4-inch HMA Type A**

Sieve Sizes	Target Value Limits	Allowable Tolerance
1-inch	100	-
3/4-inch	90-100	TV ±5
1/2-inch	70-90	TV ±6
No. 4	45-55	TV ±7
No. 8	32-40	TV ±5
No. 30	12-21	TV ±4
No. 200	2-7	TV ±2

**Aggregate Gradation HMA Type A
(Percentage Passing)
1/2-inch HMA Type A**

Sieve Sizes	Target Value Limits	Allowable Tolerance
3/4-inch	100	-
1/2-inch	95-99	TV ±6
3/8-inch	75-95	TV ±6
No. 4	55-66	TV ±7
No. 8	38-49	TV ±5
No. 30	15-27	TV ±4
No. 200	2-8	TV ±2

HMA Type A Aggregate Quality

Quality Characteristic	Test Method	Requirement
Percent of crushed particles ¹	CT 205	90
Coarse aggregate (% min.)		
One fractured face		
Two fractured faces	75	
Fine aggregate (Passing No. 4 Sieve and retained on No. 8 Sieve) (% min.)	70	
One fractured face		

Los Angeles Rattler (% max.) ¹	CT 211	12
Loss at 100 rev.		45
Loss at 500 rev.		47
Sand equivalent ^{1,2} (min.)	CT 217	45
Fine aggregate angularity (% min.) ¹	AASHTO T 304 Method A	10
Flat and elongated particles (% max. by weight at 5:1) ¹	ASTM D 4791	

Note: ¹Combine aggregate in the job mix formula proportions.

²Reported value must be the average of three (3) tests from a single sample.

19.5 Asphalt Binder - The asphalt binder to be mixed with aggregate shall conform to these Detailed Specifications and shall be as designated below or as determined by the Engineer:

- Grade PG 64-10 (Inland Valleys)

The Contractor shall furnish and place the HMA with all asphaltic emulsions required.

Asphalt binder shall consist of refined petroleum or a mixture of refined liquid asphalt and refined solid asphalt, prepared from crude petroleum. Asphalt binder shall be:

- Free from residues caused by the artificial distillation of coal, coal tar or paraffin
- Free from water
- Homogeneous

The Contractor shall furnish asphalt binder from a supplier that conforms to the State of California Department of Transportation's "Certification Program for Suppliers of Asphalt". The Department maintains the program requirements, procedures, and a list of approved suppliers at <https://dot.ca.gov/programs/engineering-services/asphalt-supplier-certification-program>.

The amount of asphalt binder to be mixed with the mineral aggregate shall be between three percent (3%) and seven percent (7%) by weight, of the dry mineral aggregate. The exact amount of asphalt binder to be mixed with the mineral aggregate shall be determined by a special mix design.

Performance grade paving asphalt shall conform to the testing requirements in the table below:

Performance Graded Asphalt Binder

Property	AASHTO Test Method	Specification Grade			
		PG 64-10	PG 64-16	PG 70-10	PG 64-28PM ⁱ
Original Binder					
Flash Point, Minimum °C	T48	230	230	230	230
Solubility, Minimum % ^b	T44	99	99	99	98.5
Viscosity ^c at 135 °C, Maximum, Pa·s	T316	3.0	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T315	64 1.00	64 1.00	70 1.00	64 1.00
RTFO Test ^e , Mass Loss, Maximum, %	T240	1.00	1.00	1.00	1.00
RTFO Test Aged Binder					
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T315	64 2.20	64 2.20	70 2.20	64 2.20
Ductility at 25 °C Minimum, cm	T51	75	75	75	-
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum (delta), %	T315	-	-	-	Note g 80
PAV ^f Aging, Test Temperature, °C	R28	100	100	110	100
Elastic Recovery ^h , Test Temp., °C Minimum recovery, %	T 301	-	-	-	25 75
RTFO Test and PAV Aged Binder					
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*/sin(delta), kPa	T315	31 ^d 5000	28 ^d 5000	34 ^d 5000	31 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, Mpa Minimum M-value	T313	0 300 0.300	-6 300 0.300	0 300 0.300	-12 300 0.300

Notes:

- Not used.
- The Engineer will waive this specification if the supplier is a Quality Supplier as defined by Department's "Certification Program for Suppliers of Asphalt".
- The Engineer will waive this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- Test the sample at 3 °C higher if it fails at the specified test temperature. G* sin(delta) shall remain 5000 kPa maximum.
- "RTFO Test" means the asphaltic residue obtained using the Rolling Thin Film Oven Test, AASHTO Test Method T240 or ASTM Designation: D2827.

- f. "PAV" means Pressurized Aging Vessel.
- g. Test temperature is the temperature at which $G^*/\sin(\delta)$ is 2.2 kPa. A graph of $\log G^*/\sin(\delta)$ plotted against temperature may be used to determine the test temperature when $G^*/\sin(\delta)$ is 2.2 Kpa. A graph of (δ) versus temperature may be used to determine δ at the temperature when $G^*/\sin(\delta)$ is 2.2 kPa. The Engineer also accepts direct measurement of (δ) at the temperature when $G^*/\sin(\delta)$ is 2.2 kPa.
- h. Test without a force ductility clamp may be performed.
- i. Do not modify PG Polymer Modifier using acid modification.

Certificates of compliance shall be furnished to the Engineer certifying that the asphaltic emulsions and paving asphalts conform to the referenced Greenbook Specifications.

19.6 Hot Mix Asphalt (HMA) Prime Coat - Prime coat shall consist of refined petroleum and shall conform to the provisions in Section 93 "Liquid Asphalts" of the Caltrans Specifications. Prime coat shall be applied only to those areas designated by the Engineer. The application rate shall be 0.25 gallon per square yard of surface covered. The exact rate and number of applications will be determined by the Engineer.

19.7 Hot Mix Asphalt (HMA) Paint Binder/Tack Coat - Asphaltic emulsion for paint binder (tack coat) shall conform to the provisions in Section 94 "Asphaltic Emulsion" of the Caltrans Specifications for the rapid-setting or slow-setting type and grade approved by the Engineer. Grade CQS1 shall be used if not otherwise specified by the Engineer. Tack coat shall be applied to all vertical surfaces of existing pavement, curbs, gutters, and construction joints in the surfacing against which additional material is to be placed, to a pavement to be surfaced, and to other surfaces designated in the Detailed Specifications. The application rate shall be from 0.02 to 0.10 gallon per square yard of surface covered. The exact rate and number of applications will be determined by the Engineer.

19.8 Hot Mix Asphalt (HMA) Placement - Hot Mix Asphalt (HMA) shall be spread and compacted in the number of layers of the thicknesses indicated in the following table:

Total Thickness Shown on Plans ¹	Minimum No. of Layers	Top Layer Thickness (ft.)		Next Lower Layer Thickness (ft.)		All Other Lower Layer Thickness (ft.)	
		Min.	Max.	Min.	Max.	Min.	Max.
0.24-foot or less	1	-	-	-	-	-	-
0.25-foot	2	0.12	0.13	0.12	0.13	-	-
0.26 - 0.46-foot	2	0.12	0.21	0.14	0.25	-	-
0.47-foot or more	3 or more	0.15	0.21	0.15	0.25	0.17	0.25

¹When pavement reinforcing mat is shown to be placed between layers of HMA, the thickness of HMA above the pavement reinforcing mat shall be considered to be the "total thickness shown on plans".

The straightedge for smoothness determination on the top layer of HMA pavement shall conform to the tolerance specified in Section 39-1.12B, "Straightedge" of the Caltrans Specifications.

Areas of the top surface of the uppermost layer of HMA pavement that do not meet the specified surface tolerances shall be brought within tolerance by abrasive grinding. Areas which have been subjected to abrasive grinding shall receive a seal coat. The corrective method for each area shall be selected by the Contractor and shall be approved by the Engineer prior to beginning the corrective work.

When abrasive grinding is used to bring the top surface of the uppermost layer of HMA surfacing within the specified surface tolerances, additional abrasive grinding shall be performed as necessary to extend the area ground in each lateral direction so that the lateral limits of grinding are at a constant offset from, and parallel with, the nearest lane line or pavement edge, and in each longitudinal direction so that the grinding begins and ends at lines normal to the pavement centerline, within a ground area. Ground areas shall be neat rectangular areas of uniform surface appearance.

19.9 Hot Mix Asphalt (HMA) - The contract item Hot Mix Asphalt (HMA) covers the furnishing and installation of HMA necessary for the repair and resurfacing of streets damaged or removed due to construction operations, or as otherwise specified on the plans, including all aggregate, asphalt binder, prime coat, and tack coat/paint binder as specified herein, exclusive of any excavation or pavement grinding. Also included in this item is the installation of a 30° FHWA Safety Edge along portions of proposed edges of pavement without curb and gutter as shown on the drawings.

19.10 Measurement - Measurement for payment of the contract item Aggregate Base, Class 2 will be the number of cubic yards placed to the lines, grades and dimensions shown on the drawings. **No allowance will be made for aggregate base placed outside said dimensions unless otherwise ordered by the Engineer.**

Measurement for payment of the contract item Hot Mix Asphalt (HMA) will be the number of tons placed to the lines, grades and dimensions shown on the drawings. The HMA pay quantity shall be determined by using a conversion factor of 144 pounds per cubic foot for all HMA placed within standard paylines. No measurement for payment will be made for asphalt emulsions, including asphalt binder, HMA prime coat, HMA tack coat/paint binder required for this portion of the work, all costs for these items shall be included in the price paid for HMA. **No allowance will be made for HMA placed outside said dimensions unless otherwise ordered by the Engineer.**

19.11 Payment - The contract prices paid for Aggregate Base, Class 2; and Hot Mix Asphalt (HMA) shall include full compensation for all costs incurred under this section.

SECTION 20 - FENCES AND GATES

20.1 Description - This section covers the contract items Modified 6-Foot Chain Link Fence; Temporary Fencing; and Modified 14-Foot Double Drive Gates.

20.2 Modified 6-Foot Chain Link Fence - The contract item Modified 6-Foot Chain Link Fence includes furnishing and installing the material required for this portion of the work as

shown on the drawings and as directed by the Engineer. Included in this item is all hardware parts, posts, fittings, and privacy fabric necessary for the installation of the Modified 6-Foot Chain Link Fence.

All materials shall be new except that specified for removal and relocation and shall conform to Section 206-6 of the Greenbook Specifications and the drawings, with installation in conformance with Section 304-3.2. Materials salvaged shall be subject to the Engineer's approval prior to reinstallation. All posts shall be set in commercial plant quality, 4 sack per cubic yard concrete.

20.3 Temporary Fencing - The contract item Temporary Fencing shall include all labor, materials and equipment necessary for installing and removing the temporary fencing and removing and reinstalling the property line fences as shown on the drawings. The temporary fencing shall be a 6-foot high chain link fence. Fencing materials need not be new and fence posts need not be set in concrete. Temporary Fencing shall be installed as directed by Engineer to ensure residential properties adjacent to the construction site are secured at all times.

20.4 Modified 14-Foot Double Drive Gates - The contract item Modified 14-Foot Double Drive Gates includes furnishing and installing the various gates as shown on the drawings, complete with all gate posts set in concrete and in conformance with Section 304-3.3 of the Greenbook Specifications. Also included in this item is the green privacy fabric necessary for the installation of the Modified 14-Foot Double Drive Gates. Padlocks are not included in this item. On completion, gates shall operate freely without wedging or binding.

20.5 Measurement - Measurement for payment for the contract items Modified 6-Foot Chain Link Fence; and Temporary Fencing will be the number of lineal feet of new and relocated fence installed measured along the top of the fence parallel to the ground.

Measurement for payment for the contract item Modified 14-Foot Double Drive Gates will be the number of pairs installed. Excavation and concrete required for fence or gate posts will not be measured for payment.

20.6 Payment - The contract price paid for Modified 6-Foot Chain Link Fence; Temporary Fencing; and Modified 14-Foot Double Drive Gates shall include full compensation for all costs incurred under this section.

SECTION 21 - MISCELLANEOUS

21.1 Description - This section covers the contract items 4'W x 1.5'H Grated Trench Drain; Midwest Guardrail System; Adjust Manhole to Grade; and Extra Directed Work.

21.2 4'W x 1.5'H Grated Trench Drain - The contract item 4'W x 1.5'H Grated Trench Drain includes furnishing and installing the trench drain and all associated appurtenances as required by the manufacturer, inclusive of load bearing frame, trench drain grates, and trench drain concrete, but exclusive of earthwork. The trench drain system shall be a Dura Trench 48" wide

Prefabricated Trench Drain, or equivalent approved by the District, and shall conform to the specifications outlined herein.

The trench drain interior dimensions shall measure a minimum 4-foot width and a maximum 1.5-foot height from invert to top of grates. The trench drain shall have a smooth interior for improved flow rates and reduced debris build-up with a maximum Manning's n-value of $n = .013$. The trench body shall be frost proof, salt proof, and be resistant to dilute acids and alkalis per ASTM C267 and shall conform to the following standards:

Minimum Tensile Strength	12,600 psi	ASTM C307
Minimum Compressive Strength	12,000 psi	ASTM C579
Minimum Flexural Strength	26,500 psi	ASTM C580
Maximum Water Absorption	0.35%	

The load bearing frame and trench drain grates shall be installed per manufacturer's recommendations and shall conform to ASTM A-36 and galvanized in accordance with Section 210-3 of the Greenbook Specifications. The grate and frame trench drain system shall be rated for heavy-duty, HS-25 loading requirements in conformance with AASHTO M-306.

The load bearing frame shall be set to ensure the trench drain grates are flush with the trench drain concrete body. Additionally, the load bearing frame shall be securely anchored to the surrounding concrete body to ensure proper transfer of traffic loading.

The trench drain grates shall have slotted openings and shall be ADA compliant, heel proof, and safe for equestrian use. In its final form, the trench drain grates shall be set flush with the trench drain concrete body when resting on the load bearing frame. Additionally, the trench drain grates shall be theft-proof, i.e., properly secured and anchored, along the entire length of the trench drain except that the last downstream grate shall be attached in a manner to enable maintenance of the trench drain.

The trench drain concrete body shall measure 1-foot thickness around the trench drain and be constructed per Section 16 of these Detailed Specifications. The trench drain concrete body shall securely anchor the load bearing frame with the top of concrete body walls flush with the trench drain grates.

21.3 Midwest Guardrail System - The contract item Midwest Guardrail System includes all costs associated with the furnishing and installation of the Midwest Guardrail System and Caltrans approved terminal end treatments as shown on the drawings. All Caltrans Standards specified for this contract item conforms to Caltrans Standard, 2015 edition. All materials and installation shall be in conformance with Section 83 of the Caltrans Specifications, 2015 edition.

21.4 Adjust Manhole to Grade - The contract item Adjust Manhole to Grade covers all labor, equipment, materials and incidentals required for the complete adjustment of all manholes within the limits of the street improvements to meet the finished street grade. Included in this item is the preparation, submittal, and approval of the Contractor's confined space entry permit by Jurupa Community Services District prior to construction, and the installation of a false bottom

within the sewer manhole during construction. Sewer and storm drain manhole frames within the area to be paved or graded shall be set to finish grade by the Contractor. Manholes in asphalt concrete pavement shall be set to finish grade in accordance with Jurupa Community Services District Drawing No. S-7 and with Section 403-3 of the Greenbook Specifications. Repaving required as a result of reconstructing or adjusting all manhole and vault frames and covers to grade shall be the responsibility of the Contractor and the cost thereof shall be included in the bid item for pavement. The Contractor shall remove all debris from the interior of manholes and shall clean all foreign material from the top of the frames and covers.

21.5 Extra Directed Work - The contract item Extra Directed Work shall consist of necessary work that is not included in other contract bid items and not shown on the drawings, as determined by the Engineer. All Extra Directed Work shall be performed only as directed by the Engineer and in accordance with all applicable standards and specifications.

21.6 Measurement - Measurement for payment for the contract item 4'W x 1.5'H Grated Trench Drain will be the number of lineal feet of trench drain installed.

Measurement for payment for the contract item Midwest Guardrail System will be the number of lineal feet installed as specified.

Measurement for payment for the contract item Adjust Manhole to Grade shall be the number of manholes that are adjusted to meet the finished street grade.

21.7 Payment - The contract prices paid for 4'W x 1.5'H Grated Trench Drain; Midwest Guardrail System; and Adjust Manhole to Grade shall include full compensation for all costs incurred under this section.

Full compensation for the contract item Extra Directed Work shall be as "Extra Work" and shall be paid pursuant to Section 2.07 of the General Provisions. The total accumulated costs for Extra Directed Work shall not exceed the amount specified in the contract bid item unless otherwise increased by change order.

SECTION 22 THROUGH SECTION 25 – NOT USED

SECTION 26 - STONEMWORK

26.1 Description - This section covers the contract items Rock Slope Protection, Class I (20-lb); Crushed Rock; and Rock Slope Protection Fabric.

26.2 General - All rock materials shall meet the gradation requirements of Section 72-2.02 of the Caltrans Specifications and the quality requirements of Sections 200-1.6.1 and 200-1.6.3 of the Greenbook Specifications.

Rock materials shall be blocky and predominantly angular in shape. Not more than 25% of the rock shall have a length more than 2.5 times the breadth or thickness. No rock shall have a

length exceeding 3.0 times its breadth or thickness. All oversize rocks, as determined by the Engineer, shall be removed.

Rock materials shall be placed on a firm dry foundation in conformance with Method B of Section 72-2.03 of the Caltrans Specifications, however, additional placement effort shall be required to meet the lines and grades as shown on the drawings and to fill and chink oversize voids with selected rock to establish a stable interlock. Chinking of voids will not be required for rock specified to be concreted.

Permeable materials such as filter blankets shall be consolidated and the surface trimmed to final grade as directed by the Engineer.

26.3 Rock Slope Protection, Class I (20-lb) - The contract item Rock Slope Protection, Class I (20-lb) covers the rock furnished and placed as shown on the drawings as specified. Rock shall conform to Class I (20-lb), for Method B placement per Section 72-2.02 of the Caltrans Specifications.

26.4 Crushed Rock - The contract item Crushed Rock covers the complete installation of crushed rock on access roads as shown on the plans and as directed by the Engineer. Grading for the Crushed Rock shall meet the requirements for 1" x No. 4 coarse aggregate as per Section 90-1.02C(4)(b) of the Caltrans Specifications. Crushed Rock shall additionally meet the spreading and compaction requirements of Sections 26-1.03C and 26-1.03D of the Caltrans Specifications, respectively.

26.5 Rock Slope Protection Fabric - Rock Protection Fabric placed beneath rock shall conform to Class 8 per Section 72-2.02B of the Caltrans Specifications.

26.6 Measurement - Measurement for payment for the contract items Rock Slope Protection, Class I (20-lb); and Crushed Rock shall be the number of cubic yards placed as specified.

Measurement for payment for the contract item Rock Slope Protection Fabric shall be the number of square yards placed as specified. No measurement for payment will be made for laps required for installation or for convenience to the Contractor.

26.7 Payment - The contract prices paid for Rock Slope Protection, Class I (20-lb); Crushed Rock; and Rock Slope Protection Fabric shall include full compensation for all costs incurred under this section.

SECTION 27 - DUST ABATEMENT

27.1 Description - This section covers the implementation of dust control measures necessary to prevent harm and nuisance from dust. Supplementing Section 8.06 of the General Provisions, the Contractor shall comply with all the provisions of the South Coast Air Quality Management District (SCAQMD) Rule 403 as described in Appendix "A".

27.2 Dust Abatement - The contract item Dust Abatement includes the action necessary to prevent, reduce or control dust within the work area as required to complete the work. The Contractor shall carry out proper and efficient measures to prevent his operations from producing dust in amounts damaging to property or causing a nuisance, or harm to persons living nearby or occupying buildings in the vicinity of the work. The methods to be used for controlling dust in the construction area and along haul roads shall be approved by the Engineer prior to starting any work included in this contract. The Rule 403 Implementation Handbook published by the SCAQMD contains a detailed listing of reasonably available dust control measures and is available for inspection at the District office.

27.3 Payment - The contract lump sum price paid for Dust Abatement shall include full compensation for all direct and indirect costs incurred under this section.

This payment will be made on a basis of the percentage of work completed on the entire project.

SECTION 28 – HYDROSEEDING – NOT USED

SECTION 29 – STORMWATER AND NON-STORMWATER POLLUTION CONTROL

29.1 Description - This section covers the contract item Stormwater and Non-Stormwater Pollution Control. The contract item Stormwater and Non-Stormwater Pollution Control shall include preparing, obtaining approval of, amending and implementing Contractor's Pollution Prevention Plan (PPP). Non-Stormwater Discharge or Dewatering shall include compliance with Santa Ana Regional Water Quality Control Board Order No. R8-2015-0004.

29.2 General - The objectives of the PPP shall be to identify all pollution sources associated with Contractor's construction activities that may adversely affect the quality of stormwater discharges and receiving waters; to identify all non-stormwater discharges; to identify, construct, implement, and maintain water pollution control best management practices, hereafter referred to as "BMPs"; to reduce to the maximum extent practicable pollutants in both stormwater and authorized non-stormwater discharges from the construction site during construction; and to develop a maintenance schedule for BMPs after construction is completed under this contract.

In the event the District incurs any Administrative Civil Liability or Mandatory Minimum Penalty (fine) imposed by the California Regional Water Quality Control Board, as a result of Contractor's failure to fully implement the provisions of this section and permit requirements, "Stormwater and Non-Stormwater Pollution Control", the Engineer may, in the exercise of his sole judgment and discretion, withhold from payments otherwise due Contractor a sufficient amount to cover the Civil Liability or Mandatory Minimum Penalty. Liability for "Negligent Violations" may be in an amount up to \$50,000 per day per deemed occurrence while "Knowing Violations" can result in fines as high as \$250,000 and imprisonment.

29.3 Pollution Prevention Plan Preparation (PPP) and Approval - The Contractor shall prepare and obtain approval of a PPP as part of the Stormwater and Non-Stormwater Pollution Control work for this contract.

Within five (5) working days after the award of the contract, the Contractor shall submit two (2) hard copies of the PPP and one (1) pdf copy to the Engineer for review and approval. The Contractor shall allow ten (10) working days for the Engineer to review the PPP. If revisions are required as determined by the Engineer, the Contractor shall revise and resubmit the PPP within three (3) working days of receipt of the Engineer's comments and shall allow ten (10) working days for the Engineer to review the revisions. The Contractor shall submit four (4) hard copies and one (1) pdf copy of the approved PPP to the Engineer prior to the pre-construction meeting. **The Contractor must have an approved PPP prior to the pre-construction meeting.**

The PPP shall consist of a construction site map that identifies site specific BMPs to be implemented during and after construction to minimize the potential pollution of stormwater runoff and receiving waters. The identified BMPs shall be practices designed to prevent or minimize the discharge of pollutants from the construction site and Contractor's construction activities.

The PPP shall incorporate BMPs in each of the following categories:

1. Soil stabilization practices
2. Sediment control practices
3. Sediment tracking control practices
4. Wind erosion control practices
5. Non-stormwater management, and waste management and disposal control practices

The Contractor shall refer to and implement BMPs consistent with the Caltrans Construction Site BMP Details, Drawings, and Fact Sheets available at:

<https://dot.ca.gov/programs/construction/storm-water-and-water-pollution-control>

Specific objectives and minimum requirements for each category of BMPs contained in the Caltrans Handbooks. The Contractor shall consider the objectives and minimum requirements presented in the Caltrans Handbooks for each of the above categories. When minimum requirements are listed for any category, the Contractor shall incorporate one or more of the listed minimum BMPs required into the PPP and implement them on the project to meet the pollution control objectives for the category. In addition, the Contractor shall consider other BMPs presented in the Caltrans Handbooks to supplement the minimum BMPs required when necessary to meet the objectives of the PPP.

The Contractor shall not assume that the minimum BMPs required for each category presented in the Caltrans Handbooks are adequate to meet the pollution control objectives. The

Contractor may use other effective BMPs, as approved by the Engineer, in addition to the minimum BMPs required in the Caltrans Handbooks to achieve the pollution control objectives.

29.4 PPP Amendments - The Contractor shall amend the PPP whenever there is a change in Contractor's construction activities or operations which may result in the discharge of pollutants from the site to surface waters, groundwaters, municipal storm drain systems or when deemed necessary by the Engineer. The Contractor shall also amend the PPP if it is not effectively achieving the objectives of preventing or minimizing pollutants in stormwater discharges. Amendments shall show additional BMPs or revisions to Contractor's construction activities or operations (including any construction activities in areas not included in the initially approved PPP) which are required on the project to effectively control water pollution.

Amendments to the PPP shall be submitted for review and approval by the Engineer in the same manner specified for the initial approval of the PPP. The Contractor shall date and attach all approved amendments to the PPP. Upon approval of the amendment, the Contractor shall implement the additional BMPs, revised construction activities or operations as described therein.

29.5 PPP Implementation - Upon approval of the PPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting and maintaining the BMPs included in the PPP and any amendments thereto and for removing and disposing of temporary BMPs. Unless otherwise directed by the Engineer or specified in these Detailed Specifications, the Contractor's responsibility for PPP implementation and maintenance shall continue throughout any temporary suspension of work ordered in accordance with Section 6.05, TEMPORARY SUSPENSION OF THE WORK, of the General Provisions. Requirements for installation, construction, inspection, maintenance, removal and disposal of BMPs are specified in the Caltrans Handbooks and these Detailed Specifications. The Contractor shall implement the PPP in accordance with the Caltrans Handbooks and these Detailed Specifications.

The Engineer may order the suspension of construction operations if the Contractor fails to comply with the requirements of this section, "Stormwater and Non-Stormwater Pollution Control", as determined by the Engineer.

29.6 Non-Stormwater Discharge or Dewatering - **Groundwater is not anticipated on this project.** If groundwater is encountered during the project activities, the dewatering activity must be covered by the General Waste Discharge Requirements for Discharges to Surface Waters that Pose an Insignificant Threat to Water Quality (De Minimus Permit), Santa Ana Regional Water Quality Control Board Order No. R8-2015-0004. The Contractor shall comply with this Order, and notify and obtain approval from the Engineer fifteen (15) days prior to any non-stormwater discharging of groundwater dewatering. If an emergency or unforeseen dewatering activity that will discharge to Waters of the United States occurs, the Contractor shall contact the Engineer immediately.

Failure of the Contractor to fully comply with this requirement may result in the suspension of construction operations and liability for any associated monitoring, fines, penalties and remediation activities related to the discharge.

29.7 Payment - The contract lump sum price paid for contract item Stormwater and Non-Stormwater Pollution Control shall include full compensation for all direct and indirect costs incurred under this section. Payment will be made on a basis of the percentage of work completed on the entire project.

Non-Stormwater Discharge or Dewatering shall be paid for as extra directed work, if groundwater is encountered, and if, at the direction of the Engineer, a De Minimus Permit for discharge is required.

SECTION 30 AND SECTION 31 – NOT USED

APPENDIX "A"

SOUTH COAST AIR QUALITY
MANAGEMENT DISTRICT

RULE 403

(Adopted May 7, 1976) (Amended November 6, 1992)
(Amended July 9, 1993) (Amended February 14, 1997)
(Amended December 11, 1998)(Amended April 2, 2004)
(Amended June 3, 2005)

RULE 403. FUGITIVE DUST

(a) Purpose

The purpose of this Rule is to reduce the amount of particulate matter entrained in the ambient air as a result of anthropogenic (man-made) fugitive dust sources by requiring actions to prevent, reduce or mitigate fugitive dust emissions.

(b) Applicability

The provisions of this Rule shall apply to any activity or man-made condition capable of generating fugitive dust.

(c) Definitions

- (1) ACTIVE OPERATIONS means any source capable of generating fugitive dust, including, but not limited to, earth-moving activities, construction/demolition activities, disturbed surface area, or heavy- and light-duty vehicular movement.
- (2) AGGREGATE-RELATED PLANTS are defined as facilities that produce and / or mix sand and gravel and crushed stone.
- (3) AGRICULTURAL HANDBOOK means the region-specific guidance document that has been approved by the Governing Board or hereafter approved by the Executive Officer and the U.S. EPA. For the South Coast Air Basin, the Board-approved region-specific guidance document is the Rule 403 Agricultural Handbook dated December 1998. For the Coachella Valley, the Board-approved region-specific guidance document is the Rule 403 Coachella Valley Agricultural Handbook dated April 2, 2004.
- (4) ANEMOMETERS are devices used to measure wind speed and direction in accordance with the performance standards, and maintenance and calibration criteria as contained in the most recent Rule 403 Implementation Handbook.
- (5) BEST AVAILABLE CONTROL MEASURES means fugitive dust control actions that are set forth in Table 1 of this Rule.

- (6) BULK MATERIAL is sand, gravel, soil, aggregate material less than two inches in length or diameter, and other organic or inorganic particulate matter.
- (7) CEMENT MANUFACTURING FACILITY is any facility that has a cement kiln at the facility.
- (8) CHEMICAL STABILIZERS are any non-toxic chemical dust suppressant which must not be used if prohibited for use by the Regional Water Quality Control Boards, the California Air Resources Board, the U.S. Environmental Protection Agency (U.S. EPA), or any applicable law, rule or regulation. The chemical stabilizers shall meet any specifications, criteria, or tests required by any federal, state, or local water agency. Unless otherwise indicated, the use of a non-toxic chemical stabilizer shall be of sufficient concentration and application frequency to maintain a stabilized surface.
- (9) COMMERCIAL POULTRY RANCH means any building, structure, enclosure, or premises where more than 100 fowl are kept or maintained for the primary purpose of producing eggs or meat for sale or other distribution.
- (10) CONFINED ANIMAL FACILITY means a source or group of sources of air pollution at an agricultural source for the raising of 3,360 or more fowl or 50 or more animals, including but not limited to, any structure, building, installation, farm, corral, coop, feed storage area, milking parlor, or system for the collection, storage, or distribution of solid and liquid manure; if domesticated animals, including horses, sheep, goats, swine, beef cattle, rabbits, chickens, turkeys, or ducks are corralled, penned, or otherwise caused to remain in restricted areas for commercial agricultural purposes and feeding is by means other than grazing.
- (11) CONSTRUCTION/DEMOLITION ACTIVITIES means any on-site mechanical activities conducted in preparation of, or related to, the building, alteration, rehabilitation, demolition or improvement of property, including, but not limited to the following activities: grading, excavation, loading, crushing, cutting, planing, shaping or ground breaking.
- (12) CONTRACTOR means any person who has a contractual arrangement to conduct an active operation for another person.
- (13) DAIRY FARM is an operation on a property, or set of properties that are contiguous or separated only by a public right-of-way, that raises cows or

produces milk from cows for the purpose of making a profit or for a livelihood. Heifer and calf farms are dairy farms.

- (14) **DISTURBED SURFACE AREA** means a portion of the earth's surface which has been physically moved, uncovered, destabilized, or otherwise modified from its undisturbed natural soil condition, thereby increasing the potential for emission of fugitive dust. This definition excludes those areas which have:
- (A) been restored to a natural state, such that the vegetative ground cover and soil characteristics are similar to adjacent or nearby natural conditions;
 - (B) been paved or otherwise covered by a permanent structure; or
 - (C) sustained a vegetative ground cover of at least 70 percent of the native cover for a particular area for at least 30 days.
- (15) **DUST SUPPRESSANTS** are water, hygroscopic materials, or non-toxic chemical stabilizers used as a treatment material to reduce fugitive dust emissions.
- (16) **EARTH-MOVING ACTIVITIES** means the use of any equipment for any activity where soil is being moved or uncovered, and shall include, but not be limited to the following: grading, earth cutting and filling operations, loading or unloading of dirt or bulk materials, adding to or removing from open storage piles of bulk materials, landfill operations, weed abatement through disking, and soil mulching.
- (17) **DUST CONTROL SUPERVISOR** means a person with the authority to expeditiously employ sufficient dust mitigation measures to ensure compliance with all Rule 403 requirements at an active operation.
- (18) **FUGITIVE DUST** means any solid particulate matter that becomes airborne, other than that emitted from an exhaust stack, directly or indirectly as a result of the activities of any person.
- (19) **HIGH WIND CONDITIONS** means that instantaneous wind speeds exceed 25 miles per hour.
- (20) **INACTIVE DISTURBED SURFACE AREA** means any disturbed surface area upon which active operations have not occurred or are not expected to occur for a period of 20 consecutive days.
- (21) **LARGE OPERATIONS** means any active operations on property which contains 50 or more acres of disturbed surface area; or any earth-moving operation with a daily earth-moving or throughput volume of 3,850 cubic

meters (5,000 cubic yards) or more three times during the most recent 365-day period.

- (22) OPEN STORAGE PILE is any accumulation of bulk material, which is not fully enclosed, covered or chemically stabilized, and which attains a height of three feet or more and a total surface area of 150 or more square feet.
- (23) PARTICULATE MATTER means any material, except uncombined water, which exists in a finely divided form as a liquid or solid at standard conditions.
- (24) PAVED ROAD means a public or private improved street, highway, alley, public way, or easement that is covered by typical roadway materials, but excluding access roadways that connect a facility with a public paved roadway and are not open to through traffic. Public paved roads are those open to public access and that are owned by any federal, state, county, municipal or any other governmental or quasi-governmental agencies. Private paved roads are any paved roads not defined as public.
- (25) PM₁₀ means particulate matter with an aerodynamic diameter smaller than or equal to 10 microns as measured by the applicable State and Federal reference test methods.
- (26) PROPERTY LINE means the boundaries of an area in which either a person causing the emission or a person allowing the emission has the legal use or possession of the property. Where such property is divided into one or more sub-tenancies, the property line(s) shall refer to the boundaries dividing the areas of all sub-tenancies.
- (27) RULE 403 IMPLEMENTATION HANDBOOK means a guidance document that has been approved by the Governing Board on April 2, 2004 or hereafter approved by the Executive Officer and the U.S. EPA.
- (28) SERVICE ROADS are paved or unpaved roads that are used by one or more public agencies for inspection or maintenance of infrastructure and which are not typically used for construction-related activity.
- (29) SIMULTANEOUS SAMPLING means the operation of two PM₁₀ samplers in such a manner that one sampler is started within five minutes of the other, and each sampler is operated for a consecutive period which must be not less than 290 minutes and not more than 310 minutes.
- (30) SOUTH COAST AIR BASIN means the non-desert portions of Los Angeles, Riverside, and San Bernardino counties and all of Orange

County as defined in California Code of Regulations, Title 17, Section 60104. The area is bounded on the west by the Pacific Ocean, on the north and east by the San Gabriel, San Bernardino, and San Jacinto Mountains, and on the south by the San Diego county line.

- (31) STABILIZED SURFACE means any previously disturbed surface area or open storage pile which, through the application of dust suppressants, shows visual or other evidence of surface crusting and is resistant to wind-driven fugitive dust and is demonstrated to be stabilized. Stabilization can be demonstrated by one or more of the applicable test methods contained in the Rule 403 Implementation Handbook.
 - (32) TRACK-OUT means any bulk material that adheres to and agglomerates on the exterior surface of motor vehicles, haul trucks, and equipment (including tires) that have been released onto a paved road and can be removed by a vacuum sweeper or a broom sweeper under normal operating conditions.
 - (33) TYPICAL ROADWAY MATERIALS means concrete, asphaltic concrete, recycled asphalt, asphalt, or any other material of equivalent performance as determined by the Executive Officer, and the U.S. EPA.
 - (34) UNPAVED ROADS means any unsealed or unpaved roads, equipment paths, or travel ways that are not covered by typical roadway materials. Public unpaved roads are any unpaved roadway owned by federal, state, county, municipal or other governmental or quasi-governmental agencies. Private unpaved roads are all other unpaved roadways not defined as public.
 - (35) VISIBLE ROADWAY DUST means any sand, soil, dirt, or other solid particulate matter which is visible upon paved road surfaces and which can be removed by a vacuum sweeper or a broom sweeper under normal operating conditions.
 - (36) WIND-DRIVEN FUGITIVE DUST means visible emissions from any disturbed surface area which is generated by wind action alone.
 - (37) WIND GUST is the maximum instantaneous wind speed as measured by an anemometer.
- (d) Requirements
- (1) No person shall cause or allow the emissions of fugitive dust from any active operation, open storage pile, or disturbed surface area such that:

- (A) the dust remains visible in the atmosphere beyond the property line of the emission source; or
 - (B) the dust emission exceeds 20 percent opacity (as determined by the appropriate test method included in the Rule 403 Implementation Handbook), if the dust emission is the result of movement of a motorized vehicle.
- (2) No person shall conduct active operations without utilizing the applicable best available control measures included in Table 1 of this Rule to minimize fugitive dust emissions from each fugitive dust source type within the active operation.
- (3) No person shall cause or allow PM₁₀ levels to exceed 50 micrograms per cubic meter when determined, by simultaneous sampling, as the difference between upwind and downwind samples collected on high-volume particulate matter samplers or other U.S. EPA-approved equivalent method for PM₁₀ monitoring. If sampling is conducted, samplers shall be:
- (A) Operated, maintained, and calibrated in accordance with 40 Code of Federal Regulations (CFR), Part 50, Appendix J, or appropriate U.S. EPA-published documents for U.S. EPA-approved equivalent method(s) for PM₁₀.
 - (B) Reasonably placed upwind and downwind of key activity areas and as close to the property line as feasible, such that other sources of fugitive dust between the sampler and the property line are minimized.
- (4) No person shall allow track-out to extend 25 feet or more in cumulative length from the point of origin from an active operation. Notwithstanding the preceding, all track-out from an active operation shall be removed at the conclusion of each workday or evening shift.
- (5) No person shall conduct an active operation with a disturbed surface area of five or more acres, or with a daily import or export of 100 cubic yards or more of bulk material without utilizing at least one of the measures listed in subparagraphs (d)(5)(A) through (d)(5)(E) at each vehicle egress from the site to a paved public road.
- (A) Install a pad consisting of washed gravel (minimum-size: one inch) maintained in a clean condition to a depth of at least six inches and extending at least 30 feet wide and at least 50 feet long.

- (B) Pave the surface extending at least 100 feet and at least 20 feet wide.
 - (C) Utilize a wheel shaker/wheel spreading device consisting of raised dividers (rails, pipe, or grates) at least 24 feet long and 10 feet wide to remove bulk material from tires and vehicle undercarriages before vehicles exit the site.
 - (D) Install and utilize a wheel washing system to remove bulk material from tires and vehicle undercarriages before vehicles exit the site.
 - (E) Any other control measures approved by the Executive Officer and the U.S. EPA as equivalent to the actions specified in subparagraphs (d)(5)(A) through (d)(5)(D).
- (6) Beginning January 1, 2006, any person who operates or authorizes the operation of a confined animal facility subject to this Rule shall implement the applicable conservation management practices specified in Table 4 of this Rule.
- (e) Additional Requirements for Large Operations
- (1) Any person who conducts or authorizes the conducting of a large operation subject to this Rule shall implement the applicable actions specified in Table 2 of this Rule at all times and shall implement the applicable actions specified in Table 3 of this Rule when the applicable performance standards can not be met through use of Table 2 actions; and shall:
 - (A) submit a fully executed Large Operation Notification (Form 403 N) to the Executive Officer within 7 days of qualifying as a large operation;
 - (B) include, as part of the notification, the name(s), address(es), and phone number(s) of the person(s) responsible for the submittal, and a description of the operation(s), including a map depicting the location of the site;
 - (C) maintain daily records to document the specific dust control actions taken, maintain such records for a period of not less than three years; and make such records available to the Executive Officer upon request;

- (D) install and maintain project signage with project contact signage that meets the minimum standards of the Rule 403 Implementation Handbook, prior to initiating any earthmoving activities;
 - (E) identify a dust control supervisor that:
 - (i) is employed by or contracted with the property owner or developer;
 - (ii) is on the site or available on-site within 30 minutes during working hours;
 - (iii) has the authority to expeditiously employ sufficient dust mitigation measures to ensure compliance with all Rule requirements;
 - (iv) has completed the AQMD Fugitive Dust Control Class and has been issued a valid Certificate of Completion for the class; and
 - (F) notify the Executive Officer in writing within 30 days after the site no longer qualifies as a large operation as defined by paragraph (c)(18).
- (2) Any Large Operation Notification submitted to the Executive Officer or AQMD-approved dust control plan shall be valid for a period of one year from the date of written acceptance by the Executive Officer. Any Large Operation Notification accepted pursuant to paragraph (e)(1), excluding those submitted by aggregate-related plants and cement manufacturing facilities must be resubmitted annually by the person who conducts or authorizes the conducting of a large operation, at least 30 days prior to the expiration date, or the submittal shall no longer be valid as of the expiration date. If all fugitive dust sources and corresponding control measures or special circumstances remain identical to those identified in the previously accepted submittal or in an AQMD-approved dust control plan, the resubmittal may be a simple statement of no-change (Form 403NC).
- (f) **Compliance Schedule**
The newly amended provisions of this Rule shall become effective upon adoption. Pursuant to subdivision (e), any existing site that qualifies as a large operation will have 60 days from the date of Rule adoption to comply with the notification and recordkeeping requirements for large operations. Any Large Operation

Notification or AQMD-approved dust control plan which has been accepted prior to the date of adoption of these amendments shall remain in effect and the Large Operation Notification or AQMD-approved dust control plan annual resubmittal date shall be one year from adoption of this Rule amendment.

(g) Exemptions

- (1) The provisions of this Rule shall not apply to:
 - (A) Dairy farms.
 - (B) Confined animal facilities provided that the combined disturbed surface area within one continuous property line is one acre or less.
 - (C) Agricultural vegetative crop operations provided that the combined disturbed surface area within one continuous property line and not separated by a paved public road is 10 acres or less.
 - (D) Agricultural vegetative crop operations within the South Coast Air Basin, whose combined disturbed surface area includes more than 10 acres provided that the person responsible for such operations:
 - (i) voluntarily implements the conservation management practices contained in the Rule 403 Agricultural Handbook;
 - (ii) completes and maintains the self-monitoring form documenting sufficient conservation management practices, as described in the Rule 403 Agricultural Handbook; and
 - (iii) makes the completed self-monitoring form available to the Executive Officer upon request.
 - (E) Agricultural vegetative crop operations outside the South Coast Air Basin whose combined disturbed surface area includes more than 10 acres provided that the person responsible for such operations:
 - (i) voluntarily implements the conservation management practices contained in the Rule 403 Coachella Valley Agricultural Handbook; and
 - (ii) completes and maintains the self-monitoring form documenting sufficient conservation management practices, as described in the Rule 403 Coachella Valley Agricultural Handbook; and
 - (iii) makes the completed self-monitoring form available to the Executive Officer upon request.

- (F) Active operations conducted during emergency life-threatening situations, or in conjunction with any officially declared disaster or state of emergency.
 - (G) Active operations conducted by essential service utilities to provide electricity, natural gas, telephone, water and sewer during periods of service outages and emergency disruptions.
 - (H) Any contractor subsequent to the time the contract ends, provided that such contractor implemented the required control measures during the contractual period.
 - (I) Any grading contractor, for a phase of active operations, subsequent to the contractual completion of that phase of earth-moving activities, provided that the required control measures have been implemented during the entire phase of earth-moving activities, through and including five days after the final grading inspection.
 - (J) Weed abatement operations ordered by a county agricultural commissioner or any state, county, or municipal fire department, provided that:
 - (i) mowing, cutting or other similar process is used which maintains weed stubble at least three inches above the soil; and
 - (ii) any discing or similar operation which cuts into and disturbs the soil, where watering is used prior to initiation of these activities, and a determination is made by the agency issuing the weed abatement order that, due to fire hazard conditions, rocks, or other physical obstructions, it is not practical to meet the conditions specified in clause (g)(1)(H)(i). The provisions this clause shall not exempt the owner of any property from stabilizing, in accordance with paragraph (d)(2), disturbed surface areas which have been created as a result of the weed abatement actions.
 - (K) sandblasting operations.
- (2) The provisions of paragraphs (d)(1) and (d)(3) shall not apply:
- (A) When wind gusts exceed 25 miles per hour, provided that:

- (i) The required Table 3 contingency measures in this Rule are implemented for each applicable fugitive dust source type, and;
 - (ii) records are maintained in accordance with subparagraph (e)(1)(C).
- (B) To unpaved roads, provided such roads:
- (i) are used solely for the maintenance of wind-generating equipment; or
 - (ii) are unpaved public alleys as defined in Rule 1186; or
 - (iii) are service roads that meet all of the following criteria:
 - (a) are less than 50 feet in width at all points along the road;
 - (b) are within 25 feet of the property line; and
 - (c) have a traffic volume less than 20 vehicle-trips per day.
- (C) To any active operation, open storage pile, or disturbed surface area for which necessary fugitive dust preventive or mitigative actions are in conflict with the federal Endangered Species Act, as determined in writing by the State or federal agency responsible for making such determinations.
- (3) The provisions of (d)(2) shall not apply to any aggregate-related plant or cement manufacturing facility that implements the applicable actions specified in Table 2 of this Rule at all times and shall implement the applicable actions specified in Table 3 of this Rule when the applicable performance standards of paragraphs (d)(1) and (d)(3) can not be met through use of Table 2 actions.
- (4) The provisions of paragraphs (d)(1), (d)(2), and (d)(3) shall not apply to:
- (A) Blasting operations which have been permitted by the California Division of Industrial Safety; and
 - (B) Motion picture, television, and video production activities when dust emissions are required for visual effects. In order to obtain this exemption, the Executive Officer must receive notification in writing at least 72 hours in advance of any such activity and no nuisance results from such activity.
- (5) The provisions of paragraph (d)(3) shall not apply if the dust control actions, as specified in Table 2, are implemented on a routine basis for

each applicable fugitive dust source type. To qualify for this exemption, a person must maintain records in accordance with subparagraph (e)(1)(C).

- (6) The provisions of paragraph (d)(4) shall not apply to earth coverings of public paved roadways where such coverings are approved by a local government agency for the protection of the roadway, and where such coverings are used as roadway crossings for haul vehicles provided that such roadway is closed to through traffic and visible roadway dust is removed within one day following the cessation of activities.
- (7) The provisions of subdivision (e) shall not apply to:
 - (A) officially-designated public parks and recreational areas, including national parks, national monuments, national forests, state parks, state recreational areas, and county regional parks.
 - (B) any large operation which is required to submit a dust control plan to any city or county government which has adopted a District-approved dust control ordinance.
 - (C) any large operation subject to Rule 1158, which has an approved dust control plan pursuant to Rule 1158, provided that all sources of fugitive dust are included in the Rule 1158 plan.
- (8) The provisions of subparagraph (e)(1)(A) through (e)(1)(C) shall not apply to any large operation with an AQMD-approved fugitive dust control plan provided that there is no change to the sources and controls as identified in the AQMD-approved fugitive dust control plan.

(h) Fees

Any person conducting active operations for which the Executive Officer conducts upwind/downwind monitoring for PM₁₀ pursuant to paragraph (d)(3) shall be assessed applicable Ambient Air Analysis Fees pursuant to Rule 304.1. Applicable fees shall be waived for any facility which is exempted from paragraph (d)(3) or meets the requirements of paragraph (d)(3).

TABLE 1
BEST AVAILABLE CONTROL MEASURES
 (Applicable to All Construction Activity Sources)

Source Category	Control Measure	Guidance
Backfilling	01-1 Stabilize backfill material when not actively handling; and	✓ Mix backfill soil with water prior to moving
	01-2 Stabilize backfill material during handling; and	✓ Dedicate water truck or high capacity hose to backfilling equipment
	01-3 Stabilize soil at completion of activity.	✓ Empty loader bucket slowly so that no dust plumes are generated ✓ Minimize drop height from loader bucket
Clearing and grubbing	02-1 Maintain stability of soil through pre-watering of site prior to clearing and grubbing; and	✓ Maintain live perennial vegetation where possible
	02-2 Stabilize soil during clearing and grubbing activities; and	✓ Apply water in sufficient quantity to prevent generation of dust plumes
	02-3 Stabilize soil immediately after clearing and grubbing activities.	
Clearing forms	03-1 Use water spray to clear forms; or	✓ Use of high pressure air to clear forms may cause exceedance of Rule requirements
	03-2 Use sweeping and water spray to clear forms; or	
	03-3 Use vacuum system to clear forms.	
Crushing	04-1 Stabilize surface soils prior to operation of support equipment; and	✓ Follow permit conditions for crushing equipment
	04-2 Stabilize material after crushing.	✓ Pre-water material prior to loading into crusher ✓ Monitor crusher emissions opacity ✓ Apply water to crushed material to prevent dust plumes

TABLE 1
BEST AVAILABLE CONTROL MEASURES
 (Applicable to All Construction Activity Sources)

Source Category	Control Measure	Guidance
Cut and fill	05-1 Pre-water soils prior to cut and fill activities; and 05-2 Stabilize soil during and after cut and fill activities.	✓ For large sites, pre-water with sprinklers or water trucks and allow time for penetration ✓ Use water trucks/pulls to water soils to depth of cut prior to subsequent cuts
Demolition – mechanical/manual	06-1 Stabilize wind erodible surfaces to reduce dust; and 06-2 Stabilize surface soil where support equipment and vehicles will operate; and 06-3 Stabilize loose soil and demolition debris; and 06-4 Comply with AQMD Rule 1403.	✓ Apply water in sufficient quantities to prevent the generation of visible dust plumes
Disturbed soil	07-1 Stabilize disturbed soil throughout the construction site; and 07-2 Stabilize disturbed soil between structures	✓ Limit vehicular traffic and disturbances on soils where possible ✓ If interior block walls are planned, install as early as possible ✓ Apply water or a stabilizing agent in sufficient quantities to prevent the generation of visible dust plumes
Earth-moving activities	08-1 Pre-apply water to depth of proposed cuts; and 08-2 Re-apply water as necessary to maintain soils in a damp condition and to ensure that visible emissions do not exceed 100 feet in any direction; and 08-3 Stabilize soils once earth-moving activities are complete.	✓ Grade each project phase separately, timed to coincide with construction phase ✓ Upwind fencing can prevent material movement on site ✓ Apply water or a stabilizing agent in sufficient quantities to prevent the generation of visible dust plumes

TABLE 1
BEST AVAILABLE CONTROL MEASURES
 (Applicable to All Construction Activity Sources)

Source Category	Control Measure	Guidance
Importing/exporting of bulk materials	09-1 Stabilize material while loading to reduce fugitive dust emissions; and 09-2 Maintain at least six inches of freeboard on haul vehicles; and 09-3 Stabilize material while transporting to reduce fugitive dust emissions; and 09-4 Stabilize material while unloading to reduce fugitive dust emissions; and 09-5 Comply with Vehicle Code Section 23114.	✓ Use tarps or other suitable enclosures on haul trucks ✓ Check belly-dump truck seals regularly and remove any trapped rocks to prevent spillage ✓ Comply with track-out prevention/mitigation requirements ✓ Provide water while loading and unloading to reduce visible dust plumes
Landscaping	10-1 Stabilize soils, materials, slopes	✓ Apply water to materials to stabilize ✓ Maintain materials in a crusted condition ✓ Maintain effective cover over materials ✓ Stabilize sloping surfaces using soil binders until vegetation or ground cover can effectively stabilize the slopes ✓ Hydroseed prior to rain season
Road shoulder maintenance	11-1 Apply water to unpaved shoulders prior to clearing; and 11-2 Apply chemical dust suppressants and/or washed gravel to maintain a stabilized surface after completing road shoulder maintenance.	✓ Installation of curbing and/or paving of road shoulders can reduce recurring maintenance costs ✓ Use of chemical dust suppressants can inhibit vegetation growth and reduce future road shoulder maintenance costs

TABLE 1
BEST AVAILABLE CONTROL MEASURES
(Applicable to All Construction Activity Sources)

Source Category	Control Measure	Guidance
Screening	12-1 Pre-water material prior to screening; and 12-2 Limit fugitive dust emissions to opacity and plume length standards; and 12-3 Stabilize material immediately after screening.	<ul style="list-style-type: none"> ✓ Dedicate water truck or high capacity hose to screening operation ✓ Drop material through the screen slowly and minimize drop height ✓ Install wind barrier with a porosity of no more than 50% upwind of screen to the height of the drop point
Staging areas	13-1 Stabilize staging areas during use; and 13-2 Stabilize staging area soils at project completion.	<ul style="list-style-type: none"> ✓ Limit size of staging area ✓ Limit vehicle speeds to 15 miles per hour ✓ Limit number and size of staging area entrances/exists
Stockpiles/ Bulk Material Handling	14-1 Stabilize stockpiled materials. 14-2 Stockpiles within 100 yards of off-site occupied buildings must not be greater than eight feet in height; or must have a road bladed to the top to allow water truck access or must have an operational water irrigation system that is capable of complete stockpile coverage.	<ul style="list-style-type: none"> ✓ Add or remove material from the downwind portion of the storage pile ✓ Maintain storage piles to avoid steep sides or faces

TABLE 1
BEST AVAILABLE CONTROL MEASURES
 (Applicable to All Construction Activity Sources)

Source Category	Control Measure	Guidance
Traffic areas for construction activities	15-1 Stabilize all off-road traffic and parking areas; and 15-2 Stabilize all haul routes; and 15-3 Direct construction traffic over established haul routes.	✓ Apply gravel/paving to all haul routes as soon as possible to all future roadway areas ✓ Barriers can be used to ensure vehicles are only used on established parking areas/haul routes
Trenching	16-1 Stabilize surface soils where trencher or excavator and support equipment will operate; and 16-2 Stabilize soils at the completion of trenching activities.	✓ Pre-watering of soils prior to trenching is an effective preventive measure. For deep trenching activities, pre-trench to 18 inches soak soils via the pre-trench and resuming trenching ✓ Washing mud and soils from equipment at the conclusion of trenching activities can prevent crusting and drying of soil on equipment
Truck loading	17-1 Pre-water material prior to loading; and 17-2 Ensure that freeboard exceeds six inches (CVC 23114)	✓ Empty loader bucket such that no visible dust plumes are created ✓ Ensure that the loader bucket is close to the truck to minimize drop height while loading
Turf Overseeding	18-1 Apply sufficient water immediately prior to conducting turf vacuuming activities to meet opacity and plume length standards; and 18-2 Cover haul vehicles prior to exiting the site.	✓ Haul waste material immediately off-site

TABLE 1
BEST AVAILABLE CONTROL MEASURES
 (Applicable to All Construction Activity Sources)

Source Category	Control Measure	Guidance
Unpaved roads/parking lots	19-1 Stabilize soils to meet the applicable performance standards; and 19-2 Limit vehicular travel to established unpaved roads (haul routes) and unpaved parking lots.	✓ Restricting vehicular access to established unpaved travel paths and parking lots can reduce stabilization requirements
Vacant land	20-1 In instances where vacant lots are 0.10 acre or larger and have a cumulative area of 500 square feet or more that are driven over and/or used by motor vehicles and/or off-road vehicles, prevent motor vehicle and/or off-road vehicle trespassing, parking and/or access by installing barriers, curbs, fences, gates, posts, signs, shrubs, trees or other effective control measures.	

Table 2
DUST CONTROL MEASURES FOR LARGE OPERATIONS

FUGITIVE DUST SOURCE CATEGORY	CONTROL ACTIONS
Earth-moving (except construction cutting and filling areas, and mining operations)	<p>(1a) Maintain soil moisture content at a minimum of 12 percent, as determined by ASTM method D-2216, or other equivalent method approved by the Executive Officer, the California Air Resources Board, and the U.S. EPA. Two soil moisture evaluations must be conducted during the first three hours of active operations during a calendar day, and two such evaluations each subsequent four-hour period of active operations; OR</p> <p>(1a-1) For any earth-moving which is more than 100 feet from all property lines, conduct watering as necessary to prevent visible dust emissions from exceeding 100 feet in length in any direction.</p>
Earth-moving: Construction fill areas:	<p>(1b) Maintain soil moisture content at a minimum of 12 percent, as determined by ASTM method D-2216, or other equivalent method approved by the Executive Officer, the California Air Resources Board, and the U.S. EPA. For areas which have an optimum moisture content for compaction of less than 12 percent, as determined by ASTM Method 1557 or other equivalent method approved by the Executive Officer and the California Air Resources Board and the U.S. EPA, complete the compaction process as expeditiously as possible after achieving at least 70 percent of the optimum soil moisture content. Two soil moisture evaluations must be conducted during the first three hours of active operations during a calendar day, and two such evaluations during each subsequent four-hour period of active operations.</p>

Table 2 (Continued)

FUGITIVE DUST SOURCE CATEGORY	CONTROL ACTIONS
Earth-moving: Construction cut areas and mining operations:	(1c) Conduct watering as necessary to prevent visible emissions from extending more than 100 feet beyond the active cut or mining area unless the area is inaccessible to watering vehicles due to slope conditions or other safety factors.
Disturbed surface areas (except completed grading areas)	(2a/b) Apply dust suppression in sufficient quantity and frequency to maintain a stabilized surface. Any areas which cannot be stabilized, as evidenced by wind driven fugitive dust must have an application of water at least twice per day to at least 80 percent of the unstabilized area.
Disturbed surface areas: Completed grading areas	(2c) Apply chemical stabilizers within five working days of grading completion; OR (2d) Take actions (3a) or (3c) specified for inactive disturbed surface areas.
Inactive disturbed surface areas	(3a) Apply water to at least 80 percent of all inactive disturbed surface areas on a daily basis when there is evidence of wind driven fugitive dust, excluding any areas which are inaccessible to watering vehicles due to excessive slope or other safety conditions; OR (3b) Apply dust suppressants in sufficient quantity and frequency to maintain a stabilized surface; OR (3c) Establish a vegetative ground cover within 21 days after active operations have ceased. Ground cover must be of sufficient density to expose less than 30 percent of unstabilized ground within 90 days of planting, and at all times thereafter; OR (3d) Utilize any combination of control actions (3a), (3b), and (3c) such that, in total, these actions apply to all inactive disturbed surface areas.

Table 2 (Continued)

FUGITIVE DUST SOURCE CATEGORY	CONTROL ACTIONS
Unpaved Roads	<p>(4a) Water all roads used for any vehicular traffic at least once per every two hours of active operations [3 times per normal 8 hour work day]; OR</p> <p>(4b) Water all roads used for any vehicular traffic once daily and restrict vehicle speeds to 15 miles per hour; OR</p> <p>(4c) Apply a chemical stabilizer to all unpaved road surfaces in sufficient quantity and frequency to maintain a stabilized surface.</p>
Open storage piles	<p>(5a) Apply chemical stabilizers; OR</p> <p>(5b) Apply water to at least 80 percent of the surface area of all open storage piles on a daily basis when there is evidence of wind driven fugitive dust; OR</p> <p>(5c) Install temporary coverings; OR</p> <p>(5d) Install a three-sided enclosure with walls with no more than 50 percent porosity which extend, at a minimum, to the top of the pile. This option may only be used at aggregate-related plants or at cement manufacturing facilities.</p>
All Categories	<p>(6a) Any other control measures approved by the Executive Officer and the U.S. EPA as equivalent to the methods specified in Table 2 may be used.</p>

**TABLE 3
CONTINGENCY CONTROL MEASURES FOR LARGE OPERATIONS**

FUGITIVE DUST SOURCE CATEGORY	CONTROL MEASURES
Earth-moving	(1A) Cease all active operations; OR (2A) Apply water to soil not more than 15 minutes prior to moving such soil.
Disturbed surface areas	(0B) On the last day of active operations prior to a weekend, holiday, or any other period when active operations will not occur for not more than four consecutive days: apply water with a mixture of chemical stabilizer diluted to not less than 1/20 of the concentration required to maintain a stabilized surface for a period of six months; OR (1B) Apply chemical stabilizers prior to wind event; OR (2B) Apply water to all unstabilized disturbed areas 3 times per day. If there is any evidence of wind driven fugitive dust, watering frequency is increased to a minimum of four times per day; OR (3B) Take the actions specified in Table 2, Item (3c); OR (4B) Utilize any combination of control actions (1B), (2B), and (3B) such that, in total, these actions apply to all disturbed surface areas.
Unpaved roads	(1C) Apply chemical stabilizers prior to wind event; OR (2C) Apply water twice per hour during active operation; OR (3C) Stop all vehicular traffic.
Open storage piles	(1D) Apply water twice per hour; OR (2D) Install temporary coverings.
Paved road track-out	(1E) Cover all haul vehicles; OR (2E) Comply with the vehicle freeboard requirements of Section 23114 of the California Vehicle Code for both public and private roads.
All Categories	(1F) Any other control measures approved by the Executive Officer and the U.S. EPA as equivalent to the methods specified in Table 3 may be used.

Table 4
(Conservation Management Practices for Confined Animal Facilities)

SOURCE CATEGORY	CONSERVATION MANAGEMENT PRACTICES
Manure Handling (Only applicable to Commercial Poultry Ranches)	(1a) Cover manure prior to removing material off-site; AND (1b) Spread the manure before 11:00 AM and when wind conditions are less than 25 miles per hour; AND (1c) Utilize coning and drying manure management by removing manure at laying hen houses at least twice per year and maintain a base of no less than 6 inches of dry manure after clean out; or in lieu of complying with conservation management practice (1c), comply with conservation management practice (1d). (1d) Utilize frequent manure removal by removing the manure from laying hen houses at least every seven days and immediately thin bed dry the material.
Feedstock Handling	(2a) Utilize a sock or boot on the feed truck auger when filling feed storage bins.
Disturbed Surfaces	(3a) Maintain at least 70 percent vegetative cover on vacant portions of the facility; OR (3b) Utilize conservation tillage practices to manage the amount, orientation and distribution of crop and other plant residues on the soil surface year-round, while growing crops (if applicable) in narrow slots or tilled strips; OR (3c) Apply dust suppressants in sufficient concentrations and frequencies to maintain a stabilized surface.
Unpaved Roads	(4a) Restrict access to private unpaved roads either through signage or physical access restrictions and control vehicular speeds to no more than 15 miles per hour through worker notifications, signage, or any other necessary means; OR (4b) Cover frequently traveled unpaved roads with low silt content material (i.e., asphalt, concrete, recycled road base, or gravel to a minimum depth of four inches); OR (4c) Treat unpaved roads with water, mulch, chemical dust suppressants or other cover to maintain a stabilized surface.
Equipment Parking Areas	(5a) Apply dust suppressants in sufficient quantity and frequency to maintain a stabilized surface; OR (5b) Apply material with low silt content (i.e., asphalt, concrete, recycled road base, or gravel to a depth of four inches).

APPENDIX "B"

PROJECT SIGNS

8'-0"

6'-0"
1'-0"
1'-3"
1'-9"
2'-0"

RIVERSIDE COUNTY FLOOD CONTROL (1)
AND
WATER CONSERVATION DISTRICT

JURUPA-PYRITE MDP LINE A-2, STAGE 1 (2)

TOTAL CONSTRUCTION COST: \$ * (3)
FUNDED BY RIVERSIDE COUNTY FLOOD CONTROL AND
WATER CONSERVATION DISTRICT (4)

START DATE: * (4) APPROX. COMPLETION DATE: *

ENGINEER:


JASON E. UHLEY (5)
GENERAL MANAGER-CHIEF ENGINEER
RIVERSIDE COUNTY FLOOD CONTROL
AND WATER CONSERVATION DISTRICT
RIVERSIDE, CALIFORNIA
(951) 955-1200

(4) CONTRACTOR: *

3/4" CDX GRADE
PLYWOOD

LETTER SCHEDULE

	<u>SIZE</u>	<u>COLOR</u>
(1)	2"	BLACK
(2)	4"	ROYAL
(3)	3"	ROYAL
(4)	2"	ROYAL
(5)	2"	BLACK



6x6 POSTS SHALL
BE BURIED 3' MINIMUM
WITH 5' FROM GROUND
TO BOTTOM OF SIGN

NOTES:

1. MINIMUM SPACING BETWEEN LINES 1".
2. * -INFO. FURNISHED BY ENGINEER
3. ALL LETTERS FILLED AND CENTERED
4. THE STRIPES ARE GOLD AND BLACK ON WHITE BACKGROUND.

APPENDIX "B" PROJECT SIGN

**ADDITIONAL ITEMS FILED
WITH
THE CLERK OF THE
BOARD**